

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐
Sidetrack ☐

Document Number:

400210675

PluggingBond SuretyID

20040060

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: Mary Pobuda Phone: (303)312-8511 Fax: (303)291-0420

Email: mpobuda@billbarrettcorp.com

7. Well Name: Kaufman Well Number: 21B-25-692

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7394

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 25 Twp: 6S Rng: 92W Meridian: 6

Latitude: 39.502456 Longitude: -107.618364

Footage at Surface: 1109 feet FNL 1804 feet FWL

11. Field Name: MAMM CREEK Field Number: 52500

12. Ground Elevation: 5845 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/03/2010 PDOP Reading: 6.0 Instrument Operator's Name: JAMES KALMON

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
820 FNL 1977 FWL 820 FNL 1977 FWL
Sec: 25 Twp: 6S Rng: 92W Sec: 25 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 865 ft

18. Distance to nearest property line: 486 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 327 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	191-10	640	ALL
WILLIMAS FORK	WMFK	191-8	640	ALL

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attached lease map

25. Distance to Nearest Mineral Lease Line: 2936 ft

26. Total Acres in Lease: 2125

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAP & BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	14	36	0	40		40	0
SURF	12+1/4	9+5/8	36	0	738	240	738	0
1ST	7+7/8	4+1/2	11.6	0	7,394	780	7,394	2,960

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Mary Pobuda

Title: Permit Analyst Date: 10/4/2011 Email: mpobuda@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin

Director of COGCC Date: 11/7/2011

API NUMBER

05 045 21141 00

Permit Number: _____ Expiration Date: 11/6/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY – PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDER NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010) -- IS REQUIRED. SEE ATTACHED NOTICE.

5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 570 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400210675	FORM 2 SUBMITTED
400210678	WELL LOCATION PLAT
400210679	DEVIATED DRILLING PLAN
400210680	LEASE MAP
400210681	SURFACE AGRMT/SURETY

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	LGD/pub. comm. waived. Final comprehensive review status--passed.	11/7/2011 11:01:53 AM
Permit	ready to approve in permitting when 2A passes.	10/21/2011 9:17:13 AM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)