



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199659

| | | | |
|---|------------------------------|-----------------------|------------------------|
| Date <u>6/6/11</u> | Well Owner <u>Kerr McGee</u> | Well No. <u>41-26</u> | Lease <u>Barclay</u> |
| County <u>Weld</u> | State <u>Colorado</u> | | |
| Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u> | | | |
| Address <u>1999 Broadway, Suite 3700 (Xtreme #14)</u> | | | |
| City, State Zip <u>Denver, Colorado 80202</u> | | | |
| Type of Job | Depth | FL | <u>1133</u> |
| <u>Surface</u> <u>8 5/8" 156-24"</u> | Bottom of Surface | FL | <u>1128</u> |
| Plug | Plug Landed @ <u>1084</u> | FL | Time On <u>01:30</u> |
| Production | Pipe Landed @ <u>1128</u> | FL | Plug Down <u>03:45</u> |

| Description | Qty. | Meas. | Unit Price | Amount |
|---|-----------------------------|----------------------|-------------|--------|
| Set Up Charge | 1 | | | |
| Cement Neat <u>✓ Type III</u> | <u>710</u> | SKS | | |
| Poz. Mix | | | | |
| Calcium Chloride | 2.5 | % | | |
| Gel % Flo-Crete 1/4 # Per Sack <u>2019141 Dr. 1/2</u> | | | | |
| Mileage Charge | <u>204</u> | Miles | | |
| Fuel Surcharge <u>80012090</u> | <u>204</u> | Miles | | |
| Additional Cement | | SKS | | |
| Mixing Rate 4 BPM | Pre-Flush | <u>0251</u> | <u>0257</u> | |
| Disp. Rate 5 BPM | Mixing | <u>0257</u> | <u>0398</u> | |
| Slurry Vol. 1.32 ³ Cu.Ft./Sk | Change Valves | <u>0328</u> | <u>0331</u> | |
| Slurry Wt. 14.8 - 15.0 PPG | Displacement | <u>0331</u> | <u>0345</u> | |
| Water/Cement 6.25 Gal/SK | | | | |
| Water Temp. <u>69°F</u> | | | | |
| Total Slurry Vol. <u>167</u> | BBLS Cement | | | |
| Landed Plug @ <u>970</u> | PSI/Final Lift @ <u>325</u> | PSI | | |
| Pre-Flush W/ <u>30</u> | BBLS H ₂ O | Tax Reference Code | Sub Total | |
| Displace W/ <u>69</u> | BBLS H ₂ O | State <u>CO 2.9%</u> | Tax | |
| Circulate <u>5</u> | BBLS Cement | | Total | |

| Truck No. | Code | State Mileage | Nebraska | Colorado | Wyoming | Other | Total Mileage |
|------------------|------|---------------|----------|----------------|---------|-------|---------------|
| <u>1208</u> | | Pump Truck | | <u>60B</u> | | | |
| <u>1214/1217</u> | | Bulk Truck | | <u>60B/60B</u> | | | |

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin O. Kenny - Demetrio

Received By Scott H. Henshaw

Customer of His Agent