



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600139

Date	8/28/11	Well Owner	Kerr McGee	Well No.	24-29	Lease	Howard
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xframe 15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Ft. 1218				
Surface	8 5/8 CSG #24	Bottom of Surface	Ft. 1209				
Plug		Plug Landed @	1165	Ft.	Time On	2045	
Production		Pipe Landed @	1209	Ft.	Plug Down	0100	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat Type III	760	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Fio-Cete 1/4 # Per Sack				
Mileage Charge	204	Miles		
Fuel Surcharge	204	miles		
Additional Cement		SKS		
Mixing Rate	2353	2359		
Disp. Rate	2359	0043		
Slurry Vol.	1.32 Cu. Ft./Sk	Change Valves		
Slurry Wt.	14.8 - 15.0 PPG	Displacement		
Water/Cement	6.25 Gal/SK			
Water Temp.	65°F			
Total Slurry Vol.	179.6	BBLS Cement		
Landed Plug @	975	PSI/Final Lift @ 450	PSI	
Pre-Flush W/	30	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	74	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	2	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		68			
1207/1214		Bulk Truck		68/68			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/Adam/Steve/Chris

Received By Jimmy Chissey
Customer or His Agent