



02055330

Well Name: Williams Production RMT
Well Name: RGU 411-6-297
Pad Name: FED RGU 41-1-298
Legal Description: NENESEC1TWP2SRNG98W
Unit: Ryan Gulch
Unit # COC068239
COGCC # 96850
API # 05-103-11438-00
County: Rio Blanco
Field: Sulphur Creek
Field # 80090
Rig Name and Number: CYCLONE 29
Williams Supervisor: Andrew Brunk
Phone number at rig: 281-617-4385

RECEIVED
 NOV 14 2011
COGCC

This notice, sent on	<u>11/14/2011</u>	is to inform you that William:
ran and cemented	<u>9-5/8" Surface</u>	casing.
Depth casing landed	<u>3574</u>	
Volume pumped	<u>251 bbls, 317 bbl.</u>	
Cement density	<u>12.8 ppg, 12.8 ppg.</u>	
Stages	<u>2</u>	
Bumped plug	<u>Yes, Yes</u>	
Floats held	<u>Yes, Yes</u>	
Returns	<u>Full</u>	
Losses	<u>None</u>	
Lift Pressure	<u>660, 350</u>	psi

Additionally:

Cement level fell 60' after cement job and was topped
 out 4 hrs later with 28 bbl 15.8 ppg Neat G cement.level
 remained at the bottom of the cellar.
 Hole Size: 14-3/4" - 1,500', 13-1/2" - 3,580'. DV
 tool @ 1,494'.