



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199722

Date 6-22-11	Well Owner Kerr McGee	Well No. 37-4	Lease Moser
County Weld	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700 (Xtreme #15)			
City/State/Zip Denver, Colorado 80202			
Type of Job	Depth	Ft. 781	
<u>Surface</u> 8 5/8" CSG-24"	Bottom of Surface	Ft. 771	
Plug	Plug Landed @ 787	FL	Time On 03:00
Production	Pipe Landed @ 771	FL	Plug Down 06:15

Description	Qty.	Meas.	Unit Price	Amount			
Set Up Charge	1						
Cement Neat <input checked="" type="checkbox"/> Type III	490	SKS					
Poz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Cete 1/4 # Per Sack 2047757 DRL							
Mileage Charge	120	Miles					
Fuel Surcharge	120	Miles					
Additional Cement		SKS					
Mixing Rate 4 BPM	Pre-Flush	0536	0542				
Disp. Rate 5 BPM	Mixing	0542	0603				
Slurry Vol. 1.32 Cu. Ft./Sk	Change Valves	0603	0606				
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0606	0615				
Water/Cement 6.25 Gal/SK							
Water Temp. 69°F							
Total Slurry Vol. 115.2	BBLS Cement						
Landed Plug @ 350	PSI/Final Lift @ 200	PSI					
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total				
Displace W/ 46.2	BBLS H ₂ O	State CO 2.9%	Tax				
Circulate 5	BBLS Cement		Total				
Truck No. 1208	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1214/1217		Pump Truck		40			
		Bulk Truck		40/40			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Justin, Darks, Justin, Demetrio**

Received By **John Salas**
Customer or His Agent