



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600004

Date	8-11-11	Well Owner	Kerr McGee	Well No.	22-15	Lease	RICKS
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #14)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	943		
Surface	8 5/8" CSG-24A	Bottom of Surface		Fl.	925		
Plug		Plug Landed @	889	Fl.	Time On	0115	
Production		Pipe Landed @	925	Fl.	Plug Down	0545	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	580	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel. % Flo-Cete 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	0448	0456	
Disp. Rate 5 BPM	Mixing	0456	0530	
Slurry Vol. 1.32 ³ Cu. Ft./Sk	Change Valves	0530	0533	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0533	0545	
Water/Cement 6.25 Gal/SK				
Water Temp. 74°F				
Total Slurry Vol. 136.3	BBS Cement			
Landed Plug @ 800	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 30	BBS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 56.5	BBS H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			
1217/1218		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By SOE, SOSH, EVAN, ERNIE

Received By

Cody Sanders
Customer or His Agent