



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600006

Date	8-18-11	Well Owner	Kerr McGee	Well No.	23-15	Lease	RICKS
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (STREING 14)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Fl.		940	
Surface	8 5/8" csg		Bottom of Surface	Fl.		930	
Plug			Plug Landed @	885	Fl.	Time On	0915
Production			Pipe Landed @	930	Fl.	Plug Down	1230

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat	TYPE III 100% EXCESS	590	SKS	
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	20488080/132	Miles		
Fuel Surcharge	800/2090	132 miles		
Additional Cement	30	SKS		
Mixing Rate	4 BPM	Pre-Flush	1131	1139
Disp. Rate	5 BPM	Mixing	1139	1216
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1216	1219
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1219	1230
Water/Cement	6.25 Gal/SK			
Water Temp.	76			
Total Slurry Vol.	145.7	BBLs Cement		
Landed Plug @	700	PSI/Final Lift @ 300	PSI	
Pre-Flush W/	30	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	56.2	BBLs H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	3	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			
1214/1218		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By Scott Hansen  
Customer or His Agent