

**FORM  
5**Rev  
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400216345

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Cindy Vue

2. Name of Operator: KERR-MCGEE OIL &amp; GAS ONSHORE LP

Phone: (720) 929-6832

3. Address: P O BOX 173779

Fax: (720) 929-7832

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-32553-00

6. County: WELD

7. Well Name: CANNON

Well Number: 37-3

8. Location: QtrQtr: SWSE Section: 3 Township: 2N Range: 65W Meridian: 6

Footage at surface: Distance: 495 feet Direction: FSL Distance: 2121 feet Direction: FEL

As Drilled Latitude: 40.161868 As Drilled Longitude: -104.648030

## GPS Data:

Data of Measurement: 08/03/2011 PDOP Reading: 3.9 GPS Instrument Operator's Name: Renee Doiron

\*\* If directional footage at Top of Prod. Zone Dist.: 71 feet. Direction: FSL Dist.: 1294 feet. Direction: FEL

Sec: 3 Twp: 2N Rng: 65W

\*\* If directional footage at Bottom Hole Dist.: 71 feet. Direction: FSL Dist.: 1294 feet. Direction: FEL

Sec: 3 Twp: 2N Rng: 65W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 07/22/2011 13. Date TD: 07/24/2011 14. Date Casing Set or D&amp;A: 07/26/2011

## 15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7871 TVD\*\* 7744 17 Plug Back Total Depth MD 7843 TVD\*\* 7716

18. Elevations GR 4853 KB 4868

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

P/E AI-CNLD-TC-CV; CBL

## 20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	771	490	0	771	VISU
1ST	7+7/8	4+1/2	11.6#	0	7,861	230	6,240	7,861	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: 07/26/2011					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	5,520	714	344	5,560
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,510	4,576	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,036		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,246		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,268		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,724		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: 10/19/2011 Email: Cindy.Vue@anadarko.com

### Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400216347	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400216348	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400216345	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

### General Comments

User Group	Comment	Comment Date
Permit	REC LOGS DOC#1671156-59, IN SCANNING	10/21/2011 8:49:15 AM
Permit	WAITING FOR HARD COPY LOGS	10/20/2011 2:41:19 PM

Total: 2 comment(s)