



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600057

Date	9/2/2011	Well Owner	Kerr McGee	Well No.	25-19	Lease	REVERBEND
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP (XTREME#14)						
Address	1999 Broadway, Suite 3700						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	1020		
Surface	8 5/8" CSG 24"	Bottom of Surface		Fl.	1010		
Plug		Plug Landed @	966	Fl.	Time On	2330	
Production		Pipe Landed @	1010	Fl.	Plug Down	0600	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	640	SKS		
Poz. Mix				
Calcium Chloride	2027284.0r1	2.5	%	
Gal % Flo-Ceta 1/4 # Per Sack				
Mileage Charge	60012090	210	Miles	
Fuel Surcharge	210	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0511	0517
Disp. Rate	5 BPM	Mixing	0517	0545
Slurry Vol.	1.32' Cu.Ft./Sk	Change Valves	0545	0548
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0548	0600
Water/Cement	6.25 Gal/SK			
Water Temp.	71			
Total Slurry Vol.	150.4	BBLs Cement		
Landed Plug @	375	PSI/Final Lift @	250	PSI
Pre-Flush Wt	30	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace Wt	61.4	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	8	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		70			
1214/1234		Bulk Truck		70/70			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/ADAM/CHRIS

Received By

Carl S. Smith
Customer or His Agent