

# EnCana Oil & Gas (USA), Inc.

## DRILLING PROGRAM

COMPANY NAME: EnCana Oil & Gas, USA 11/21/2011  
 WELL NAME: SG 8508B-21 N22  
 FIELD: Story Gulch STATE: Colorado ELEVATION: 7,585  
 SURFACE LOCATION: 39 41 02.94028 108 09 25.38442  
 API: 0504520665  
 ADDITIONAL INFO: \_\_\_\_\_

GEOLOGICAL		MECHANICAL	
LOGS	FORMATION TOPS	HOLE SIZE	CASING SIZE
	118' MD/TVD		20" conductor
	<b>211 sx Class 'G'</b> Weight: 15.8 ppg Yield: 1.16 cf/sk Interval: Surface - 140' Excess: 25%	30"	Cemented w/ 138 sx 12.0 ppg 2.45 cf/sk
	<b>Plug #3</b>	**40 bbls of 15.8 cmt returned to surf. on Plug # 3	
	<b>250 sx LiteFIL</b> Weight: 12.5 ppg Yield: 1.81 cf/sk Interval: 140' - 445' Excess: 25%		
	<b>Plug #2</b>	14-3/4"	
	<b>504 sx LiteFIL</b> Weight: 11.0 ppg		
	A Groove @ 744' TVD ±		