

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

2285527

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: JENN MENDOZA

2. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY LLC

Phone: (303) 260-4533

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8285

City: DENVER State: CO Zip: 80202

5. API Number 05-103-11803-00

6. County: RIO BLANCO

7. Well Name: Federal

Well Number: RGU 33-35-198

8. Location: QtrQtr: Lot 11 Section: 35 Township: 1s Range: 98w Meridian: 6

Footage at surface: Distance: 2425 feet Direction: FSL Distance: 1968 feet Direction: FWL

As Drilled Latitude: 39.919200 As Drilled Longitude: -108.362440

GPS Data:

Date of Measurement: 06/29/2011 PDOP Reading: 1.9 GPS Instrument Operator's Name: J. KIRKPATRICK

** If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

** If directional footage at Bottom Hole Dist.: 2089 feet. Direction: FSL Dist.: 1974 feet. Direction: FEL

Sec: 35 Twp: 1S Rng: 98W

9. Field Name: SULPHUR CREEK

10. Field Number: 80090

11. Federal, Indian or State Lease Number: COC060735

12. Spud Date: (when the 1st bit hit the dirt) 07/16/2011 13. Date TD: 08/07/2011 14. Date Casing Set or D&A: 08/09/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 12436 TVD** 12320 17 Plug Back Total Depth MD TVD**

18. Elevations GR 6778 KB 6799

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

HIGH RESOLUTION INDUCTION, SPECTRAL DENSITY, DUAL SPACED NEUTRON, CBL, AND TWO TMD3DL, MUD

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18	0	48	135	0	80	135	CALC
SURF	14+3/4	9+5/8	0	0	3,895	2,048	0	3,895	CALC
1ST	7+7/8	4+1/2	0	0	12,426	1,604	0	12,426	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
MESAVERDE	7,585		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	10,615		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	11,204		<input type="checkbox"/>	<input type="checkbox"/>	
COZZETTE	11,340		<input type="checkbox"/>	<input type="checkbox"/>	
CORCORAN	11,571		<input type="checkbox"/>	<input type="checkbox"/>	
SEGO	12,189		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

SURFACE PRESSURE = 0#
LOGS WILL BE SUBMITTED TO THE COGCC BY THE SERVICE COMPANY UPON PAD DRILLOUT.
WILLIAMS WILL UPLOAD DIGITAL LOGS TO THE COGCC WEBSITE. WAITING ON COMPLETIONS.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JENN MENDOZA

Title: PERMIT TECH II

Date: 10/20/2011

Email: JENN.MENDOZA@WILLIAMS.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
2285529	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
2285528	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
2285527	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Engineer	Preliminary Form 5, no CBL yet.	11/29/2011 9:25:12 AM
Permit	logs in scanning doc#2202636, 2204191-93, 2204176-77	11/17/2011 2:32:27 PM

Total: 2 comment(s)