

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 2285671			
PluggingBond SuretyID 20010124			

APPLICATION FOR PERMIT TO:

1. ☐ Drill, ☐ Deepen, ☐ Re-enter, ☒ **Recomplete and Operate**

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐
Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120
5. Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-3779
6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461
Email: DJREGULATORY@ANADARKO.COM
7. Well Name: HAROLD R. MIXON GAS UNIT Well Number: 2
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 8080

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 25 Twp: 2N Rng: 67W Meridian: 6
Latitude: 40.106194 Longitude: -104.833482

Footage at Surface: 1650 feet FNL/FSL 990 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750
12. Ground Elevation: 4875 13. County: WELD

14. GPS Data:

Date of Measurement: 06/04/2008 PDOP Reading: 2.7 Instrument Operator's Name: CODY MATTSON

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 450 ft

18. Distance to nearest property line: 309 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1092 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD	407	80	E/2SE/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20010125

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SEE ATTACHED OIL AND GAS LEASE DATED FEBRUARY 13, 1970

25. Distance to Nearest Mineral Lease Line: 309 ft

26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	668	475	668	0
1ST	7+7/8	4+1/2	11.6	0	8,080	200	8,080	7,255

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments A FORM 2A IS NOT REQUIRED FOR THIS RECOMPLETION BECAUSE NO PIT WILL BE CONSTRUCTED AND THERE WILL BE NO ADDITIONAL SURFACE DISTURBANCE BEYOND THE ORIGINALLY DISTURBED AREA. RECOMPLETE FORM 4 DOC 2285669

34. Location ID: 318910

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: REGULATORY Date: 11/4/2011 Email: DJREGULATORY@

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 11/29/2011

API NUMBER

05 123 10238 00

Permit Number: _____ Expiration Date: 11/28/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Operator must meet water well testing requirements per Rule 318A.

1) Provide cement bond log to verify isolation of Sussex. 2) If this work has not been performed, then provide remedial cement coverage from 200' below Sussex to 200' above Sussex (minimum coverage 4850' to 4350'). Verify remedial coverage with cement bond log.

Attachment Check List

Att Doc Num	Name
2285667	OIL & GAS LEASE
2285668	30 DAY NOTICE LETTER
2285671	APD ORIGINAL

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	11/29/2011 2:44:01 PM
Permit	Okay to pass pending public comment 11/28/11.	11/8/2011 10:59:41 AM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)