

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400222237			
PluggingBond SuretyID 20080034			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐  
Sidetrack ☐

3. Name of Operator: BAYSWATER EXPLORATION AND PRODUCTION LLC

4. COGCC Operator Number: 10261

5. Address: 730 17TH ST STE 610

City: DENVER State: CO Zip: 80202

6. Contact Name: Kallasandra Moran Phone: (303)928-7128 Fax: (303)962-6237

Email: kmoran@petro-fs.com

7. Well Name: Schlotthauer Well Number: 14-23

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7688

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 23 Twp: 7N Rng: 67W Meridian: 6

Latitude: 40.552646 Longitude: -104.866742

Footage at Surface: 85 feet FNL/FSL FSL 886 feet FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4965 13. County: WELD

14. GPS Data:

Date of Measurement: 08/11/2011 PDOP Reading: 1.5 Instrument Operator's Name: Chris Boub / PFS

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 661 FSL 1986 FWL 660 FSL 1986 FWL  
Bottom Hole: FNL/FSL 660 FSL 1986 FWL  
Sec: 23 Twp: 7N Rng: 67W Sec: 23 Twp: 7N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 571 ft

18. Distance to nearest property line: 85 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1842 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL		80	S2/SW4
Greenhorn	GRNHN		80	S2/SW4
Hygiene	HYGN		80	S2/SW4
Niobrara	NBRR		80	S2/SW4
Parkman	PRKM		80	S2/SW4
Sussex	SUSX		80	S2/SW4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SW/4, Sec. 23, T7N-R67W

25. Distance to Nearest Mineral Lease Line: 85 ft 26. Total Acres in Lease: 111

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	660	385	660	0
1ST	7+7/8	4+1/2	11.6	0	7,688	934	7,688	0

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments No conductor casing will be set.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kallasandra M. Moran

Title: Regulatory Manager Date: 11/9/2011 Email: kmoran@petro-fs.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 12/4/2011

#### API NUMBER

05 123 34777 00

Permit Number: \_\_\_\_\_ Expiration Date: 12/3/2013

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Operator must meet water well testing requirements per Rule 318A.

- 1) Note surface casing setting depth change from 550' to 660'. Increase cement coverage accordingly and cement to surface.
- 2) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Parkman. Verify coverage with cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name
1694562	EXCEPTION LOC REQUEST
1694563	EXCEPTION LOC WAIVERS
1694564	WAIVERS
400222237	FORM 2 SUBMITTED
400222240	TOPO MAP
400222241	30 DAY NOTICE LETTER
400222242	PLAT
400222243	DEVIATED DRILLING PLAN

Total Attach: 8 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Final Review Completed. No LGD or public comment received.	12/2/2011 10:49:45 AM
Permit	Received and attached Exception Location Request letter and waiver, & Property line waiver.	12/2/2011 10:49:25 AM
Permit	ON HOLD: Requesting: the exception location request letter and waivers, & the property line waiver.	11/14/2011 4:47:49 PM

Total: 3 comment(s)

## BMP

<u>Type</u>	<u>Comment</u>
Site Specific	<p>Fence the well site after drilling to restrict public and wildlife access.</p> <p>Keep well site location, the road, and the pipeline easement free of noxious weeds, litter and debris.</p> <p>Spray for noxious weeds, and implement dust control, as needed.</p> <p>Operator will not permit the release or discharge of any toxic or hazardous chemicals or wastes on Owner's Land.</p> <p>Construct and maintain gates where any roads used by operator, its employees, or contractors cross through fences on the leased premises.</p>
Storm Water/Erosion Control	<p>Use water bars, and other measures to prevent erosion and non-source pollution.</p> <p>Implement and maintain BMPs to control stormwater runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation.</p> <p>Co-locate gas and water gathering lines whenever feasible, and mitigate any erosion problems that arise due to the construction of any pipeline(s).</p>
Interim Reclamation	<p>Utilize only such area around each producing well as is reasonably necessary.</p> <p>Restore the remainder of the well site location to its original condition within a reasonable time after the completion of operations.</p> <p>All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.</p>
Planning	<p>When feasible develop multiple well sites by using directional drilling to reduce cumulative impacts and adverse impacts on wildlife resources.</p>
Construction	<p>Remove only the minimum amount of vegetation necessary for the construction of roads and facilities.</p> <p>Conserve topsoil during excavation and reuse as cover on disturbed areas to facilitate regrowth of vegetation.</p> <p>No construction or routine maintenance activities will be performed during periods when the soil is too wet to adequately support construction equipment.</p>
Final Reclamation	<p>All surface restoration shall be accomplished to the satisfaction of Owner.</p> <p>All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.</p> <p>Final reclamation shall be completed to the reasonable satisfaction of the Owner as soon as practical after installation (weather permitting) and in accordance with regulatory agency standards (BLM/COGCC).</p>
Drilling/Completion Operations	<p>When available and reasonable use a closed-loop drilling mud system to preclude the use of an earthen reserve pits when available.</p>

Total: 7 comment(s)