



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600040

Date <u>9-2-11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>36-30</u>	Lease <u>Bryant</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #12)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>882</u>	
<u>Surface</u> <u>8 7/8" - CSG - 24"</u>	Bottom of Surface	Fl. <u>875</u>	
Plug	Plug Landed @ <u>831</u>	Fl. Time On <u>13:15</u>	
Production	Pipe Landed @ <u>875</u>	Fl. Plug Down <u>21:00</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III 100% Finess</u>	<u>550</u>	SKS		
Poz. Mix				
Calcium Chloride <u>LIINGREEN</u>	2.5	%		
Gel % <u>Fio-Cete 1/4 # Per Sack</u>				
Mileage Charge <u>User ID ZMDL8</u>	<u>270</u>	Miles		
Fuel Surcharge <u>WBS/WOICC 2030379.0RL</u>	<u>270</u>			
Additional Cement <u>\$500/2090</u>	<u>40</u>	SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>20:17</u>	<u>20:23</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>20:23</u>	<u>20:47</u>	
Slurry Vol. <u>1.32<sup>3</sup> Cu.Ft./Sk</u>	Change Valves	<u>20:47</u>	<u>20:50</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>20:50</u>	<u>21:00</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>80 °F</u>				
Total Slurry Vol. <u>138.7</u>	BBLS Cement			
Landed Plug @ <u>800</u>	PSI/Final Lift @ <u>400</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ <u>52.8</u>	BBLS H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax	
Circulate <u>6</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>90</u>			
<u>1917 / 1218</u>		Bulk Truck		<u>90 / 90</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Dallas, Kenny, Demetrio

Received By [Signature]  
Customer or His Agent