

WELLBORE DIAGRAM

704' FSL & 794' FWL

Operator: Koch Exploration Company
 Well Name: WRD Fed M-28-2-96N
 Lease Number: C-127529
 Location: SWSW Sec. 28-T2N-R96W
 Field: White River Dome
 County, State: Rio Blanco, CO
 API Number: 05-103-09469
 Diagram Date: 4/25/2011

KB 5884'

GL 5873'

Well History

Spud Date: 1/13/1991
 Date TD Reached: 1/31/1991
 Completion Date: 4/15/1991
 Recomplete: 1/28/1997

13-3/8" 48# csg set @ 291'
 cmtd w/ 400 sx Class "G"

9-5/8" 36# csg set @ 1635'
 cmtd w/ 600 sx 50/50 Poz

Set 100' plug at surface

**Perforate casing at 1685' and attempt to circulate to surface.
 Set 100' balanced plug over surface casing shoe**

Set cement plugs over bad casing, based on DLD log

Original TOC @ 5280'

Based on DLD casing log

5561-67' } Acidized 1/28/1997 **Set cement plug from 5511-6300'**
 5672-76'
 5760-66'

5840-46' }
 5948-54' } Perf'd and fraced 1/28/1997
 6036-42'

6143-6240' }
 6348-54' }
 6408-16' }
 6713-18' }
 6734-40' } 1991 (Original Completions)
 6768-76' }
 6822-31' }
 6864-71' }
 6880-87' }
 6916-20' }

Set cement plug from 6300-6953'

5-1/2" 17# N80 csg set @ 7040'
 cmtd w/ ?? sx Class "G"

PBTD 6953'

TD 7050'

