



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-2299 • FAX (970) 353-7712

OUR INVOICE

## 600094

|   |                              |                      |                       |
|---|------------------------------|----------------------|-----------------------|
| Date <b>7-24-11</b>                                   | Well Owner <b>Kerr McGee</b> | Well No. <b>3-36</b> | Lease <b>CARMA</b>    |
| County <b>WELD</b>                                    | State <b>Colorado</b>        |                      |                       |
| Charge to <b>Kerr McGee Oil &amp; Gas Onshore, LP</b> |                              |                      |                       |
| Address <b>1999 Broadway, Suite 3700 (XTREME-11)</b>  |                              |                      |                       |
| City, State Zip <b>Denver, Colorado 80202</b>         |                              |                      |                       |
| Type of Job:  | Depth                        | Ft. <b>844</b>       |                       |
| <u>Surface</u> <b>8 5/8" CSG-24 #</b>                 | Bottom of Surface            | Ft. <b>829</b>       |                       |
| Plug  | Plug Landed @ <b>784</b>     | Ft.                  | Time On <b>2200</b>   |
| Production  | Pipe Landed @ <b>829</b>     | Ft.                  | Plug Down <b>0015</b> |

| Description                                   | Qty.                        | Meas.                | Unit Price | Amount |
|---|-----------------------------|----------------------|------------|--------|
| Set Up Charge                                 | <b>1</b>                    |                      |            |        |
| Cement Neat <b>TYPE III</b>                   | <b>520</b>                  | SKS                  |            |        |
| Poz. Mix                                      |                             |                      |            |        |
| Calcium Chloride <b>2039904191</b>            | <b>25</b>                   | %                    |            |        |
| Gel % Flo-Cete 1/4 # Per Sack                 |                             |                      |            |        |
| Mileage Charge <b>80012090</b>                | <b>156</b>                  | Miles                |            |        |
| Fuel Surcharge                                | <b>156</b>                  | MILES                |            |        |
| Additional Cement                             |                             | SKS                  |            |        |
| Mixing Rate: <b>4 BPM</b>                     | Pre-Flush                   | <b>2320-2331</b>     |            |        |
| Disp. Rate: <b>5 BPM</b>                      | Mixing                      | <b>2331-0002</b>     |            |        |
| Slurry Vol. <b>1.32<sup>3</sup> Cu.Ft./Sk</b> | Change Valves               | <b>0002-0005</b>     |            |        |
| Slurry Wt. <b>14.8 - 15.0 PPG</b>             | Displacement                | <b>0005-0015</b>     |            |        |
| Water/Cement <b>6.25 Gal/SK</b>               |                             |                      |            |        |
| Water Temp. <b>70°F</b>                       |                             |                      |            |        |
| Total Slurry Vol. <b>122.2</b>                | BBLS Cement                 |                      |            |        |
| Landed Plug @ <b>250</b>                      | PSI/Final Lift @ <b>230</b> | PSI                  |            |        |
| Pre-Flush Wt. <b>20</b>                       | BBLS H <sub>2</sub> O       | Tax Reference Code   | Sub Total  |        |
| Displace Wt. <b>49.8</b>                      | BBLS H <sub>2</sub> O       | State <b>CO 2.9%</b> | Tax        |        |
| Circulate <b>4</b>                            | BBLS Cement                 |                      | Total      |        |

| Truck No.        | Code | State Mileage | Nebraska | Colorado     | Wyoming | Other | Total Mileage |
|------------------|------|---------------|----------|--------------|---------|-------|---------------|
| <b>1202</b>      |      | Pump Truck    |          | <b>52</b>    |         |       |               |
| <b>1217/1218</b> |      | Bulk Truck    |          | <b>52/52</b> |         |       |               |

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By

**JOE JOSH, EVAN**

Received By

**TOM BOWER**

Customer or His Agent