

KING 12-28 WELL SCHEMATIC

Surface Loc: SWNW, Sec. 28, T19S, R69W

TD: 3533' MD

API No.: 05-043-06211

BH Loc: NWNW, Sec. 28, T19S, R69W

TVD: 3224' TVD

County: Fremont State: CO

Capstar RKB 11'

RKB - 5368'

GL- 5357'

MD
(RKB)
71'

675'

← 24" Hole

← 16" Conductor

← 12 1/4" Hole

← 8-5/8", 24 PPF, J-55, STC

← 7 7/8" Hole

← 2 7/8", 6.5#, J-55, EUE 8rd tbg

Max Deviation: 33.27

Max Dogleg: 6.18

Pre-Perfed Casing 5-1/2", 15.0 ppf, J-55,
R3, LT&C
2447' - 3514' MD

TD 3533' MD / 3224' TVD

NOT TO SCALE