

APPLICATION FOR PERMIT TO:

1. **Drill,** Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____

SINGLE ZONE MULTIPLE COMMINGLE

Refiling
Sidetrack

Document Number:
400191807

PluggingBond SuretyID
20030009

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202

6. Contact Name: SUSAN MILLER Phone: (303)228-4246 Fax: (303)228-4286
Email: smiller@nobleenergyinc.com

7. Well Name: FIVE M Well Number: E28-69HN

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 13993

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 28 Twp: 6N Rng: 65W Meridian: 6
Latitude: 40.463430 Longitude: -104.676970

Footage at Surface: 646 feet FNL 284 feet FWL

11. Field Name: Greeley Field Number: 32760

12. Ground Elevation: 4712 13. County: WELD

14. GPS Data:
Date of Measurement: 06/30/2011 PDOP Reading: 1.8 Instrument Operator's Name: Robert Daley

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

245 FNL 722 FWL 100 FNL 2105 FWL

Sec: 28 Twp: 6N Rng: 65W Sec: 27 Twp: 6N Rng: 65W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 255 ft

18. Distance to nearest property line: 254 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 572 ft

LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		480	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached Mineral Lease Description. Noble Energy Inc certifies that the leases shall be committed to the unit.

25. Distance to Nearest Mineral Lease Line: 538 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+3/4	9+5/8	36	0	700	348	700	0
1ST	8+3/4	7	26	0	7,316	521	7,316	
1ST LINER	6+1/8	4+1/2	11.6	6104	13,993			

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Conductor casing will not be used. First string top of cement will be 200' above the Niobrara formation. Production liner will be hung off inside of the 7" casing. This is part of a 2-well, multi-well pad which includes the Five M E28-69HN and Five M E28-67HN. See 2A doc. no. 400191616 which covers both locations. Unit Configuration: Sec. 21: S/2S/2, Sec. 22: S/2SW/4, Sec. 28: N/2N/2, Sec. 27: N2/NW/4, T6N-R65W. Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Operator requests an exception location to 318Aa, 318Ac: Exception request and waiver attached.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: SUSAN MILLER

Title: Regulatory Analyst II Date: 11/14/2011 Email: smiller@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nash Director of COGCC Date: 12/11/2011

API NUMBER
05 123 34797 00

Permit Number: _____ Expiration Date: 12/10/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Operator must meet water well sampling requirements per rule 318A

- 1) Provide 24 hour notice of MIRU to Jim Precup via e-mail at jim.precup@state.co.us.
- 2) Comply with Rule 317.i and provide cement coverage from the end of the production casing to a minimum of 200' above the Niobrara and from 200' below Parkman to 200' above Parkman. Verify coverage with a cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from the end of production casing to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
2481294	SURFACE CASING CHECK
400191807	FORM 2 SUBMITTED
400191852	30 DAY NOTICE LETTER
400191853	EXCEPTION LOC WAIVERS
400206389	WELL LOCATION PLAT
400206390	DEVIATED DRILLING PLAN
400206391	PROPOSED SPACING UNIT
400206431	EXCEPTION LOC REQUEST
400223527	PROPOSED SPACING UNIT
400223528	LEGAL/LEASE DESCRIPTION
400223529	PROPOSED SPACING UNIT

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) and General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location and will remain in place until the pad reaches final reclamation.
General Housekeeping	General housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur, prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.

Total: 3 comment(s)