



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7298 • FAX (970) 353-7712

OUR INVOICE

600102

Date <u>7-18-11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>32-3</u>	Lease <u>Cannon</u>
County <u>Lincoln</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700</u>	<u>(Patterson #189)</u>		
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job:	Depth	Ft. <u>765</u>	
<u>Surface</u> <u>8 1/4" - C-56-24</u>	Bottom of Surface	Ft. <u>750</u>	
Plug	Plug Landed @ <u>706</u>	Ft. <u>10:00</u>	
Production	Pipe Landed @ <u>750</u>	Ft. <u>13:30</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	470	SKS		
Poz Mix				
Calcium Chloride	-2.5	%		
Gel % <u>Fio-Cete 1/4 # Per Sack</u>				
Mileage Charge	129	Miles		
Fuel Surcharge	129	Miles		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	1252	1258	
Disp. Rate <u>5 BPM</u>	Mixing	1258	1318	
Slurry Vol. <u>1.32" Cu.Ft./Sk</u>	Change Valves	1318	1321	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	1321	1330	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>92°F</u>				
Total Slurry Vol. <u>110.5</u>	BBLS Cement			
Landed Plug @ <u>400</u>	PSI/Final Lift @ <u>200</u>	PSI		
Pre-Flush Wt <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace Wt <u>45</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>43</u>			
<u>1214/1218</u>		Bulk Truck		<u>43/43</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Parker, Demetrio, Kenny

Received By [Signature]
Customer or His Agent