



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600056

Date	9/2/11	Well Owner	Kerr McGee	Well No.	11-16	Lease	COOLEY
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (PATTERSON #159)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Ft. 940				
Surface	8 5/8" CSG 24"	Bottom of Surface	Ft. 934				
Plug		Plug Landed @	889	Ft.	Time On	1820	
Production		Pipe Landed @	934	Ft.	Plug Down	2000	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	590	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack 2040974				
Mileage Charge 80012090	229	Miles		
Fuel Surcharge	229	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1513	1915	
Disp. Rate 5 BPM	Mixing	1915	1945	
Slurry Vol. 1.32 Cu.Ft./Sk	Change Valves	1945	1945	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1945	2000	
Water/Cement 6.25 Gal/SK				
Water Temp. 71				
Total Slurry Vol. 138.7	BBLS Cement			
Landed Plug @ 600	PSI/Final Lift @ 375	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 56.5	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		76			
1216/1214		Bulk Truck		76/76			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM ADAM KRIS

Received By [Signature]
Customer or His Agent