

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400231755

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Cindy Vue

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6832

3. Address: P O BOX 173779

Fax: (720) 929-7832

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-32275-00

6. County: WELD

7. Well Name: COOLEY

Well Number: 12-16

8. Location: QtrQtr: SWSW Section: 16 Township: 2N Range: 68W Meridian: 6

Footage at surface: Distance: 988 feet Direction: FSL Distance: 1153 feet Direction: FWL

As Drilled Latitude: 40.134209 As Drilled Longitude: -105.013541

GPS Data:

Data of Measurement: 10/13/2011 PDOP Reading: 2.2 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 1972 feet. Direction: FSL Dist.: 657 feet. Direction: FWL

Sec: 16 Twp: 2N Rng: 68W

** If directional footage at Bottom Hole Dist.: 1975 feet. Direction: FSL Dist.: 658 feet. Direction: FWL

Sec: 16 Twp: 2N Rng: 68W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 09/06/2011 13. Date TD: 09/09/2011 14. Date Casing Set or D&A: 09/11/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8190 TVD** 8017 17 Plug Back Total Depth MD 8162 TVD** 7989

18. Elevations GR 4885 KB 4899

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

AC-TR-SD-DSN; CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	950	600	14	950	CALC
1ST	7+7/8	4+1/2	11.6#	0	8,180	232	6,612	8,180	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 09/11/2011					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	5,444	652	1,260	5,500
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,920	4,150	<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,572	4,823	<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	4,866	5,072	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,306		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,572		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,594		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,190		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: _____ Email: Cindy.Vue@anadarko.com

The subreport 'subreport3' could not be found at the specified location W:\Inetpub\Net\Reports\AttachListNew.rdlc. Please

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)