



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600044

Date	9-7-11	Well Owner	Kerr McGee	Well No.	12-16	Lease	Cooley
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Patterson #189)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	955		
Surface	8 5/8" - CSG - 24"	Bottom of Surface		Ft.	950		
Plug		Plug Landed @	906	Ft.	Time On	10:15	
Production		Pipe Landed @	950	Ft.	Plug Down	14:15	
Description		Qty.		Meas.		Unit Price	Amount
Set Up Charge		1					
Cement Neat	✓ Type III	600		SKS			
Poz. Mix							
Calcium Chloride		2.5		%			
Gel	% Flo-Cete 1/4 # Per Sack						
Mileage Charge	2044 978	228		Miles			
Fuel Surcharge		228		miles			
Additional Cement	600 2090			SKS			
Mixing Rate	4 BPM	Pre-Flush	13:29	13:35			
Disp. Rate	5 BPM	Mixing	13:35	14:01			
Slurry Vol.	1.32 Cu. Ft./Sk	Change Valves	14:01	14:04			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	14:04	14:15			
Water/Cement	6.25 Gal/SK						
Water Temp.	70°F						
Total Slurry Vol.	141	BBLS Cement					
Landed Plug @	600	PSI/Final Lift @	300	PSI			
Pre-Flush W/	30	BBLS H ₂ O	Tax Reference Code	Sub Total			
Displace W/	57.6	BBLS H ₂ O	State CO 2.9%	Tax			
Circulate	5	BBLS Cement		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		76			
1214/1217		Bulk Truck		76/76			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Dicks, Kenny, Dondrio

Received By M. W. White
Customer or His Agent