



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600014

Date <u>8-29-11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>13-16</u>	Lease <u>COOLEY</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (PAT-189)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	
<u>Surface</u>	<u>8 5/8" CSG-24H</u>	<u>955</u>	
Plug	Bottom of Surface	Fl.	
		<u>945</u>	
Production	Plug Landed @ <u>901</u> Ft.	Time On <u>1245</u>	
	Pipe Landed @ <u>945</u> Ft.	Plug Down <u>1600</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge <u>MIKE LINGREEN</u>	1			
Cement Neat <u>TYPE III</u>	600	SKS		
Proz. Mix <u>User ID ZMDL6</u>				
Calcium Chloride <u>WBSAWO/CC 80012070 DRL</u>	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge <u>G/L Acct. 2044837</u>	228	Miles		
Fuel Surcharge	228	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush 1503	-1510		
Disp. Rate 5 BPM	Mixing 1510	-1546		
Slurry Vol. 1.32 ³ Cu. Ft./Sk	Change Valves 1546	-1549		
Slurry Wt. 14.8 - 15.0 PPG	Displacement 1549	-1600		
Water/Cement 6.25 Gal/SK				
Water Temp. <u>78°F</u>				
Total Slurry Vol. <u>141.0</u> BBLs Cement				
Landed Plug @ <u>300</u> PSI/Final Lift @ <u>280</u> PSI				
Pre-Flush W/ <u>30</u> BBLs H ₂ O	Tax Reference Code	Sub Total		
Displace W/ <u>57.3</u> BBLs H ₂ O	State <u>CO 2.9%</u>	Tax		
Circulate <u>5</u> BBLs Cement		Total		

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1202</u>		Pump Truck		<u>76</u>			
<u>1216/1218</u>		Bulk Truck		<u>76/76</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By Danny
Customer or His Agent