



Total Surface Disturbance = 0.82 Acres

NOTES:

- (1) Slope Track and/or Terrace all Slopes and Piles
- (2) Erosion Control & Seed Topsoil
- (3) Erosion Control & Seed Outside

ESTIMATED EARTHWORK QUANTITIES

EXCAVATION: 763 cy
 EMBANKMENT: 661 cy
 SPOIL: 102 cy
 (use in access road construction)
 TOPSOIL: 530 cy

SURFACE DISTURBANCE
 (IN ACRES)

Pad Site	0.58
Side Slopes	0.05
Stockpiles & Stormwater	0.19
TOTAL	0.82

LEGEND

- SL— = SLASH
- SedR = SEDIMENT RESERVOIR
- W— = PERIMETER CONTROL (WATTLES)
- D = FILL DIVERSION TO SEDIMENT TRAP
- VGB = VEGETATION BUFFER (UNDISTURBED LAND INSIDE PC)
- ▨ = LEVEL SPREADER
- = TOE BERM (PLACED AT TOE OF ALL FILL SLOPES/STOCKPILES)
- = TOPSOIL BERM

Encana Oil & Gas (USA) Inc.
 RD11 Remote Frac Pad

SE1/4 SE1/4, SECTION 27

T6S, R94W, 6th P.M.

GARFIELD COUNTY, COLORADO



906 Main Street
 Evanston, Wyoming 82930
 Phone No. (307) 789-4545

Site Design	Scale: 1" = 50'	SHEET 1 OF 1
Project No. 05-04-25	Date Surveyed: 11/21/11	
Date Drawn: 11/30/11	Latest Revision Date:	