

**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400231769

## COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120

4. Contact Name: Cindy Vue

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6832

3. Address: P O BOX 173779

Fax: (720) 929-7832

City: DENVER State: CO Zip: 80217-

5. API Number      05-123-32275-00

6. County: WELD

7. Well Name: COOLEY

Well Number: 12-16

8. Location: QtrQtr: SWSW Section: 16 Township: 2N Range: 68W Meridian: 6

9. Field Name: WATTENBERG Field Code: 90750

### Completed Interval

FORMATION: NIOBRARA-CODELL

Status: PRODUCING

Treatment Date: 10/04/2011

Date of First Production this formation: 11/22/2011

Perforations	Top:	7318	Bottom:	7609	No. Holes:	118	Hole size:	0.38
--------------	------	------	---------	------	------------	-----	------------	------

Provide a brief summary of the formation treatment:

Open Hole: 

NB PERF 7318-7474 HOLES 62 SIZE 0.42      CD PERF 7595-7609 HOLES 56 SIZE 0.38  
Frac Niobrara A & B & C down 4-1/2" Csg w/ 252 gal 15% HCl & 242,088 gal Slickwater w/ 201,760# 40/70, 4,000# SB Excel  
Frac Codell down 4-1/2" Csg w/ 203,112 gal Slickwater w/ 150,200# 40/70, 4,000# SB Excel

This formation is commingled with another formation: ☐ Yes ☒ No

**Test Information:**

Date:	11/25/2011	Hours:	24	Bbls oil:	50	Mcf Gas:	100	Bbls H2O:	0
-------	------------	--------	----	-----------	----	----------	-----	-----------	---

Calculated 24 hour rate:	Bbls oil:	50	Mcf Gas:	100	Bbls H2O:	0	GOR:	2000
--------------------------	-----------	----	----------	-----	-----------	---	------	------

Test Method: FLOWING	Casing PSI: 2213	Tubing PSI:	Choke Size: 12/64
----------------------	------------------	-------------	-------------------

Gas Disposition:	SOLD	Gas Type:	WET	BTU Gas:	1251	API Gravity Oil:	49
------------------	------	-----------	-----	----------	------	------------------	----

Tubing Size:                      Tubing Setting Depth:                      Tbg setting date:                      Packer Depth:

Reason for Non-Production:

Date formation Abandoned: ☐ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

Bridge Plug Depth: \_\_\_\_\_ Sacks cement on top: \_\_\_\_\_

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Cindy Vue

Title: Regulatory Analyst II                      Date: 12/13/2011                      Email: Cindy.Vue@anadarko.com

### Attachment Check List

Att Doc Num	Name
400231769	FORM 5A SUBMITTED

Total Attach: 1 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)