



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600075

Date <u>9/26/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>6-116</u>	Lease <u>Thomasow</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #14)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>957</u>	
<input checked="" type="checkbox"/> Surface <u>8 5/8" CSG-24 #</u>	Bottom of Surface	Ft. <u>942</u>	
Plug	Plug Landed @ <u>898</u>	Ft.	Time On <u>1345</u>
Production	Pipe Landed @ <u>942</u>	Ft.	Plug Down <u>1800</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III 100% Excess</u>	<u>590</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Fio-Cete 1/4 # Per Sack				
Mileage Charge <u>205 2321</u>	<u>132</u>	Miles		
Fuel Surcharge <u>800 2090</u>	<u>132</u>	Miles		
Additional Cement	<u>40</u>	SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>1714-</u>	<u>1730</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>1730-</u>	<u>1746</u>	
Slurry Vol. <u>1.32 Cu.Ft./Sk</u>	Change Valves	<u>1746-</u>	<u>1749</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>1749-</u>	<u>1800</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>70</u>				
Total Slurry Vol. <u>148.1</u>	BBLS Cement			
Landed Plug @ <u>700</u>	PSI/Final Lift @	PSI		
Pre-Flush Wt <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub.Total	
Displace Wt <u>57.1</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>3</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1000</u>		Pump Truck		<u>44</u>			
<u>1014/1016</u>		Bulk Truck		<u>44/44</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Kenny & Demetrio

Received By Wayne G. Hilland
Customer or His Agent