



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600153

Date	10-9-11	Well Owner	Kerr McGee	Well No.	23-16	Lease	Thomason
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (VTR-06-14)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	961		
Surface	8 5/8 CSG-24#	Bottom of Surface		Fl.	951		
Plug		Plug Landed @	906	Fl.	Time On	1600	
Production		Pipe Landed @	951	Fl.	Plug Down	1915	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat	MIKE LINGREEN	600	SKS	
Poz. Mix	User ID ZMDLS			
Calcium Chloride	WBE/WC/03 2052381.0m	2.5	%	
Gel %	Fio-Cete 1/4 # Per Sack			
Mileage Charge	G/L ACCL. 80012090	132	Miles	
Fuel Surcharge		132	MILES	
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1816-1824	
Disp. Rate	5 BPM	Mixing	1824-1900	
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	1900-1903	
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1903-1915	
Water/Cement	6.25 Gal/SK			
Water Temp.	50°F			
Total Slurry Vol.	141.0	BBLs Cement		
Landed Plug @	300	PSI/Final Lift @	280	PSI
Pre-Flush W/	30	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	57.6	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			
1207/1217		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Joe, Josh, Evan, Eric

Received By

Customer or His Agent