

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400225770			
PluggingBond SuretyID			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☒
Sidetrack ☐

3. Name of Operator: EXXON MOBIL CORPORATION 4. COGCC Operator Number: 28600
5. Address: P O BOX 4358
City: HOUSTON State: TX Zip: 77210-4358
6. Contact Name: MARK CORNETT Phone: (281)654-1925 Fax: (281)654-1940
Email: mark.cornett@exxonmobil.com
7. Well Name: FREEDOM UNIT Well Number: 197-31C7
8. Unit Name (if appl): FREEDOM UNIT Unit Number: COC069547
X
9. Proposed Total Measured Depth: 13500

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 31 Twp: 1S Rng: 97W Meridian: 6
Latitude: 39.925971 Longitude: -108.326107

Footage at Surface: 400 feet FNL/FSL FNL 1973 feet FEL/FWL FWL

11. Field Name: PICEANCE CREEK Field Number: 68800
12. Ground Elevation: 6539 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 01/02/2006 PDOP Reading: 2.7 Instrument Operator's Name: D. PETTY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 613 FSL 1567 FWL FWL Bottom Hole: FNL/FSL 613 FSL 1567 FWL FWL
Sec: 30 Twp: 1S Rng: 97W Sec: 30 Twp: 1S Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 217 ft

18. Distance to nearest property line: 1973 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 934 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MESAVERDE	MVRD			
OHIO CREEK	OHCRK			
WASATCH	WSTC			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC057961

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

☒

23. Is the Surface Owner also the Mineral Owner? Yes ☐ No ☐ Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

No changes since original APD submittal.

25. Distance to Nearest Mineral Lease Line: 1567 ft 26. Total Acres in Lease: 1162

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: BURIAL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	LINE PIPE	0	120	100	120	0
SURF	14+3/4	10+3/4	45.5	0	4,300	1,380	4,300	0
1ST	9+7/8	7	26	0	9,000	730	9,000	3,800
2ND	6+1/8	4+1/2	15.1	0	13,100	250	13,100	6,700

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments No changes to original APD submittal. Pad has not been built. Location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii). Location is not in a wildlife restricted surface occupancy area. Intermediate casing TOC will be greater than or equal to 200' above the Wasatch G top. Production casing TOC will be greater than or equal to 200' above the Williams Fork (or Ohio Creek, if productive) top.

34. Location ID: 415888

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Mark Cornett

Title: Sr. Regulatory Specialist Date: 11/21/2011 Email: mark.cornett@exxonmobil.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 12/15/2011

API NUMBER

05 103 11642 00

Permit Number: _____ Expiration Date: 12/14/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Before placing oil/salt based muds in a pit, operator must file and receive prior approval of a Pit Permit, Form 15. COGCC regulations regarding pit permits can be found in Rule 903.a.(3). PIT PERMITTING/REPORTING REQUIREMENTS.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 1040 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400225770	FORM 2 SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	LGD/public comments waived. Final Comprehensive Review Status--passed.	12/14/2011 9:02:15 AM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)