



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600079

Date <u>10/4/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>8-32</u>	Lease <u>Howard</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #15)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	
<u>Surface</u>	<u>8 5/8" CSG-24"</u>	<u>1225</u>	
Plug	Bottom of Surface	Fl.	
	<u>1171</u>	<u>1215</u>	
Production	Plug Landed @	Fl.	Time On
	<u>1215</u>		<u>1915</u>
	Plug Down		<u>2300</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III 100% Excess</u>	760	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge <u>80578-03 DRL</u>	216	Miles		
Fuel Surcharge	216	Miles		
Additional Cement <u>800/1090</u>	40	SKS		
Mixing Rate 4 BPM	Pre-Flush	2203-	2209	
Disp. Rate 5 BPM	Mixing	2209-	2242	
Slurry Vol. 1.32 ³ Cu.Ft/Sk	Change Valves	2242-	2245	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	2245-	2300	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>68°F</u>				
Total Slurry Vol. <u>188</u>	BBS Cement			
Landed Plug @ <u>600</u>	PSI/Final Lift @ <u>300</u>	PSI		
Pre-Flush W/ <u>30</u>	BBS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>74.4</u>	BBS H ₂ O	State CO 2.9%	Tax	
Circulate <u>7</u>	BBS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>72</u>			
<u>1214/1216</u>		Bulk Truck		<u>72/72</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Kenny & Demetrio

Received By [Signature]
Customer or His Agent