

**FORM**  
**5**Rev  
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400233841

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120 4. Contact Name: Cindy Vue  
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6832  
3. Address: P O BOX 173779 Fax: (720) 929-7832  
City: DENVER State: CO Zip: 80217-

5. API Number 05-123-32996-00 6. County: WELD  
7. Well Name: PALYO Well Number: 28-11  
8. Location: QtrQtr: NENW Section: 11 Township: 2N Range: 65W Meridian: 6  
Footage at surface: Distance: 1058 feet Direction: FNL Distance: 1401 feet Direction: FWL  
As Drilled Latitude: 40.157576 As Drilled Longitude: -104.635459

## GPS Data:

Data of Measurement: 09/22/2011 PDOP Reading: 3.9 GPS Instrument Operator's Name: Renee Doiron\*\* If directional footage at Top of Prod. Zone Dist.: 56 feet. Direction: FNL Dist.: 2594 feet. Direction: FELSec: 11 Twp: 2N Rng: 65W\*\* If directional footage at Bottom Hole Dist.: 56 feet. Direction: FNL Dist.: 2580 feet. Direction: FELSec: 11 Twp: 2N Rng: 65W9. Field Name: WATTENBERG 10. Field Number: 90750

11. Federal, Indian or State Lease Number: \_\_\_\_\_

12. Spud Date: (when the 1st bit hit the dirt) 09/06/2011 13. Date TD: 09/09/2011 14. Date Casing Set or D&A: 09/10/2011

## 15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation16. Total Depth MD 7990 TVD\*\* 7709 17 Plug Back Total Depth MD 7928 TVD\*\* 764718. Elevations GR 4854 KB 4869

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

CBL  
NO OPEN HOLE LOGS PLANNED FOR THIS WELL.

## 20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	832	530	15	832	CALC
1ST	7+7/8	4+1/2	11.6#	0	7,974	55	7,696	7,974	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: 09/09/2011					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	7,680	1,010	334	7,680
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,163		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,423		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,085		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,354		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,377		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,840		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: \_\_\_\_\_ Email: Cindy.Vue@anadarko.com

The subreport 'subreport3' could not be found at the specified location W:\Inetpub\Net\Reports\AttachListNew.rdlc. Please

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)