



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600016

Date	9-7-11	Well Owner	Kerr McGee	Well No.	28-11	Lease	PALCO
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #12)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Fl.	837			
Surface	8 5/8" CSG-24H	Bottom of Surface	Fl.	832			
Plug		Plug Landed @	787	Fl.	Time On 0745		
Production		Pipe Landed @	832	Fl.	Plug Down 1130		
Description	Qty.	Meas.	Unit Price	Amount			
Set Up Charge	1						
Cement Neat TYPE III	530	SKS					
Poz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Crete 1/4 # Per Sack							
Mileage Charge	2048331 DRL	132	Miles				
Fuel Surcharge	800/2090	132	MILES				
Additional Cement	800/2090		SKS				
Mixing Rate	4 BPM	Pre-Flush	1040	1045			
Disp. Rate	5 BPM	Mixing	1045	1117			
Slurry Vol.	1.32 Cu.Ft./Sk	Change Valves	1117	1120			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1120	1130			
Water/Cement	6.25 Gal/SK						
Water Temp.	66°F						
Total Slurry Vol.	124.5	BBLS Cement					
Landed Plug @	800	PSI/Final Lift @	300	PSI			
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code	Sub Total			
Displace W/	50.0	BBLS H ₂ O	State CO 2.9%	Tax			
Circulate	5	BBLS Cement		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			
1216/1218		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVA, & ERNIE

Received By Keith R. Wolcott
Customer or His Agent