



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600032

Date	9-16-11	Well Owner	Kerr McGee	Well No.	22-11	Lease	PALYO
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #12)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	FL	848			
Surface	8 5/8" CSG-24A	Bottom of Surface	FL	838			
Plug		Plug Landed @	793	Fl.	Time On	1645	
Production		Pipe Landed @	838	Fl.	Plug Down	1930	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	530	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gal % Flo-Crete 1/4 # Per Sack	2048332 Drlg			
Mileage Charge	132	Miles		
Fuel Surcharge	800/2090	MOLES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1841	1846
Disp. Rate	5 BPM	Mixing	1846	1917
Slurry Vol.	1.32 Cu.Ft./Sk	Change Valves	1917	1920
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1920	1930
Water/Cement	6.25 Gal/SK			
Water Temp.	62 F			
Total Slurry Vol.	124.6	BBLS Cement		
Landed Plug @	800	PSI/Final Lift @	300	PSI
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	50.4	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		4/4			
1214/1217		Bulk Truck		4/4/4/4			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By Scott Hamrick
Customer or His Agent