

**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400229125

PluggingBond SuretyID

20060159

**APPLICATION FOR PERMIT TO:**

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling 

## Sidetrack

3. Name of Operator: BLACK RAVEN ENERGY INC 4. COGCC Operator Number: 10203
5. Address: 1331 17TH STREET - #350
- City: DENVER State: CO Zip: 80202
6. Contact Name: Janice Aldstadt Phone: (303)308-1330 Fax: (303)308-1590
- Email: jaldstadt@blackravenenergy.com
7. Well Name: Brinkema Well Number: 943-32-11
8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_
9. Proposed Total Measured Depth: 3000

## WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 32 Twp: 9N Rng: 43W Meridian: 6  
Latitude: 40.717290 Longitude: -102.167510

			FNL/FSL			FEL/FWL
Footage at Surface:	894	feet	FNL	837	feet	FWL

11. Field Name: AMHERST Field Number: 2480  
12. Ground Elevation: 3673 13. County: PHILLIPS

14. GPS Data:
- Date of Measurement: 11/19/2011 PDOP Reading: 2.1 Instrument Operator's Name: KEVIN MCCORMICK

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone:			Bottom Hole:		
Sec:	Twp:	Rng:	Sec:	Twp:	Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No
17. Distance to the nearest building, public road, above ground utility or railroad: 837 ft
18. Distance to nearest property line: 837 ft      19. Distance to nearest well permitted/completed in the same formation(BHL): 1772

20. **LEASE, SPACING AND POOLING INFORMATION**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_
22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian
23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_
- 23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No
- 23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T9N-R43W SECTION 32 - N/2

25. Distance to Nearest Mineral Lease Line: 837 ft

26. Total Acres in Lease: 320

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAP & BURIAL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	9+7/8	7+0/0	17	12	450	180	450	0
1ST	6+1/4	4+1/2	10.5	12	2,700	80	2,700	1,600

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. THE PERFORATED INTERVAL IS ESTIMATED TO BE SHALLOWER THAN 2500 FEET. Black Raven Energy is requesting Expedited Approval of Forms 2 & 2A (Rule 303.1) due to exigent circumstances and therefore has attached acopy of the surface owner waiver as part of this application.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: JANICE ALDSTADT

Title: LANDMAN

Date: 12/13/2011

Email: jaldstadt@blackravenenergy.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_

*David S. Neslin*

Director of COGCC

Date:

12/20/2011

#### API NUMBER

05 095 06402 00

Permit Number: \_\_\_\_\_

Expiration Date: 12/19/2013

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of spud to Jim Precup at 303-469-1902 or e-mail at james.precup@ state.co.us.
- 2) Set surface casing at least 50' into Pierre Shale for aquifer coverage, (450' minimum - as proposed).
- 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.

The perforated interval or completed interval must be shallower than 2500 feet in true vertical depth or the well must be 600 feet from a lease and 1200 feet from another well completed or approved in the same formation; unless the permit application contains an approved exception location. Per rule 318a.

### **Attachment Check List**

Att Doc Num	Name
2531572	VARIANCE REQUEST
2531607	WAIVERS
400229125	FORM 2 SUBMITTED
400231883	WELL LOCATION PLAT
400231885	TOPO MAP
400231903	WAIVERS

Total Attach: 6 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	No LGD or public comment received; final review completed.	12/19/2011 2:26:48 PM
Permit	Exigent variance approved to operator request 12/16/2011.	12/19/2011 2:25:05 PM
Permit	Operator input conductor pipe statement. This form has passed completeness.	12/14/2011 9:11:13 AM
Permit	Returned to draft. Missing conductor pipe statement.	12/14/2011 6:52:00 AM

Total: 4 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)