

FORM
5
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

DRILLING COMPLETION REPORT

Document Number:
400224522

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 100322 4. Contact Name: EILEEN ROBERTS
2. Name of Operator: NOBLE ENERGY INC Phone: (303) 2284330
3. Address: 1625 BROADWAY STE 2200 Fax: (303) 2284286
City: DENVER State: CO Zip: 80202

5. API Number 05-123-32977-00 6. County: WELD
7. Well Name: POWERS Well Number: X22-04
8. Location: QtrQtr: NWNW Section: 22 Township: 2N Range: 65W Meridian: 6
Footage at surface: Distance: 717 feet Direction: FNL Distance: 714 feet Direction: FWL
As Drilled Latitude: 40.129440 As Drilled Longitude: -104.657020

GPS Data:

Data of Measurement: 09/19/2011 PDOP Reading: 3.6 GPS Instrument Operator's Name: Paul Tappy

** If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

** If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

9. Field Name: WATTENBERG 10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 08/24/2011 13. Date TD: 08/27/2011 14. Date Casing Set or D&A: 08/28/2011

15. Well Classification:

Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 7850 TVD** 17 Plug Back Total Depth MD 7796 TVD**

18. Elevations GR 4881 KB 4894

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

GRL/CCL/CBL/VDL.

No open hole logs for this well.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24.00	0	905	386	0	905	VISU
1ST	7+7/8	4+1/2	11.60	0	7,838	495	6,482	7,838	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	5,950	700	1,844	5,954

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
NIOBRARA	6,810		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,170		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,192		<input type="checkbox"/>	<input type="checkbox"/>	
MOWRY	7,620		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,685		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts

Title: Regulatory Specialist Date: 11/18/2011 Email: eroberts@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
400224523	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Directional Survey **	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
400224522	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	REC LOGS DOC#1672014 , IN SCANNING	11/21/2011 2:37:27 PM
Permit	waiting on logs	11/18/2011 11:53:17 AM

Total: 2 comment(s)