

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400225171			
PluggingBond SuretyID 20010124			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120
5. Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-3779
6. Contact Name: Cheryl Light Phone: (720)929-6461 Fax: (720)929-7461
Email: cheryl.light@anadarko.com
7. Well Name: GOBLER Well Number: 37N-E22HZ
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 11854

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 22 Twp: 2N Rng: 66W Meridian: 6
Latitude: 40.129807 Longitude: -104.760978

Footage at Surface: 400 feet FNL/FSL 1980 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750
12. Ground Elevation: 5052 13. County: WELD

14. GPS Data:

Date of Measurement: 09/28/2011 PDOP Reading: 2.5 Instrument Operator's Name: CHRIS BOUB

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 620 FNL 1498 FEL 460 FSL 1498 FEL 460
Sec: 22 Twp: 2N Rng: 66W Sec: 22 Twp: 2N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 400 ft

18. Distance to nearest property line: 400 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1837 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		320	E/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SEE ATTACHED OIL AND GAS LEASE

25. Distance to Nearest Mineral Lease Line: 460 ft

26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	980	290	980	0
1ST	8+3/4	7+0/0	26	0	7,666	730	7,666	
1ST LINER	6+1/8	4+1/2	11.6	6601	11,854			

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used. A request letter and waiver (s) are attached to the Form 2's and Form 2A to request an exception location and twinning waiver. The wells are being placed at the locations described on the plats at the request of the surface owner.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: SR. REGULATORY ANALYST Date: 11/21/2011 Email: DJREGULATORY@

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 12/21/2011

API NUMBER

05 123 34827 00

Permit Number: _____ Expiration Date: 12/20/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Water sampling required. Ready to pass pending public comment 12/12/11.

No comment on the permit requesting exception or waivers.

- 1)Note surface casing setting depth change from 900' to 980'. Increase cement coverage accordingly and cement to surface.
- 2)Provide 24 hour notice of MIRU to Jim Precup via e-mail at jim.precup@state.co.us.
- 3)Comply with Rule 317.i and provide cement coverage from the end of the production casing to a minimum of 200' above the Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with a cement bond log.
- 4)Comply with Rule 321. Run and submit Directional Survey from the end of production casing to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
2481305	SURFACE CASING CHECK
400225171	FORM 2 SUBMITTED
400225232	DEVIATED DRILLING PLAN
400225233	PLAT
400225234	TOPO MAP
400225235	30 DAY NOTICE LETTER
400225236	SURFACE AGRMT/SURETY
400225237	OIL & GAS LEASE
400225238	PROPOSED SPACING UNIT
400225239	OTHER
400225737	EXCEPTION LOC REQUEST
400225738	EXCEPTION LOC WAIVERS

Total Attach: 12 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Comment added as directed by opr. Final review complete.	12/21/2011 10:02:07 AM
Permit	Final review complete.	12/19/2011 2:57:58 PM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>1. At least seven (7) days prior to fracture stimulation, the operator is to notify all operators of non-operated wells within 300 feet of the wellbore to be fracture stimulated of the anticipated date stimulation date and the recommended best management practice to shut-in all wells within 300' of the stimulated wellbore completed in the same formation.</p> <p>2. The operator will monitor the bradenhead pressure of all wells operated by the operator within 300 feet of the well to be fracture stimulated.</p> <p>3. Bradenhead pressure gauges are to be installed 24 hours prior to stimulation. The gauges are to read at least once during every 24-hour period until 24-hours after stimulation is completed (post flowback). The gauges are to be of the type able to read current pressure and record the maximum encountered pressure in a 24-hour period. The gauge is to be reset between each 24-hour period. The pressures are to be recorded and saved. Alternate electronic measurement may be used to record the prescribed pressures.</p> <p>4. If at any time during stimulation or the 24-hour post-stimulation period, the bradenhead annulus pressure of the treatment well or offset wells increases more than 200 psig, as per Rule 341, the operator of the well being stimulated shall verbally notify the Director as soon as practicable, but no later than twenty-four (24) hours following the incident. Within fifteen (15) days after the occurrence, the operator shall submit a Sundry Notice, Form 4, giving all details, including corrective actions taken.</p>

Total: 1 comment(s)