

FORM  
2

Rev  
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400225802			
PluggingBond SuretyID 20040060			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐  
Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION\* BILL 4. COGCC Operator Number: 10071  
5. Address: 1099 18TH ST STE 2300  
City: DENVER State: CO Zip: 80202  
6. Contact Name: Mary Pobuda Phone: (303)312-8511 Fax: (303)291-0420  
Email: mpobuda@billbarrettcorp.com  
7. Well Name: GGU Well Number: 24A-30-691  
8. Unit Name (if appl): Gibson Gulch II Unit Number: COC052447  
A  
9. Proposed Total Measured Depth: 7563

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 30 Twp: 6S Rng: 91W Meridian: 6  
Latitude: 39.492351 Longitude: -107.605515

Footage at Surface: 416 feet FNL/FSL 114 feet FEL/FWL  
FSL FWL

11. Field Name: MAMM CREEK Field Number: 52500  
12. Ground Elevation: 5929 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 10/12/2011 PDOP Reading: 6.0 Instrument Operator's Name: JAMES KALMON

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 150 FSL 1549 FWL 150 FSL 1549 FWL  
Bottom Hole: FNL/FSL 150 FSL 1549 FWL  
Sec: 30 Twp: 6S Rng: 91W Sec: 30 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No  
17. Distance to the nearest building, public road, above ground utility or railroad: 1200 ft  
18. Distance to nearest property line: 900 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 420 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	191-65		
WILLIAMS FORK	WMFK	191-9		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: CO10261

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attached lease map

25. Distance to Nearest Mineral Lease Line: 1186 ft

26. Total Acres in Lease: 1705

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAL & BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	14	36	0	40	0	40	0
SURF	12+1/4	9+5/8	36	0	722	230	722	0
1ST	7+7/8	4+1/2	11.6	0	7,563	780	7,563	3,113

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Mary Pobuda

Title: Permit Analyst Date: 11/21/2011 Email: mpobuda@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin

Director of COGCC Date: 12/21/2011

#### API NUMBER

05 045 21260 00

Permit Number: \_\_\_\_\_ Expiration Date: 12/20/2013

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY – PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDER NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010) -- IS REQUIRED. SEE ATTACHED NOTICE.

5) CEMENT ON PRODUCTION CASING MUST BE A MINIMUM OF 200' ABOVE THE TOP OF THE MESA VERDE FORMATION (OR 200' ABOVE THE OHIO CREEK FORMATION IF PRESENT). CEMENT TOP VERIFY BY CBL IS REQUIRED. THIS REQUIREMENT SHALL SUPERSEDE THE TOP OF CEMENT REQUIREMENTS IN THE NEW MAMM CREEK FIELD NOTICE TO OPERATORS.

6) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 210 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
2537679	SURFACE AGRMT/SURETY
400225802	FORM 2 SUBMITTED
400225808	WELL LOCATION PLAT
400225809	DEVIATED DRILLING PLAN
400225810	LEASE MAP
400225811	SURFACE AGRMT/SURETY

Total Attach: 6 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	LGD/public comments waived. Final Comprehensive Review Status--passed.	12/21/2011 1:43:18 PM
Permit	attached new SUA doc #2537679 per oper.'s email instructions.	11/30/2011 7:47:43 AM
Permit	changed spacing orders per oper.'s email instructions.	11/28/2011 1:56:21 PM

Total: 3 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)