

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400233208

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 28700

4. Contact Name: Jackie Davis

2. Name of Operator: EXXON MOBIL OIL CORPORATION

Phone: (281) 654-1913

3. Address: P O BOX 4358 WGR RM 310

Fax: (281) 654-1940

City: HOUSTON State: TX Zip: 77210-

5. API Number 05-103-11184-00

6. County: RIO BLANCO

7. Well Name: PICEANCE CREEK UNIT

Well Number: 197-36A5

8. Location: QtrQtr: NESW Section: 36 Township: 1S Range: 97W Meridian: 6

Footage at surface: Distance: 1849 feet Direction: FSL Distance: 2613 feet Direction: FWL

As Drilled Latitude: 39.918618 As Drilled Longitude: -108.229133

GPS Data:

Data of Measurement: 06/27/2011 PDOP Reading: 2.7 GPS Instrument Operator's Name: D. Slaugh

** If directional footage at Top of Prod. Zone Dist.: 1705 feet. Direction: FSL Dist.: 2564 feet. Direction: FWL

Sec: 36 Twp: 1S Rng: 97W

** If directional footage at Bottom Hole Dist.: 1266 feet. Direction: FSL Dist.: 2535 feet. Direction: FWL

Sec: 36 Twp: 1S Rng: 97W

9. Field Name: PICEANCE CREEK

10. Field Number: 68800

11. Federal, Indian or State Lease Number: COC035729

12. Spud Date: (when the 1st bit hit the dirt) 08/03/2010 13. Date TD: 08/29/2010 14. Date Casing Set or D&A: 09/03/2010

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 13620 TVD** 13612 17 Plug Back Total Depth MD 13529 TVD** 13521

18. Elevations GR 7084 KB 7114

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Mud, Reservoir Performance Monitor Gasview Saturation Analysis, Perform-Drilling Mechanics, (2) Reservoir Performance Monitor, (2) Radial Analysis Bond, Segmented Bond Gamma Ray.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	109	0	120	96	0	120	CALC
SURF	14+3/4	10+3/4	45.50	1553	3,752	1,030	1,553	3,769	CALC
1ST	9+7/8	7	26.00	0	9,208	1,310	3,750	9,208	CALC
2ND	6+1/8	4+1/2	15.10	0	13,618	968	4,250	13,620	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	SURF	1,553	1,090	0	1,553

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	5,970	6,320	<input type="checkbox"/>	<input type="checkbox"/>	
FORT UNION	6,320	7,869	<input type="checkbox"/>	<input type="checkbox"/>	
OHIO CREEK	7,869	8,093	<input type="checkbox"/>	<input type="checkbox"/>	
WILLIAMS FORK - CAMEO	8,093	12,274	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	12,274	12,448	<input type="checkbox"/>	<input type="checkbox"/>	
COZZETTE	12,448	12,762	<input type="checkbox"/>	<input type="checkbox"/>	
CORCORAN	12,762	13,620	<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

This Form 5 is being resubmitted to show corrected formation tops and bottoms.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jackie Davis

Title: Support Staff Tech Asst Date: 12/16/2011 Email: jackie.p.davis@exxonmobil.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
	CMT Summary *	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400233208	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)