



Hester #1 Herbicides and Reduced COGCC Table 910.1

ID	Conductivity (surface)	pH (surface)	SAR (surface)	2,4,5-T (surface) (µg/kg)	2,4-D (surface) (µg/kg)	2,4-DB (surface) (µg/kg)	Dinoseb (surface) (µg/kg)	Picloram (surface) (µg/kg)	MCP (surface) (µg/kg)	Diuron (surface) (µg/kg)
Fi 1 S	0.387	6.92	0.14	0	0	3.5	0	0	0	180
Fi 1 6	0.166	6.8	0.13	0	0	6.9	0	0	0	71
Fi 2 S	0.275	6.77	0.15	0	0	14	1.7	0	0	0
Fi 2 6	0.296	6.85	0.2	0	0	25	3.4	0	0	0
Fi 3 S	0.411	7.14	0.06	0	0	41	0	0	0	0
Fi 3 6	0.278	7.65	0.19	0	0	11	0	0	0	0
Fi 4 S	0.51	6.85	0.1	0	0	8.3	0	0	0	0
Fi 4 6	0.327	9.91	0.16	0	0	12	0	0	2300	0
Fo 1 S	0.27	6.82	0.16	0	0	0	0	2.7	0	40
Fo 1 6	0.152	6.92	0.19	0	0	0	0	2.2	0	0
Fo 2 S	0.428	6.96	0.14	0	0	11	0	2.9	0	0
Fo 2 6	0.367	6.81	0.22	0	0	30	0	2.1	0	0
Fo 3 S	0.226	6.62	0.07	0	0	14	0	3	0	0
Fo 3 6	0.245	7	0.14	0	0	19	0	2.1	0	0
Fo 4 S	0.728	7.17	0.3	0	0	12	0	0	0	0
Fo 4 6	0.702	7.29	0.3	0	0	8.1	0	2.8	0	0
P 1 S	1210	7.87	0.58	6.3	0	11	0	18	0	280
P 1 6	0.424	8.06	0.44	0	0	0	0	7.6	0	0
P 2 S	0.58	8.04	0.55	0	27	33	9.8	15	2500	1100
P 2 6	0.307	8.12	0.65	0	0	5.4	2.9	4.1	2800	0
P 3 S	0.583	8.06	0.32	0	29	14	10	3.4	2700	2000
P 3 6	0.374	7.76	0.45	0	0	5.4	1.6	0	0	61
P 4 S	1350	8	1.78	0	0	19	4.3	9.4	0	100
P 4 6	0.67	8.02	1.74	0	0	11	1.9	18	0	0
SE 1 S	0.285	6.67	0.9	0	0	16	0	1.7	0	300
SE 1 6	0.276	6.77	0.23	0	0	0	0	2.9	0	49
SE 2 S	0.321	7.36	0.09	0	0	0	0	0	0	220
SE 2 6	0.189	7.08	0.11	0	0	0	0	3.5	0	41
SE 3 S	0.377	7.89	0.3	3.9	0	24	0	4.1	0	710
SE 3 6	0.211	7.48	0.13	0	0	0	0	0	0	28

230,000 µg/kg

79,000
µg/kg5,500,000
µg/kg78,000
µg/kg160,000
µg/kg

(EPA Soil Ingestion
Regional Screening Levels)

Key: I = IRIS; P = PPRTV; A = ATSDR; C = Cal EPA; X = PPRTV Appendix; H = HEAST; J = New Jersey; Y = New York; O = EPA Office of Water; E = Environmental Criteria and Assessment Office; S = see user guide Section 5; L = see user guide on lead; M = mutagen; V = volatile; F = See FAQ; c = cancer; * = where: n SL < 100X c SL; ** = where n SL < 10X c SL; n = noncancer; m = Concentration may exceed ceiling limit (See User Guide); s = Concentration may exceed Csat (See User Guide); SSL values are based on DAF=1

Toxicity and Chemical-specific Information														Contaminant		Carcinogenic Target Risk (TR) = 1E-06				Noncancer Hazard Index (HI) = 1			
SFO (mg/kg-day) ⁻¹	k _e IUR (ug/m ³) ⁻¹	k _e Y	RfD _a (mg/kg-day)	k _e ₁ Y	RfC ₁ (mg/m ³)	k _e ₂ Y	mutagen	GIABS	ABS	C _{sat} (mg/kg)	PEF (m ³ /kg)	VF (m ³ /kg)	CAS No.	Analyte	Ingestion SL TR=1.0E-6 (mg/kg)	Dermal SL TR=1.0E-6 (mg/kg)	Inhalation SL TR=1.0E-6 (mg/kg)	Carcinogenic SL TR=1.0E-6 (mg/kg)	Ingestion SL HQ=1 (mg/kg)	Dermal SL HQ=1 (mg/kg)	Inhalation SL HQ=1 (mg/kg)	Noncarcinogenic SL HI=1 (mg/kg)	
8.0E-01	P	6.0E-03	P	2.0E-04	P	2.0E-04	I	V	M	1	1	0.1	9.8E+02	1.4E+09	3.4E+04	Dibromo-3-chloropropane, 1,2-	96-12-8	1.9E-01	5.5E-03	5.4E-03	1.6E+01	7.2E+00	4.9E+00
1.0E-02	I	2.7E-05	C	2.0E-02	I	2.0E-02	I	V		1	0.1	0.1	1.4E+09	Dibromobenzene, 1,4-	106-37-6				7.8E+02	2.8E+03	6.1E+02		
8.4E-02	I	2.7E-05	C	2.0E-02	I	2.0E-02	I	V		1	0.1	0.1	8.0E+02	Dibromochloromethane	124-48-1	7.6E+00	2.4E+01	7.7E-01	6.8E-01	1.6E+03	5.6E+03	1.2E+03	
2.0E+00	I	6.0E-04	I	9.0E-03	I	9.0E-03	I	V		1	1.3E+03	1.4E+09	9.3E+03	Dibromoethane, 1,2-	106-93-4	3.2E-01		3.8E-02	3.4E-02	7.0E+02	8.7E+01	7.8E+01	
				1.0E-02	H	4.0E-03	X	V		1	2.8E+03	1.4E+09	6.1E+03	Dibromomethane (Methylene Bromide)	74-95-3					7.8E+02	2.5E+01	2.5E+01	
				1.0E-01	I	1.0E-01	I	V		1	1.4E+09			Dibutyl Phthalate	84-74-2					7.8E+03	2.8E+04	6.1E+03	
				3.0E-04	P	3.0E-04	P			1	0.1	1.4E+09		Dibutyltin Compounds	NA					2.3E+01	8.4E+01	1.8E+01	
				3.0E-02	I	3.0E-02	I	V		1	0.1	1.4E+09		Dicamba	1918-00-9					2.3E+03	8.4E+03	1.8E+03	
				4.2E-03	P	4.2E-03	P			1	0.1	5.2E+02	1.4E+09	1.2E+04	Dichloro-2-butene, 1,4-	764-41-0		6.9E-03	6.9E-03				
				4.2E-03	P	4.2E-03	P			1	0.1	5.2E+02	1.4E+09	1.2E+04	Dichloro-2-butene, cis-1,4-	1476-11-5		6.9E-03	6.9E-03				
				4.2E-03	P	4.2E-03	P			1	0.1	7.6E+02	1.4E+09	1.2E+04	Dichloro-2-butene, trans-1,4-	110-57-6		6.9E-03	6.9E-03				
5.0E-02	I			4.0E-03	I	4.0E-03	I	V		1	0.1	1.4E+09		Dichloroacetic Acid	79-43-6	1.3E+01	4.0E+01		9.7E+00	3.1E+02	1.1E+03	2.4E+02	
				9.0E-02	I	2.0E-01	H	V		1	3.8E+02	1.4E+09	1.3E+04	Dichlorobenzene, 1,2-	95-50-1					7.0E+03	2.6E+03	1.9E+03	
5.4E-03	C	1.1E-05	C	7.0E-02	A	8.0E-01	I	V		1	1.4E+09	1.1E+04		Dichlorobenzene, 1,4-	106-46-7	1.2E+02	2.5E+00	2.4E+00	5.5E+03	9.4E+03	3.5E+03		
4.5E-01	I	3.4E-04	C							1	0.1	1.4E+09		Dichlorobenzidine, 3,3'-	91-94-1	1.4E+00	4.5E+00	9.7E+03	1.1E+00				
				9.0E-03	X	1.0E-01	X	V		1	0.1	1.4E+09		Dichlorobenzophenone, 4,4'-	90-98-2					7.0E+02	2.5E+03	5.5E+02	
5.7E-03	C	1.6E-06	C	2.0E-01	P	2.0E-01	P	V		1	8.5E+02	1.4E+09	9.1E+02	Dichlorodifluoromethane	75-71-8					1.6E+04	9.4E+01	9.4E+01	
				2.0E-01	P	2.0E-01	P	V		1	1.7E+03	1.4E+09	2.2E+03	Dichloroethane, 1,1-	75-34-3	1.1E+02	3.4E+00	3.3E+00		1.6E+04	1.6E+04		
9.1E-02	I	2.6E-05	I	6.0E-03	X	7.0E-03	P	V		1	3.0E+03	1.4E+09	4.9E+03	Dichloroethane, 1,2-	107-06-2	7.0E+00	4.6E-01	4.3E-01		4.7E+02	3.6E+01	3.3E+01	
				5.0E-02	I	2.0E-01	I	V		1	1.2E+03	1.4E+09	1.2E+03	Dichloroethylene, 1,1-	75-35-4					3.9E+03	2.6E+02	2.4E+02	
				9.0E-03	H			V		1	1.3E+03	1.4E+09	2.7E+03	Dichloroethylene, 1,2- (Mixed Isomers)	540-59-0					7.0E+02	7.0E+02		
				2.0E-03	I			V		1	2.4E+03	1.4E+09	2.7E+03	Dichloroethylene, 1,2-cis-	156-59-2					1.6E+02	1.6E+02		
				2.0E-02	I	6.0E-02	P	V		1	1.7E+03	1.4E+09	2.7E+03	Dichloroethylene, 1,2-trans-	156-60-5					1.6E+03	1.7E+02	1.5E+02	
				3.0E-03	I			V		1	1.4E+09			Dichlorophenol, 2,4-	120-83-2					2.3E+02	8.4E+02	1.8E+02	
				1.0E-02	I					1	0.05	1.4E+09		Dichlorophenoxy Acetic Acid, 2,4-	94-75-7					7.8E+02	5.6E+03	6.9E+02	
				8.0E-03	I					1	0.1	1.4E+09		Dichlorophenoxybutyric Acid, 4-(2,4-	94-82-6					6.3E+02	2.2E+03	4.9E+02	
3.6E-02	C	1.0E-05	C	9.0E-02	A	4.0E-03	I	V		1	1.4E+03	1.4E+09	4.1E+03	Dichloropropane, 1,2-	78-87-5	1.8E+01	9.9E-01	9.4E-01		7.0E+03	1.7E+01	1.7E+01	
				2.0E-02	P			V		1	1.5E+03	1.4E+09	7.3E+03	Dichloropropane, 1,3-	142-28-9					1.6E+03		1.6E+03	
				3.0E-03	I					1	0.1	1.4E+09		Dichloropropanol, 2,3-	616-23-9					2.3E+02	8.4E+02	1.8E+02	
1.0E-01	I	4.0E-06	I	3.0E-02	I	2.0E-02	I	V		1	1.6E+03	1.4E+09	3.8E+03	Dichloropropene, 1,3-	542-75-6	6.4E+00	2.3E+00	1.7E+00		2.3E+03	8.0E+01	7.7E+01	
2.9E-01	I	8.3E-05	C	5.0E-04	I	5.0E-04	I	V		1	0.1	1.4E+09		Dichlorvos	62-73-7	2.2E+00	7.0E+00	4.0E+04	1.7E+00	3.9E+01	1.4E+02	7.1E+05	
				8.0E-03	P	7.0E-03	P	V		1	1.3E+02	1.4E+09	4.4E+03	Dicyclopentadiene	77-73-6					6.3E+02	3.2E+01	3.1E+01	
1.6E+01	I	4.6E-03	I	5.0E-05	I					1	0.1	1.4E+09		Dieldrin	60-57-1	4.0E-02	1.3E-01	7.2E+02	3.0E-02	3.9E+00	1.4E+01	3.1E+00	
				3.0E-04	C	5.0E-03	I			1	0.1	1.4E+09		Diesel Engine Exhaust	NA								
				8.0E-01	I	3.0E-03	C			1	0.1	1.4E+09		Diethanolamine	111-42-2					6.3E+04	2.2E+05	4.3E+06	
				3.0E-02	P	1.0E-04	P			1	0.1	1.4E+09		Diethyl Phthalate	84-66-2							4.9E+04	
				6.0E-02	P	3.0E-04	P			1	0.1	1.4E+09		Diethylene Glycol Monobutyl Ether	112-34-5					2.3E+03	8.4E+03	1.4E+05	
				1.0E-03	P					1	0.1	1.4E+09		Diethylene Glycol Monoethyl Ether	111-90-0					4.7E+03	1.7E+04	4.3E+05	
										1	0.1	1.4E+09		Diethylformamide	617-84-5					7.8E+01	2.8E+02	6.1E+01	
3.5E+02	C	1.0E-01	C							1	0.1	1.4E+09		Diethylstilbestrol	56-53-1	1.8E-03	5.8E-03	3.3E+01	1.4E-03				
				8.0E-02	I					1	0.1	1.4E+09		Difenoquat	43222-48-6					6.3E+03	2.2E+04	4.9E+03	
				2.0E-02	I					1	0.1	1.4E+09		Diffubenzuron	35367-38-5					1.6E+03	5.6E+03	1.2E+03	
4.4E-02	C	1.3E-05	C			4.0E+01	I	V		1	0.1	1.4E+09	1.2E+03	Diffuoroethane, 1,1-	75-37-6	1.5E+01	4.6E+01	2.5E+05	1.1E+01		5.2E+04	5.2E+04	
				7.0E-01	P	V				1	2.3E+03	1.4E+09	3.3E+03	Dihydrosafrole	94-58-6							2.4E+03	
										1	0.1	1.4E+09		Diisopropyl Ether	108-20-3							2.4E+03	
				8.0E-02	I			V		1	5.3E+02	1.4E+09	3.1E+04	Diisopropyl Methylphosphonate	1445-75-6					6.3E+03		6.3E+03	
				2.0E-02	I					1	0.1	1.4E+09		Dimethipin	55290-64-7					1.6E+03	5.6E+03	1.2E+03	
				2.0E-04	I					1	0.1	1.4E+09		Dimethoate	60-51-5					1.6E+01	5.6E+01	1.2E+01	
1.4E-02	H									1	0.1	1.4E+09		Dimethoxybenzidine, 3,3'-	119-90-4	4.6E+01	1.4E+02		3.5E+01				
1.7E-03	P			6.0E-02	P					1	0.1	1.4E+09		Dimethyl methylphosphonate	756-79-6				2.9E+02	4.7E+03	1.7E+04	3.7E+03	
4.6E+00	C	1.3E-03	C							1	0.1	1.4E+09		Dimethylamino azobenzene [p-]	60-11-7	1.4E-01	4.4E-01	2.5E+03	1.1E-01				
5.8E-01	H									1	0.1	1.4E+09		Dimethylaniline HCl, 2,4-	21436-96-4	1.1E+00	3.5E+00		8.4E-01				
2.0E-01	P			2.0E-03	X					1	0.1	1.4E+09		Dimethylaniline, 2,4-	95-68-1	3.2E+00	1.0E+01		2.4E+00	1.6E+02	5.6E+02	1.2E+02	
				2.0E-03	I			V		1	8.3E+02	1.4E+09	3.4E+04	Dimethylaniline, N,N-	121-69-7					1.6E+02		1.6E+02	
1.1E+01	P									1	0.1	1.4E+09		Dimethylbenzidine, 3,3'-	119-93-7	5.8E-02	1.8E-01		4.4E-02				
				1.0E-01	P	3.0E-02	I			1	0.1	1.4E+09		Dimethylformamide	68-12-2					7.8E+03	2.8E+04	4.3E+07	
				1.0E-04	X	2.0E-06	X			1	0.1	1.4E+09		Dimethylhydrazine, 1,1-	57-14-7					7.8E+00	2.8E+01	2.8E+03	
5.5E+02	C	1.6E-01	C							1	0.1	1.4E+09		Dimethylhydrazine, 1,2-	540-73-8	1.2E-03	3.7E-03	2.1E+01	8.8E-04				
				2.0E-02	I					1	0.1	1.4E+09		Dimethylphenol, 2,4-	105-67-9					1.6E+03	5.6E+03	1.2E+03	
				6.0E-04	I					1	0.1	1.4E+09		Dimethylphenol, 2,6-	576-26-1					4.7E+01	1.7E+02	3.7E+01	
				1.0E-03	I					1	0.1	1.4E+09		Dimethylphenol, 3,4-	95-65-8					7.8E+01	2.8E+02	6.1E+01	
				1.0E-01	I			V		1	5.5E+00	1.4E+09	2.3E+04	Dimethylterephthalate	120-61-6					7.8E+03		7.8E+03	
4.5E-02	C	1.3E-05	C							1	0.1	1.4E+09		Dimethylvinylchloride	513-37-1	1.4E+01	4.5E+01	2.5E+05	1.1E+01				
				8.0E-05	X					1	0.1	1.4E+09		Dinitro-o-cresol, 4,6-									

Toxicity and Chemical-specific Information														Contaminant		Carcinogenic Target Risk (TR) = 1E-06				Noncancer Hazard Index (HI) = 1				
SFO (mg/kg-day) ⁻¹	k _e (μg/m ³) ⁻¹	IUR (μg/m ³) ⁻¹	k _e (mg/kg-day)	RfD _a (mg/kg-day)	k _e (mg/m ³)	RfC _i (mg/m ³)	k _e (mg/m ³)	mutagen	GIAB5	ABS	C _{sat} (mg/kg)	PEF (m ³ /kg)	VF (m ³ /kg)	Analyte	CAS No.	Ingestion SL TR=1.0E-6 (mg/kg)	Dermal SL TR=1.0E-6 (mg/kg)	Inhalation SL TR=1.0E-6 (mg/kg)	Carcinogenic SL TR=1.0E-6 (mg/kg)	Ingestion SL HQ=1 (mg/kg)	Dermal SL HQ=1 (mg/kg)	Inhalation SL HQ=1 (mg/kg)	Noncarcinogenic SL HI=1 (mg/kg)	
			1.0E-04	P					1	0.1	1.4E+09			Dinitrobenzene, 1,2-	528-29-0					7.8E+00	2.8E+01		6.1E+00	
			1.0E-04	I					1	0.1	1.4E+09			Dinitrobenzene, 1,3-	99-65-0					7.8E+00	2.8E+01		6.1E+00	
			1.0E-04	P					1	0.1	1.4E+09			Dinitrobenzene, 1,4-	100-25-4					7.8E+00	2.8E+01		6.1E+00	
			2.0E-03	I					1	0.1	1.4E+09			Dinitrophenol, 2,4-	51-28-5					1.6E+02	5.6E+02		1.2E+02	
6.8E-01	I								1	0.1	1.4E+09			Dinitrotoluene Mixture, 2,4/2,6-	25321-14-6	9.4E-01	3.0E+00		7.2E-01					
3.1E-01	C	8.9E-05	C	2.0E-03	I				1	0.102	1.4E+09			Dinitrotoluene, 2,4-	121-14-2	2.1E+00	6.4E+00	3.7E+04	1.6E+00	1.6E+02	5.5E+02		1.2E+02	
			1.0E-03	P					1	0.099	1.4E+09			Dinitrotoluene, 2,6-	606-20-2					7.8E+01	2.8E+02		6.1E+01	
			2.0E-03	S					1	0.006	1.4E+09			Dinitrotoluene, 2-Amino-4,6-	35572-78-2					1.6E+02	9.3E+03		1.5E+02	
			2.0E-03	S					1	0.009	1.4E+09			Dinitrotoluene, 4-Amino-2,6-	19406-51-0					1.6E+02	6.2E+03		1.5E+02	
			1.0E-03	I					1	0.1	1.4E+09			Dinoseb	88-85-7					7.8E+01	2.8E+02		6.1E+01	
1.0E-01	I	7.7E-06	C	3.0E-02	I	3.0E+00	C		1	0.1	1.4E+09			Dioxane, 1,4-	123-91-1	6.4E+00	2.0E+01	4.3E+05	4.9E+00	2.3E+03	8.4E+03	4.3E+09	1.8E+03	
6.2E+03	I	1.3E+00	I						1	0.03	1.4E+09			Dioxins										
1.3E+05	C	3.8E+01	C	1.0E-09	A	4.0E-08	C		1	0.03	1.4E+09			*Hexachlorodibenzo-p-dioxin, Mixture	NA	1.0E-04	1.1E-03	2.5E+00	9.4E-05					
			3.0E-02	I					1	0.1	1.4E+09			*TCDD, 2,3,7,8-	1746-01-6	4.9E-06	5.2E-05	8.7E-02	4.5E-06	7.8E-05	9.3E-04	5.7E+01	7.2E-05	
			8.0E-04	X					1	0.1	1.4E+09			Diphenamid	957-51-7					2.3E+03	8.4E+03		1.8E+03	
									1	0.1	1.4E+09			Diphenyl Sulfone	127-63-9					6.3E+01	2.2E+02		4.9E+01	
			2.5E-02	I					1	0.1	1.4E+09			Diphenylamine	122-39-4					2.0E+03	7.0E+03		1.5E+03	
8.0E-01	I	2.2E-04	I						1	0.1	1.4E+09			Diphenylhydrazine, 1,2-Diquat	122-66-7	8.0E-01	2.5E+00	1.5E+04	6.1E-01					
			2.2E-03	I					1	0.1	1.4E+09				85-00-7					1.7E+02	6.1E+02		1.3E+02	
7.4E+00	C	2.1E-03	C						1	0.1	1.4E+09			Direct Black 38	1937-37-7	8.7E-02	2.7E-01	1.6E+03	6.6E-02					
7.4E+00	C	2.1E-03	C						1	0.1	1.4E+09			Direct Blue 6	2602-46-2	8.7E-02	2.7E-01	1.6E+03	6.6E-02					
6.7E+00	C	1.9E-03	C						1	0.1	1.4E+09			Direct Brown 95	16071-86-6	9.6E-02	3.0E-01	1.7E+03	7.3E-02					
			4.0E-05	I					1	0.1	1.4E+09			Disulfoton	298-04-4					3.1E+00	1.1E+01		2.4E+00	
			1.0E-02	I					1	0.1	1.4E+09			Dithiane, 1,4-	505-29-3					7.8E+02	2.8E+03		6.1E+02	
			2.0E-03	I					1	0.1	1.4E+09			Duron	330-54-1					1.6E+02	5.6E+02		1.2E+02	
			4.0E-03	I					1	0.1	1.4E+09			Dodine	2439-10-3					3.1E+02	1.1E+03		2.4E+02	
			2.5E-02	I				V	1		4.1E+02	1.4E+09	1.3E+05	EPTC	759-94-4					2.0E+03			2.0E+03	
			6.0E-03	I					1	0.1	1.4E+09			Endosulfan	115-29-7					4.7E+02	1.7E+03		3.7E+02	
			2.0E-02	I					1	0.1	1.4E+09			Endothall	145-73-3					1.6E+03	5.6E+03		1.2E+03	
			3.0E-04	I					1	0.1	1.4E+09			Endrin	72-20-8					2.3E+01	8.4E+01		1.8E+01	
9.9E-03	I	1.2E-06	I	6.0E-03	P	1.0E-03	I	V	1		1.1E+04	1.4E+09	2.0E+04	Epichlorohydrin	106-89-8	6.5E+01		4.1E+01	2.5E+01	4.7E+02		2.1E+01		2.0E+01
			2.0E-02	I	V				1		1.5E+04	1.4E+09	8.2E+03	Epoxybutane, 1,2-	106-88-7							1.7E+02	1.7E+02	
			5.0E-03	I					1	0.1	1.4E+09			Ethephon	16672-87-0					3.9E+02	1.4E+03		3.1E+02	
			5.0E-04	I					1	0.1	1.4E+09			Ethion	563-12-2					3.9E+01	1.4E+02		3.1E+01	
			1.0E-01	P	6.0E-02	P			1	0.1	1.4E+09			Ethoxyethanol Acetate, 2-	111-15-9					7.8E+03	2.8E+04	8.5E+07	6.1E+03	
			4.0E-01	H	2.0E-01	I			1	0.1	1.4E+09			Ethoxyethanol, 2-	110-80-5					3.1E+04	1.1E+05	2.8E+08	2.4E+04	
			9.0E-01	I			V		1		1.1E+04	1.4E+09	9.3E+03	Ethyl Acetate	141-78-6					7.0E+04			7.0E+04	
4.8E-02	H						V		1		2.5E+03	1.4E+09	6.8E+03	Ethyl Acrylate	140-88-5	1.3E+01			1.3E+01					
			1.0E+01	I	V				1		2.1E+03	1.4E+09	1.4E+03	Ethyl Chloride	75-00-3							1.5E+04	1.5E+04	
			2.0E-01	I		V			1		1.0E+04	1.4E+09	3.4E+03	Ethyl Ether	60-29-7					1.6E+04			1.6E+04	
			9.0E-02	H	3.0E-01	P	V		1		1.1E+03	1.4E+09	6.2E+03	Ethyl Methacrylate	97-63-2					7.0E+03		1.9E+03	1.5E+03	
			1.0E-05	I					1	0.1	1.4E+09			Ethyl-p-nitrophenyl Phosphonate	2104-64-5					7.8E-01	2.8E+00		6.1E-01	
1.1E-02	C	2.5E-06	C	1.0E-01	I	1.0E+00	I	V	1		4.8E+02	1.4E+09	6.1E+03	Ethylbenzene	100-41-4	5.8E+01		5.9E+00	5.4E+00	7.8E+03		6.4E+03	3.5E+03	
			3.0E-02	P					1	0.1	1.4E+09			Ethylene Cyanohydrin	109-78-4					2.3E+03	8.4E+03		1.8E+03	
			9.0E-02	P					1	0.1	1.4E+09			Ethylene Diamine	107-15-3					7.0E+03	2.5E+04		5.5E+03	
			2.0E+00	I	4.0E-01	C			1	0.1	1.4E+09			Ethylene Glycol	107-21-1					1.6E+05	5.6E+05	5.7E+08	1.2E+05	
			1.0E-01	I	1.6E+00	I			1	0.1	1.4E+09			Ethylene Glycol Monobutyl Ether	111-76-2					7.8E+03	2.8E+04	2.3E+09	6.1E+03	
3.1E-01	C	8.8E-05	C						1		1.2E+05	1.4E+09	6.6E+03	Ethylene Oxide	75-21-8	2.1E+00		1.8E-01	1.7E-01			2.0E+02	2.0E+02	
4.5E-02	C	1.3E-05	C	8.0E-05	I				1	0.1	1.4E+09			Ethylene Thiourea	96-45-7	1.4E+01	4.5E+01	2.5E+05	1.1E+01	6.3E+00	2.2E+01		4.9E+00	
6.5E+01	C	1.9E-02	C						1	0.1	1.4E+09			Ethyleneimine	151-56-4									
			3.0E+00	I					1	0.1	1.4E+09			Ethylphthalyl Ethyl Glycolate	84-72-0					2.3E+05	8.4E+05		1.8E+05	
			8.0E-03	I					1	0.1	1.4E+09			Express	101200-48-0					6.3E+02	2.2E+03		4.9E+02	
			2.5E-04	I					1	0.1	1.4E+09			Fenamiphos	22224-92-6					2.0E+01	7.0E+01		1.5E+01	
			2.5E-02	I					1	0.1	1.4E+09			Fenpropathrin	39515-41-8					2.0E+03	7.0E+03		1.5E+03	
			1.3E-02	I					1	0.1	1.4E+09			Fluometuron	2164-17-2					1.0E+03	3.6E+03		7.9E+02	
			4.0E-02	C	1.3																			

Key: I = IRIS; P = PPRTV; A = ATSDR; C = Cal EPA; X = PPRTV Appendix; H = HEAST; J = New Jersey; Y = New York; O = EPA Office of Water; E = Environmental Criteria and Assessment Office; S = see user guide Section 5; L = see user guide on lead; M = mutagen; V = volatile; F = See FAQ; c = cancer; * = where: n SL < 100X c SL; ** = where n SL < 10X c SL; n = noncancer; m = Concentration may exceed ceiling limit (See User Guide); s = Concentration may exceed Csat (See User Guide); SSL values are based on DAF=1																								
Toxicity and Chemical-specific Information														Contaminant		Carcinogenic Target Risk (TR) = 1E-06				Noncancer Hazard Index (HI) = 1				
SFO (mg/kg-day) ⁻¹	k e y	IUR (ug/m ³) ⁻¹	k e y	RfD _a (mg/kg-day)	k e y	RfC _i (mg/m ³)	k e y	muta- gen	GIABS	ABS	C _{sat} (mg/kg)	PEF (m ³ /kg)	VF (m ³ /kg)	Analyte	CAS No.	Ingestion SL TR=1.0E-6 (mg/kg)	Dermal SL TR=1.0E-6 (mg/kg)	Inhalation SL TR=1.0E-6 (mg/kg)	Carcinogenic SL TR=1.0E-6 (mg/kg)	Ingestion SL HQ=1 (mg/kg)	Dermal SL HQ=1 (mg/kg)	Inhalation SL HQ=1 (mg/kg)	Noncarcinogenic SL HI=1 (mg/kg)	
				1.0E-02	I				1	0.1	1.4E+09			MCPB	94-81-5					7.8E+02	2.8E+03		6.1E+02	
				1.0E-03	I				1	0.1	1.4E+09			MCPB	93-65-2					7.8E+01	2.8E+02		6.1E+01	
				2.0E-02	I				1	0.1	1.4E+09			Malathion	121-75-5					1.6E+03	5.6E+03		1.2E+03	
				1.0E-01	I	7.0E-04	C		1	0.1	1.4E+09			Maleic Anhydride	108-31-6					7.8E+03	2.8E+04	9.9E+05	6.1E+03	
				5.0E-01	I				1	0.1	1.4E+09			Maleic Hydrazide	123-33-1					3.9E+04	1.4E+05		3.1E+04	
				1.0E-04	P				1	0.1	1.4E+09			Malononitrile	109-77-3					7.8E+00	2.8E+01		6.1E+00	
				3.0E-02	H				1	0.1	1.4E+09			Mancozeb	8018-01-7					2.3E+03	8.4E+03		1.8E+03	
				5.0E-03	I				1	0.1	1.4E+09			Maneb	12427-38-2					3.9E+02	1.4E+03		3.1E+02	
				1.4E-01	I	5.0E-05	I		1					Manganese (Diet)	7439-96-5									
				2.4E-02	S	5.0E-05	I		0.04		1.4E+09			Manganese (Non-diet)	7439-96-5					1.9E+03		7.1E+04	1.8E+03	
				9.0E-05	H				1	0.1	1.4E+09			Mephosfolan	950-10-7					7.0E+00	2.5E+01		5.5E+00	
				3.0E-02	I				1	0.1	1.4E+09			Mepiquat Chloride	24307-26-4					2.3E+03	8.4E+03		1.8E+03	
				3.0E-04	I	3.0E-05	C		0.07		1.4E+09			Mercury Compounds										
						3.0E-04	I V		1		3.1E+00	1.4E+09	3.2E+04	*Mercuric Chloride (and other Mercury salts)	7487-94-7					2.3E+01		4.3E+04	2.3E+01	
														*Mercury (elemental)	7439-97-6							1.0E+01	1.0E+01	
				1.0E-04	I				1		1.4E+09			*Methyl Mercury	22967-92-6					7.8E+00			7.8E+00	
				8.0E-05	I				1	0.1	1.4E+09			*Phenylmercuric Acetate	62-38-4					6.3E+00	2.2E+01		4.9E+00	
				3.0E-05	I				1	0.1	1.4E+09			Merphos	150-50-5					2.3E+00	8.4E+00		1.8E+00	
				3.0E-05	I				1	0.1	1.4E+09			Merphos Oxide	78-48-8					2.3E+00	8.4E+00		1.8E+00	
				6.0E-02	I				1	0.1	1.4E+09			Metalaxyl	57837-19-1					4.7E+03	1.7E+04		3.7E+03	
				1.0E-04	I	7.0E-04	H V		1		4.6E+03	1.4E+09	7.3E+03	Methacrylonitrile	126-98-7					7.8E+00		5.3E+00	3.2E+00	
				5.0E-05	I				1	0.1	1.4E+09			Methamidophos	10265-92-6					3.9E+00	1.4E+01		3.1E+00	
				5.0E-01	I	4.0E+00	C		1	0.1	1.4E+09			Methanol	67-56-1					3.9E+04	1.4E+05	5.7E+09	3.1E+04	
				1.0E-03	I				1	0.1	1.4E+09			Methidathion	950-37-8					7.8E+01	2.8E+02		6.1E+01	
4.9E-02	C	1.4E-05	C	2.5E-02	I				1	0.1	1.4E+09			Methomyl	16752-77-5					2.0E+03	7.0E+03		1.5E+03	
				5.0E-03	I				1	0.1	1.4E+09			Methoxy-5-nitroaniline, 2-Methoxychlor	99-59-2	1.3E+01	4.1E+01	2.4E+05	9.9E+00					
									1	0.1	1.4E+09				72-43-5					3.9E+02	1.4E+03		3.1E+02	
				8.0E-03	P	1.0E-03	P		1	0.1	1.4E+09			Methoxyethanol Acetate, 2-Methoxyethanol, 2-Methyl Acetate	110-49-6					6.3E+02	2.2E+03	1.4E+06	4.9E+02	
				5.0E-03	P	2.0E-02	I		1	0.1	1.4E+09				109-86-4					3.9E+02	1.4E+03	2.8E+07	3.1E+02	
				1.0E+00	X		V		1		2.9E+04	1.4E+09	8.7E+03		79-20-9				7.8E+04			7.8E+04		
				3.0E-02	H		V		1		6.8E+03	1.4E+09	7.5E+03	Methyl Acrylate	96-33-3					2.3E+03			2.3E+03	
				6.0E-01	I	5.0E+00	I V		1		2.8E+04	1.4E+09	1.3E+04	Methyl Ethyl Ketone (2-Butanone)	78-93-3					4.7E+04		6.8E+04	2.8E+04	
1.0E-03	X			1.0E-03	P	2.0E-05	X		1	0.1	1.4E+09			Methyl Hydrazine	60-34-4			3.3E+03	3.3E+03	7.8E+01	2.8E+02	2.8E+04	6.1E+01	
				8.0E-02	H	3.0E+00	I V		1		3.4E+03	1.4E+09	1.1E+04	Methyl Isobutyl Ketone (4-methyl-2-pentanone)	108-10-1					6.3E+03		3.6E+04	5.3E+03	
						1.0E-03	C		1	0.1	1.4E+09			Methyl Isocyanate	624-83-9							1.4E+06	1.4E+06	
				1.4E+00	I	7.0E-01	I V		1		2.4E+03	1.4E+09	6.8E+03	Methyl Methacrylate	80-62-6					1.1E+05		5.0E+03	4.8E+03	
				2.5E-04	I				1	0.1	1.4E+09			Methyl Parathion	298-00-0					2.0E+01	7.0E+01		1.5E+01	
				6.0E-02	X				1	0.1	1.4E+09			Methyl Phosphonic Acid	993-13-5					4.7E+03	1.7E+04		3.7E+03	
				6.0E-03	H	4.0E-02	H V		1		3.8E+02	1.4E+09	1.2E+04	Methyl Styrene (Mixed Isomers)	25013-15-4					4.7E+02		5.1E+02	2.5E+02	
9.9E-02	C	2.8E-05	C						1	0.1	1.4E+09			Methyl methanesulfonate	66-27-3	6.5E+00	2.0E+01	1.2E+05	4.9E+00					
1.8E-03	C	2.6E-07	C			3.0E+00	I V		1		8.9E+03	1.4E+09	5.3E+03	Methyl tert-Butyl Ether (MTBE)	1634-04-4	3.6E+02		4.9E+01	4.3E+01			1.7E+04	1.7E+04	
				2.0E-04	X				1	0.1	1.4E+09			Methyl-1,4-benzenediamine dihydrochloride, 2-Methyl-5-Nitroaniline, 2-Methyl-N-nitro-N-nitrosoguanidine, N-Methylaniline Hydrochloride, 2-Methylarsonic acid	615-45-2					1.6E+01	5.6E+01		1.2E+01	
9.0E-03	P			2.0E-02	X				1	0.1	1.4E+09				99-55-8	7.1E+01	2.2E+02		5.4E+01	1.6E+03	5.6E+03		1.2E+03	
8.3E+00	C	2.4E-03	C						1	0.1	1.4E+09				70-25-7	7.7E-02	2.4E-01	1.4E+03	5.9E-02					
1.3E-01	C	3.7E-05	C						1	0.1	1.4E+09				636-21-5	4.9E+00	1.6E+01	8.9E+04	3.7E+00					
				1.0E-02	A				1	0.1	1.4E+09			Methylarsonic acid	124-58-3					7.8E+02	2.8E+03		6.1E+02	
				2.0E-04	X				1	0.1	1.4E+09			Methylbenzene,1,4-diamine monohydrochloride, 2-Methylbenzene-1,4-diamine sulfate, 2-Methylcholanthrene, 3-Methylene Chloride	74612-12-7					1.6E+01	5.6E+01		1.2E+01	
				2.0E-04	X				1	0.1	1.4E+09				615-50-9					1.6E+01	5.6E+01		1.2E+01	
2.2E+01	C	6.3E-03	C					M	1	0.1	1.4E+09				56-49-5	6.8E-03	2.3E-02	2.1E+02	5.2E-03					
7.5E-03	I	4.7E-07	I	6.0E-02	I	1.0E+00	A V		1		3.3E+03	1.4E+09	2.4E+03		75-09-2	8.5E+01		1.2E+01	1.1E+01	4.7E+03		2.6E+03	1.7E+03	
1.0E-01	P	4.3E-04	C	2.0E-03	P			M	1	0.1	1.4E+09			Methylene-bis(2-chloroaniline), 4,4'-Methylene-bis(N,N-dimethyl) Aniline, 4,4'-Methylenebisbenzenamine, 4,4'-Methylenediphenyl Diisocyanate	101-14-4	1.5E+00	5.1E+00	3.0E+03	1.2E+00	1.6E+02	5.6E+02		1.2E+02	
4.6E-02	I	1.3E-05	C						1	0.1	1.4E+09				101-61-1	1.4E+01	4.4E+01	2.5E+05	1.1E+01					
1.6E+00	C	4.6E-04	C			2.0E-02	C		1	0.1	1.4E+09				101-77-9	4.0E-01	1.3E+00	7.2E+03	3.0E-01			2.8E+07	2.8E+07	
				6.0E-04	I				1	0.1	1.4E+09				101-68-8							8.5E+05	8.5E+05	
				7.0E-02	H			V	1		5.0E+02	1.4E+09	1.4E+04	Methylstyrene, Alpha-Metolachlor	98-83-9					5.5E+03			5.5E+03	
				1.5E-01	I				1	0.1	1.4E+09				5121									

Toxicity and Chemical-specific Information															Contaminant		Carcinogenic Target Risk (TR) = 1E-06				Noncancer Hazard Index (HI) = 1			
SFO (mg/kg-day) ⁻¹	k _e y	IUR (ug/m ³) ⁻¹	k _e y	RfD _o (mg/kg-day)	k _e y	RfC _o (mg/m ³)	k _e y	V _o c	muta- gen	GIABS	ABS	C _{soil} (mg/kg)	PEF (m ³ /kg)	VF (m ³ /kg)	Analyte	CAS No.	Ingestion SL TR=1.0E-6 (mg/kg)	Dermal SL TR=1.0E-6 (mg/kg)	Inhalation SL TR=1.0E-6 (mg/kg)	Carcinogenic SL TR=1.0E-6 (mg/kg)	Ingestion SL HQ=1 (mg/kg)	Dermal SL HQ=1 (mg/kg)	Inhalation SL HQ=1 (mg/kg)	Noncarcinogenic SL HI=1 (mg/kg)
				2.5E-01	I					1	0.1	1.4E+09			Phenmedipham	13684-63-4					2.0E+04	7.0E+04		1.5E+04
				3.0E-01	I	2.0E-01	C			1	0.1	1.4E+09			Phenol	108-95-2					2.3E+04	8.4E+04	2.8E+08	1.8E+04
				5.0E-04	X					1	0.1	1.4E+09			Phenothiazine	92-84-2					3.9E+01	1.4E+02		3.1E+01
4.7E-02	H			6.0E-03	I					1	0.1	1.4E+09			Phenylenediamine, m- Phenylenediamine, o-	108-45-2 95-54-5	1.4E+01	4.3E+01		1.0E+01	4.7E+02	1.7E+03		3.7E+02
				1.9E-01	H					1	0.1	1.4E+09			Phenylenediamine, p-	106-50-3					1.5E+04	5.3E+04		1.2E+04
1.9E-03	H			2.0E-04	H					1	0.1	1.4E+09			Phenylphenol, 2- Phorate	90-43-7 298-02-2	3.3E+02	1.0E+03		2.5E+02	1.6E+01	5.6E+01		1.2E+01
				3.0E-04	I	V				1		1.6E+03	1.4E+09	1.1E+03	Phosgene	75-44-5							3.3E-01	3.3E-01
				2.0E-02	I					1	0.1	1.4E+09			Phosmet Phosphates, Inorganic	732-11-6					1.6E+03	5.6E+03		1.2E+03
				4.9E+01	P					1		1.4E+09			~Aluminum metaphosphate	13776-88-0					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Ammonium polyphosphate	68333-79-9					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Calcium pyrophosphate	7790-76-3					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Diammonium phosphate	7783-28-0					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Dicalcium phosphate	7757-93-9					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Dimagnesium phosphate	7782-75-4					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Dipotassium phosphate	7758-11-4					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Disodium phosphate	7558-79-4					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Monoaluminum phosphate	13530-50-2					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Monoammonium phosphate	7722-76-1					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Monocalcium phosphate	7758-23-8					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Monomagnesium phosphate	7757-86-0					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Monopotassium phosphate	7778-77-0					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Monosodium phosphate	7558-80-7					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Polyphosphoric acid	8017-16-1					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Potassium triphosphate	13845-36-8					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Sodium acid pyrophosphate	7758-16-9					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Sodium aluminum phosphate (acidic)	7785-88-8					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Sodium aluminum phosphate (anhydrous)	10279-59-1					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Sodium aluminum phosphate (tetrahydrate)	10305-76-7					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Sodium hexametaphosphate	10124-56-8					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Sodium polyphosphate	68915-31-1					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Sodium trimetaphosphate	7785-84-4					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Sodium tripolyphosphate	7758-29-4					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Tetrapotassium phosphate	7320-34-5					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Tetrasodium pyrophosphate	7722-88-5					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Trialuminum sodium tetra decahydrogenoctaorthophosphate (dihydrate)	15136-87-5					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Tricalcium phosphate	7758-87-4					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Trimagnesium phosphate	7757-87-1					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Tripotassium phosphate	7778-53-2					3.8E+06			3.8E+06
				4.9E+01	P					1		1.4E+09			~Trisodium phosphate	7601-54-9					3.8E+06			3.8E+06
				3.0E-04	I	3.0E-04	I			1		1.4E+09			Phosphine	7803-51-2					2.3E+01		4.3E+05	2.3E+01
				4.9E+01	P	1.0E-02	I			1		1.4E+09			Phosphoric Acid	7664-38-2					3.8E+06		1.4E+07	3.0E+06
				2.0E-05	I					1		1.4E+09			Phosphorus, White	7723-14-0					1.6E+00			1.6E+00
				1.0E+00	H					1	0.1	1.4E+09			Phthalic Acid, P-	100-21-0					7.8E+04	2.8E+05		6.1E+04
				2.0E+00	I	2.0E-02	C			1	0.1	1.4E+09			Phthalic Anhydride	85-44-9					1.6E+05	5.6E+05	2.8E+07	1.2E+05
				7.0E-02	I					1	0.1	1.4E+09			Picloram	1918-02-1					5.5E+03	2.0E+04		4.3E+03
				1.0E-04	X					1	0.1	1.4E+09			Picramic Acid (2-Amino-4,6-dinitrophenol)	96-91-3					7.8E+00	2.8E+01		6.1E+00
				1.0E-02	I					1	0.1	1.4E+09			Pirimiphos, Methyl	29232-93-7					7.8E+02	2.8E+03		6.1E+02
3.0E+01	C	8.6E-03	C	7.0E-06	H					1	0.1	1.4E+09			Polybrominated Biphenyls Polychlorinated Biphenyls (PCBs)	59536-65-1	2.1E-02	6.7E-02	3.8E+02	1.6E-02	5.5E-01	2.0E+00		4.3E-01
7.0E-02	S	2.0E-05	S	7.0E-05	I					1	0.14	1.4E+09			~Aroclor 1215	12674-11-2	9.1E+00	2.1E+01	1.7E+05	6.3E+00	5.5E+00	1.4E+01		3.9E+00
2.0E+00	S	5.7E-04	S						V	1	0.14	7.6E+02	1.4E+09	9.2E+04	~Aroclor 1221	11104-28-2	3.2E-01	7.2E-01	3.9E-01	1.4E-01				
2.0E+00	S	5.7E-04	S						V	1	0.14	7.3E+01	1.4E+09	9.2E+04	~Aroclor 1232	11141-16-5	3.2E-01	7.2E-01	3.9E-01	1.4E-01				
2.0E+00	S	5.7E-04	S							1	0.14	1.4E+09			~Aroclor 1242	53469-21-9	3.2E-01	7.2E-01	5.8E+03	2.2E-01				
2.0E+00	S	5.7E-04	S							1	0.14	1.4E+09			~Aroclor 1248	12672-29-6	3.2E-01	7.2E-01	5.8E+03	2.2E-01				
2.0E+00	S	5.7E-04	S	2.0E-05	I					1	0.14	1.4E+09			~Aroclor 1254	11097-69-1	3.2E-01	7.2E-01	5.8E+03	2.2E-01	1.6E+00	4.0E+00		1.1E+00
2.0E+00	S	5.7E-04	S							1	0.14	1.4E+09			~Aroclor 1260	11096-82-5	3.2E-01	7.2E-01	5.8E+03	2.2E-01				
3.9E+00	E	1.1E-03	E	3.3E-05	E	1.3E-03	E			1	0.14	1.4E+09			~Heptachlorobiphenyl, 2,3,3',4,4',5,5'-(PCB 189)	39635-31-9	1.6E-01	3.7E-01	2.9E+03	1.1E-01	2.6E+00	6.7E+00	1.9E+06	1.9E+00
3.9E+00	E	1.1E-03	E	3.3E-05	E	1.3E-03	E			1	0.14	1.4E+09			~Hexachlorobiphenyl, 2,3',4,4',5,5'-(PCB 167)	52663-72-6	1.6E-01	3.7E-01	2.9E+03	1.1E-01	2.6E+00	6.7E+00	1.9E+06	1.9E+00
3.9E+00	E	1.1E-03	E	3.3E-05	E	1.3E-03	E			1	0.14	1.4E+09			~Hexachlorobiphenyl, 2,3,3',4,4',5,5'-(PCB 157)	69782-90-7	1.6E-01	3.7E-01	2.9E+03	1.				

ARCHIVE INFORMATION -

***Go to http://www.epa.gov/reg3hwmd/risk/human/rb-concentration_table/usersguide.htm
for the current guide***

**USERS' GUIDE AND BACKGROUND TECHNICAL DOCUMENT
FOR
USEPA REGION 9'S PRELIMINARY REMEDIATION GOALS (PRG) TABLE**

TABLE OF CONTENTS

1.0	INTRODUCTION	3
2.0	READING THE PRG TABLE.....	5
	General Considerations.....	5
	Toxicity Values.....	6
	PRGs Derived with Special Considerations.....	8
	Cal-Modified PRGs.....	10
	Soil Screening Levels.....	10
	Miscellaneous.....	11
3.0	USE OF PRGS AT SITES.....	11
	Conceptual Site Model.....	12
	Background Levels Evaluation.....	13
	Screening Sites with Multiple Pollutants.....	14
	Potential Problems.....	15
4.0	TECHNICAL SUPPORT DOCUMENTATION.....	16
	Ambient Air and Vapor Intrusion Pathway.....	16
	Soils - Direct Ingestion.....	17
	Soils - Dermal Contact.....	18
	Soils - Vapor and Particulate Inhalation	18
	Soils - Migration to Groundwater.....	20
	Soil Saturation Limits.....	21
	Tap Water - Ingestion and Inhalation.....	21
	Default Exposure Factors.....	22
	Standardized Equations.....	24
	REFERENCES.....	29

DISCLAIMER

Preliminary remediation goals (PRGs) focus on common exposure pathways and may not consider all exposure pathways encountered at CERCLA / RCRA sites (Exhibit 1-1). PRGs do not consider impact to groundwater or address ecological concerns. The PRG Table is specifically not intended as a (1) stand-alone decision-making tool, (2) as a substitute for EPA guidance for preparing baseline risk assessments, (3) a rule to determine if a waste is hazardous under RCRA, or (4) set of final cleanup or action levels to be applied at contaminated sites.

The guidance set out in this document is not final Agency action. It is not intended, nor can it be relied upon to create any rights enforceable by any party in litigation with the United States. EPA officials may decide to follow the guidance provided herein, or act at variance with the guidance, based on an analysis of specific circumstances. The Agency also reserves the right to change this guidance at any time without public notice.

1.0 INTRODUCTION

Region 9 Preliminary Remediation Goals (PRGs) are risk-based tools for evaluating and cleaning up contaminated sites. They are being used to streamline and standardize all stages of the risk decision-making process.

The Region 9 PRG Table combines current human health toxicity values with standard exposure factors to estimate contaminant concentrations in environmental media (soil, air, and water) that are considered by the Agency to be health protective of human exposures (including sensitive groups), over a lifetime. Chemical concentrations above these levels would not automatically designate a site as "dirty" or trigger a response action. However, exceeding a PRG suggests that further evaluation of the potential risks that may be posed by site contaminants is appropriate. Further evaluation may include additional sampling, consideration of ambient levels in the environment, or a reassessment of the assumptions contained in these screening-level estimates (e.g. appropriateness of route-to-route extrapolations, appropriateness of using chronic toxicity values to evaluate childhood exposures, appropriateness of generic exposure factors for a specific site etc.).

The risk-based concentrations presented in the Table may be used as screening goals or initial cleanup goals if applicable. Generally a screening goal is intended to provide health protection without knowledge of the specific exposure conditions at a site. PRGs may also be used as initial cleanup goals when the exposure assumptions based on site-specific data match up with the default exposure assumptions in the PRG Table. When considering PRGs as cleanup goals, it is EPA's preference to assume maximum beneficial use of a property (that is, residential use) unless a non-residential number (for example, industrial soil PRG) can be justified.

Before applying PRGs at a particular site, the Table user should consider whether the exposure pathways and exposure scenarios at the site are fully accounted for in the PRG calculations. Region 9 PRG concentrations are based on direct contact pathways for which generally accepted methods, models, and assumptions have been developed (i.e. ingestion, dermal contact, and inhalation) for specific land-use conditions and do not consider impact to groundwater or ecological receptors (see Developing a Conceptual Site Model below).

EXHIBIT 1-1
TYPICAL EXPOSURE PATHWAYS BY MEDIUM
FOR RESIDENTIAL AND INDUSTRIAL LAND USES^a

EXPOSURE PATHWAYS, ASSUMING:		
MEDIUM	RESIDENTIAL LAND USE	INDUSTRIAL LAND USE
Ground Water	<i>Ingestion from drinking</i>	Ingestion from drinking
	<i>Inhalation of volatiles</i>	Inhalation of volatiles
	Dermal absorption from bathing	Dermal absorption
Surface Water	<i>Ingestion from drinking</i>	Ingestion from drinking
	<i>Inhalation of volatiles</i>	Inhalation of volatiles
	Dermal absorption from bathing	Dermal absorption
	Ingestion during swimming	
	Ingestion of contaminated fish	
Soil	<i>Ingestion</i>	<i>Ingestion</i>
	<i>Inhalation of particulates</i>	<i>Inhalation of particulates</i>
	<i>Inhalation of volatiles</i>	<i>Inhalation of volatiles</i>
	Exposure to indoor air from soil gas	Exposure to indoor air from soil gas
	Exposure to ground water contaminated by soil leachate	Exposure to ground water contaminated by soil leachate
	Ingestion via plant, meat, or dairy products	Inhalation of particulates from trucks and heavy equipment
	<i>Dermal absorption</i>	<i>Dermal absorption</i>

Footnote:

^aExposure pathways considered in the PRG calculations are indicated in boldface italics.

2.0 READING THE PRG TABLE

2.1 General Considerations

With the exceptions described below, PRGs are chemical concentrations that correspond to fixed levels of risk (i.e. either a one-in-one million [10^{-6}] cancer risk or a noncarcinogenic hazard quotient of 1) in soil, air, and water. In most cases, where a substance causes both cancer and noncancer (systemic) effects, the 10^{-6} cancer risk will result in a more stringent criteria and consequently this value is presented in the printed copy of the Table. PRG concentrations that equate to a 10^{-6} cancer risk are indicated by "ca". PRG concentrations that equate to a hazard quotient of 1 for noncarcinogenic concerns are indicated by "nc".

If the risk-based concentrations are to be used for site screening, it is recommended that both cancer and noncancer-based PRGs be used. Both carcinogenic and noncarcinogenic values may be obtained at the Region 9 PRG homepage at:

<http://www.epa.gov/region09/superfund/prg/>

It has come to my attention that some users have been multiplying the cancer PRG concentrations by 10 or 100 to set "action levels" for triggering remediation or to set less stringent cleanup levels for a specific site after considering non-risk-based factors such as ambient levels, detection limits, or technological feasibility. This risk management practice recognizes that there may be a range of values that may be "acceptable" for carcinogenic risk (EPA's risk management range is one-in-a-million [10^{-6}] to one-in-ten thousand [10^{-4}]). However, this practice could lead one to overlook serious noncancer health threats and it is strongly recommended that the user consult with a toxicologist or regional risk assessor before doing this. For carcinogens, I have indicated by asterisk ("ca*") in the PRG Table where the noncancer PRGs would be exceeded if the cancer value that is displayed is multiplied by 100. Two stars ("ca**") indicate that the noncancer values would be exceeded if the cancer PRG were multiplied by 10. There is no range of "acceptable" noncarcinogenic "risk" so that under no circumstances should noncancer PRGs be multiplied by 10 or 100, when setting final cleanup criteria. In the rare case where noncancer PRGs are more stringent than cancer PRGs set at one-in-one-million risk, a similar approach has been applied (e.g. "nc**").

In general, PRG concentrations in the printed Table are risk-based but for soil there are two important exceptions: (1) for several volatile chemicals, PRGs are based on the soil saturation equation ("sat") and (2) for relatively less toxic inorganic and semivolatile contaminants, a non-risk based "ceiling limit" concentration is given as 10^{-5} mg/kg ("max"). At the Region 9 PRG website, the risk-based calculations for these same chemicals are also available in the "InterCalc Tables" if the user wants to view the risk-based concentrations prior to the application of "sat" or "max". For more information on why the "sat" value and not a risk-based value is presented for several volatile chemicals in the PRG Table, please see the discussion in Section 4.6.

With respect to applying a "ceiling limit" for chemicals other than volatiles, it is recognized that

this is not a universally accepted approach. Some within the agency argue that all values should be risk-based to allow for scaling (for example, if the risk-based PRG is set at a hazard quotient = 1.0, and the user would like to set the hazard quotient to 0.1 to take into account multiple chemicals, then this is as simple as multiplying the risk-based PRG by 1/10th). If scaling is necessary, PRG users can do this simply by referring to the “InterCalc Tables” at our website where risk-based soil concentrations are presented for all chemicals (see soil calculations, “combined” pathways column).

In spite of the fact that applying a ceiling limit is not a universally accepted approach, we have opted to continue applying a “max” soil concentration to the PRG Table for the following reasons:

- Risk-based PRGs for some chemicals in soil exceed unity ($>1,000,000$ mg/kg) which is not possible.
- The ceiling limit of 10^{+5} mg/kg is equivalent to a chemical representing 10% by weight of the soil sample. At this contaminant concentration (and higher), the assumptions for soil contact may be violated (for example, soil adherence and windborne dispersion assumptions) due to the presence of the foreign substance itself.
- PRGs currently do not address short-term exposures (e.g. pica children and construction workers). Although extremely high soil PRGs are likely to represent relatively non-toxic chemicals, such high values may not be justified if in fact more toxicological data were available for evaluating short-term and/or acute exposures.

In addition to Region 9 PRG values, the PRG Table also includes California EPA PRGs ("CAL-Modified PRGs") for specific chemicals where CAL-EPA screening values may deviate significantly from the federal values (see Section 2.4) and EPA OSWER soil screening levels (SSLs) for protection of groundwater (see Section 2.5).

2.2 Toxicity Values

Hierarchy of Toxicity Values

There is a new hierarchy of human health toxicity values that replaces earlier guidance. This is important because human toxicity values known as cancer slope factors (SF) or non-cancer reference doses (RfDs) form the basis of the PRG values listed in the table. As noted in OSWER Directive 9285.7-53 (dated December 5, 2003), the updated EPA hierarchy is as follows: Tier 1 - EPA’s Integrated IRIS, Tier 2 - EPA’s Provisional Peer Reviewed Toxicity Values (PPRTVs), and Tier 3 - Other Toxicity Values. Tier 3 includes additional EPA sources (e.g. historic HEAST and NCEA provisional values) and non-EPA sources of toxicity information (e.g. California EPA toxicity values).

The PRG Table lists Tier 1 toxicity values from IRIS as “i” and Tier 2 toxicity values known as PPRTVs as “p”. Tier 3 toxicity values were obtained from various sources including California EPA databases “c”, historic HEAST tables “h” and NCEA provisional values “n”.

Inhalation Conversion Factors

As of January 1991, IRIS and NCEA databases no longer present RfDs or SFs for the inhalation route. These criteria have been replaced with reference concentrations (RfC) for noncarcinogenic effects and unit risk factors (URF) for carcinogenic effects. However, for purposes of estimating risk and calculating risk-based concentrations, inhalation reference doses (RfDi) and inhalation slope factors (SF_i) are preferred. This is not a problem for most chemicals because the inhalation toxicity criteria are easily converted. To calculate an RfDi from an RfC, the following equation and assumptions may be used for most chemicals:

$$\text{RfDi} \frac{\text{mg}}{(\text{kg} \cdot \text{day})} = \text{RfC} (\text{mg} / \text{m}^3) \times \frac{20\text{m}^3}{\text{day}} \times \frac{1}{70\text{kg}}$$

Likewise, to calculate an SF_i from an inhalation URF, the following equation and assumptions may be used:

$$\text{SF}_i \frac{(\text{kg} \cdot \text{day})}{(\text{mg})} = \text{URF} (\text{m}^3 / \text{ug}) \times \frac{\text{day}}{20\text{m}^3} \times 70\text{kg} \times \frac{10^3 \text{ ug}}{\text{mg}}$$

Route-to-Route Methods

Route-to-route extrapolations (“r”) were frequently used when there were no toxicity values available for a given route of exposure. Oral cancer slope factors (“SF_o”) and reference doses (“RfD_o”) were used for both oral and inhaled exposures for organic compounds lacking inhalation values. Inhalation slope factors (“SF_i”) and inhalation reference doses (“RfD_i”) were used for both inhaled and oral exposures for organic compounds lacking oral values. Route extrapolations were not performed for inorganics due to portal of entry effects and known differences in absorption efficiency for the two routes of exposure.

An additional route extrapolation is the use of oral toxicity values for evaluating dermal exposures. In general, dermal toxicity values are not listed in EPA databases and consequently must be estimated from oral toxicity information. However, a scientifically defensible data base often does not exist for making an adjustment to the oral slope factor/RfD so that the oral toxicity value is often applied without adjustment to estimate a dermal toxicity value. For more information please refer to recent Agency guidance (USEPA 2004) entitled *Risk Assessment Guidance for Superfund Volume I: Human Health Evaluation Manual (Part E, Supplemental Guidance for Dermal Risk Assessment)* available on the web at:

<http://www.epa.gov/superfund/programs/risk/ragse/index.htm>

Please note that whenever route-extrapolated values are used to calculate risk-based PRGs, additional uncertainties are introduced in the calculation.

2.3 PRGs Derived with Special Considerations

Most of the Region 9 PRGs are readily derived by referring to Equations 4-1 thru 4-8 contained in this “User’s Guide/Technical Background Document” to the Region 9 PRGs. However, there are some chemicals for which the standard equations do not apply and/or adjustments to the toxicity values are recommended. These special case chemicals are discussed below.

Cadmium The PRGs for Cadmium are based on the oral RfD for water which is slightly more conservative (by a factor of 2) than the RfD for food. Because the PRGs are considered screening values, we elected to use the more conservative RfD for cadmium. However, reasonable arguments could be made for applying an RfD for food (instead of the oral RfD for water) for some media such as soils.

The water RfD for cadmium assumes a 5% oral absorption factor. The assumption of an oral absorption efficiency of 5% for Cadmium leads to an estimated dermal RfD of 2.5E-05. The PRG calculations incorporate these adjustments per recent guidance (USEPA 2004).

Chromium 6 For Chromium 6 (Cr6), IRIS shows an air unit risk of 1.2E-2 per (ug/cu.m) or expressed as an inhalation cancer slope factor (adjusting for inhalation/body weight) of 42 (mg/kg-day)⁻¹. However, the supporting documentation in the IRIS file states that these toxicity values are based on an assumed 1:6 ratio of Cr6:Cr3. Because of this assumption, we in Region 9 prefer to present PRGs based on these cancer toxicity values as “total chromium” numbers.

In the PRG Table, we also include a Cr6 specific value (assuming 100% Cr6) that is derived by multiplying the “total chromium” value by 7, yielding a cancer potency factor of 290 (mg/kg-day)⁻¹. This is considered to be an overly conservative assumption by some within the Agency. However, this calculation is also consistent with the State of California's interpretation of the Mancuso study that forms the basis of Cr6's toxicity values.

If you are working on a project outside of California (and outside of Region 9), you may want to contact the appropriate regulatory officials to determine what their position is on this issue. As mentioned, Region 9 also includes PRGs for “total chromium” which is based on the same ratio (1:6 ratio Cr6:Cr3) that forms the basis of the cancer slope factor of 42 (mg/kg-day)⁻¹ presented in IRIS.

Dioxin Dioxins, furans, and some polychlorinated biphenyls are members of the same family and exhibit similar toxicological properties. Before using the dioxin PRG at an individual site, these dioxin-related compounds must be summed together. However, they differ in the degree of toxicity so that a toxicity equivalence factor (TEF) must first be applied to adjust the measured concentrations to a toxicity equivalent concentration. EPA Region 9 has adopted the 1997 World Health Organization (WHO) TEFs. For more on this, please refer to the following article (in Environmental Health Perspectives, Vol. 6, No. 12, Dec. 1998) online at: <http://ehp.niehs.nih.gov/members/1998/106p775-792vandenberg/vandenberg-full.html>

Lead Residential PRGs for Lead (Region 9 EPA and California EPA) are derived based on pharmacokinetic models. Both EPA's Integrated Exposure Uptake Biokinetic (IEUBK) Model and California's LeadSpread model are designed to predict the probable blood lead concentrations for children between six months and seven years of age who have been exposed to lead through various sources (air, water, soil, dust, diet and *in utero* contributions from the mother). Run in the reverse, these models also allow the user to calculate lead PRGs that are considered "acceptable" by EPA or the State of California.

EPA uses a second Adult Lead Model to estimate PRGs for an industrial setting. This PRG is intended to protect a fetus that may be carried by a pregnant female worker. It is assumed that a cleanup goal that is protective of a fetus will also afford protection for male or female adult workers. The model equations were developed to calculate cleanup goals such that there would be no more than a 5% probability that fetuses exposed to lead would exceed a blood lead (PbB) of 10 Fg/dL. An updated screening level for soil lead at commercial/industrial (i.e., non-residential) sites of 800 ppm is based on a recent analysis of the combined phases of NHANES III that chooses a cleanup goal protective of all subpopulations.

For more information on EPA's lead models and other lead-related topics, please go to:

<http://www.epa.gov/oerrpage/superfund/programs/lead/>

For more information on California's LeadSpread Model and Cal-Modified PRGs for lead, please go to:

<http://www.dtsc.ca.gov/ScienceTechnology/ledspred.html>

Manganese The IRIS RfD (0.14 mg/kg-day) includes manganese from all sources, including diet. The author of the IRIS assessment for manganese recommends that the dietary contribution from the normal U.S. diet (an upper limit of 5 mg/day) be subtracted when evaluating non-food (e.g. drinking water or soil) exposures to manganese, leading to a RfD of 0.071 mg/kg-day for non-food items. The explanatory text in IRIS further recommends using a modifying factor of 3 when calculating risks associated with non-food sources due to a number of uncertainties that are discussed in the IRIS file for manganese, leading to a RfD of 0.024 mg/kg-day. This modified RfD is applied in the derivation of the Region 9 PRGs for soil and water. For more information regarding the Manganese RfD, you may want to contact Dr. Bob Benson at (303) 312-7070.

Nitrates/Nitrites Tap water PRGs for Nitrates/Nitrites are based on the MCL as there is no available RfD for these compounds. For more information, please see IRIS at:

<http://www.epa.gov/iriswebp/iris/index.html>

Thallium IRIS has many values for the different salts of thallium. However, our analytical data packages typically report "thallium". Therefore, as a practical matter it makes more sense to report a PRG for plain thallium. We have done this by making the adjustment contained in the IRIS file for thallium sulfate based on the molecular weight of the thallium in the thallium salt. The adjusted oral RfD for plain thallium is 6.6 E-05 mg/kg-day which we use to calculate a thallium PRG.

Vinyl Chloride In EPA's recent reassessment of vinyl chloride toxicity, IRIS presents two cancer slope factors for vinyl chloride (VC): one that is intended to be applied towards evaluating adult risks and a second more protective slope factor that takes into account the unique susceptibility of developing infants and young children. For residential PRGs, the Region 9 PRG Table applies the more conservative cancer potency factor that addresses exposures to both children and adults whereas for the industrial soils PRG, the adult only cancer slope factor is applied.

Because of the age-dependent vulnerability associated with vinyl chloride exposures, and due to the method that is applied in deriving the cancer slope factor for VC, an assumption of a 70 year exposure over the lifetime is assumed, consistent with the way that the toxicity value for VC was derived. Therefore, instead of the usual exposure assumption of 6 years as a child and 24 years as an adult that is assumed for carcinogenic substances, we have revised the exposure assumption for VC to 6 years as a child and 64 years as adult. Since most of the cancer risk is associated with the first 30 years of exposure to VC, there is actually little difference between a 30 year exposure assumption (typically assumed for Superfund risk assessments) and the 70 year exposure assumption that is assumed in calculating the PRG for VC.

2.4 Cal-Modified PRGs

When EPA Region 9 first came out with a Draft of the PRG Table in 1992, there was concern expressed by California EPA's Department of Toxic Substances and Control (DTSC) that for some chemicals, the risk-based concentrations that are calculated using Cal-EPA toxicity values are "significantly" more protective than the risk-based concentrations that are calculated using EPA toxicity values. Because the risk-based PRGs are order-of-magnitude estimates at best, it was agreed by both Agencies that a difference of approximately 4 or greater would be regarded as a significant difference. For chemicals with California and EPA values that differ by a factor of 4 or more, both the EPA PRGs and the "Cal-Modified PRGs" are listed in the Table.

Please note that in the State of California, Cal-Modified PRGs should be used as screening levels for contaminated sites if they are more stringent than the Federal numbers.

2.5 Soil Screening Levels

Generic, soil screening levels (SSLs) for the protection of groundwater have been included in the PRG Table for 100 of the most common contaminants at Superfund sites. Generic SSLs are derived using default values in standardized equations presented in EPA OSWER's *Soil Screening Guidance* series, available on the web at <http://www.epa.gov/superfund/resources/soil/index.htm>.

The SSLs were developed using a default dilution-attenuation factor (DAF) of 20 to account for natural processes that reduce contaminant concentrations in the subsurface. Also included are generic SSLs that assume no dilution or attenuation between the source and the receptor well (i.e., a DAF of 1). These values can be used at sites where little or no dilution or attenuation of soil leachate concentrations is expected at a site (e.g., sites with shallow water tables, fractured media, karst topography, or source size greater than 30 acres).

In general, if an SSL is not exceeded for the migration to groundwater pathway, the user may eliminate this pathway from further investigation.

It should be noted that in the State of California, the California Regional Water Quality Control Board has derived “California SSLs” for a number of pathways including migration to groundwater. These are not included in the Region 9 PRG Table, but may be accessed at the following website:

<http://www.swrcb.ca.gov/rwqcb2/rbsl.htm>

Or, for more information on the “California SSLs”, please contact Dr Roger Brewer at: (510) 622-2374.

2.6 Miscellaneous

Volatile organic compounds (VOCs) are indicated by "y" in the VOC column of the Table and in general, are defined as those chemicals having a Henry's Law constant greater than 10^{-5} (atm-m³/mol) and a molecular weight less than 200 g/mole). Three borderline chemicals (dibromochloromethane, 1,2-dibromochloropropane, and pyrene) which do not strictly meet these criteria of volatility have also been included based upon discussions with other state and federal agencies and after a consideration of vapor pressure characteristics etc. Volatile organic chemicals are evaluated for potential volatilization from soil/water to air using volatilization factors (see Section 4.4).

Chemical-specific dermal absorption values for contaminants in soil and dust are presented for arsenic, cadmium, chlordane, 2,4-D, DDT, lindane, TCDD, PAHs, PCBs, and pentachlorophenols as recommended in the *Risk Assessment Guidance for Superfund Volume I: Human Health Evaluation Manual (Part E, Supplemental Guidance for Dermal Risk Assessment) Interim Guidance* (USEPA 2004). Otherwise, default skin absorption fractions are assumed to be 0.10 for nonvolatile organics. Please note that previous defaults of 0.01 and 0.10 for inorganics and VOCs respectively, have been withdrawn per new guidance.

3.0 USE OF PRGS AT SITES

The decision to use PRGs at a site will be driven by the potential benefits of having generic risk-based concentrations in the absence of site-specific risk assessments. The original intended use of PRGs was to provide initial cleanup goals for individual chemicals given specific medium and land-use combinations (see RAGS Part B, 1991), however risk-based concentrations have several applications. They can also be used for:

- □ Setting health-based detection limits for chemicals of potential concern
- □ Screening sites to determine whether further evaluation is appropriate
- □ Calculating cumulative risks associated with multiple contaminants

A few basic procedures are recommended for using PRGs properly. These are briefly described below. Potential problems with the use of PRGs are also identified.

3.1 Conceptual Site Model

The primary condition for use of PRGs is that exposure pathways of concern and conditions at the site match those taken into account by the PRG framework. Thus, it is always necessary to develop a conceptual site model (CSM) to identify likely contaminant source areas, exposure pathways, and potential receptors. This information can be used to determine the applicability of PRGs at the site and the need for additional information. For those pathways not covered by PRGs, a risk assessment specific to these additional pathways may be necessary. Nonetheless, the PRG lookup values will still be useful in such situations for focusing further investigative efforts on the exposure pathways not addressed.

To develop a site-specific CSM, perform an extensive records search and compile existing data (e.g. available site sampling data, historical records, aerial photographs, and hydrogeologic information). Once this information is obtained, CSM worksheets such as those provided in ASTM's *Standard Guide for Risk-Based Corrective Action Applied at Petroleum Release Sites* (1995) can be used to tailor the generic worksheet model to a site-specific CSM. The final CSM diagram represents linkages among contaminant sources, release mechanisms, exposure pathways and routes and receptors. It summarizes our understanding of the contamination problem.

As a final check, the CSM should answer the following questions:

- Are there potential ecological concerns?
- Is there potential for land use other than those covered by the PRGs (that is, residential and industrial)?
- Are there other likely human exposure pathways that were not considered in development of the PRGs (e.g. impact to groundwater, local fish consumption, raising beef, dairy, or other livestock)?
- Are there unusual site conditions (e.g. large areas of contamination, high fugitive dust levels, potential for indoor air contamination)?

If any of these four conditions exist, the PRG may need to be adjusted to reflect this new information. Suggested websites for the evaluation of pathways not currently addressed by Region 9 PRG's are presented in Exhibit 3-1.

EXHIBIT 3-1
SUGGESTED WEBSITES FOR EVALUATING EXPOSURE
PATHWAYS NOT CURRENTLY ADDRESSED BY REGION 9 PRGs

EXPOSURE PATHWAY	WEBSITE
Migration of contaminants to an underlying potable aquifer	EPA Soil Screening Guidance: http://www.epa.gov/superfund/resources/soil/index.htm California Water Board Guidance: http://www.swrcb.ca.gov/rwqcb2/rbsl.htm
Ingestion via plant uptake	EPA Soil Screening Guidance: http://www.epa.gov/superfund/resources/soil/index.htm EPA Fertilizer Risk Assessment: http://www.epa.gov/epaoswer/hazwaste/recycle/fertiliz/risk/
Ingestion via meat, dairy products, human milk	EPA Protocol for Combustion Facilities: http://www.epa.gov/epaoswer/hazwaste/combust/riskvol.htm#volume1 California “Hot Spots” Risk Guidelines: http://www.oehha.ca.gov/air/hot_spots/HRSguide.html
Inhalation of volatiles that have migrated into basements or other enclosed spaces.	EPA’s draft Subsurface Vapor Intrusion Guidance: http://www.epa.gov/correctiveaction/eis/vapor.htm EPA’s Version of Johnson & Ettinger Model: http://www.epa.gov/oerrpage/superfund/programs/risk/airmodel/johnson_ettinger.htm
Ecological pathways	EPA Ecological Soil Screening Guidance: http://www.epa.gov/superfund/programs/risk/ecorisk/ecossl.htm NOAA Sediment Screening Table: http://response.restoration.noaa.gov/cpr/sediment/squirt/squirt.html

3.2 Background Levels Evaluation

A necessary step in determining the applicability of Region 9 risk-based PRGs is the consideration of background contaminant concentrations. There is new EPA guidance on determining background at sites. *Guidance for Characterizing Background Chemicals in Soil at Superfund Sites* (USEPA 2001b) is available on the web at:
<http://www.epa.gov/superfund/programs/risk/background.pdf> .

EPA may be concerned with two types of background at sites: naturally occurring and

anthropogenic. Natural background is usually limited to metals whereas anthropogenic (i.e. human-made) “background” includes both organic and inorganic contaminants. Before embarking on an extensive sampling and analysis program to determine local background concentrations in the area, one should first compile existing data on the subject. Far too often there is pertinent information in the literature that gets ignored, resulting in needless expenditures of time and money.

Generally EPA does not clean up below natural background. In some cases, the predictive risk-based models generate PRG concentrations that lie within or even below typical background concentrations for the same element or compound. If natural background concentrations are higher than the risk-based PRG concentrations, then background concentrations should also be considered in determining whether further evaluation and/or remediation is necessary at a particular site. Exhibit 3-2 presents summary statistics for selected elements in soils that have background levels that may exceed risk-based PRGs.

Where anthropogenic “background” levels exceed PRGs and EPA has determined that a response action is necessary and feasible, EPA's goal will be to develop a comprehensive response to the widespread contamination. This will often require coordination with different authorities that have jurisdiction over the sources of contamination in the area.

**EXHIBIT 3-2
BACKGROUND CONCENTRATIONS OF SELECTED ELEMENTS IN SOILS**

TRACE ELEMENT	U.S. STUDY DATA ¹			CALIFORNIA DATA ²		
	Range	GeoMean	ArMean	Range	GeoMean	ArMean
Arsenic	<.1-97	5.2 mg/kg	7.2 mg/kg	0.59-11	2.75 mg/kg	3.54 mg/kg
Beryllium	<1-15	0.63 “	0.92 “	0.10-2.7	1.14 “	1.28 “
Cadmium	<1-10	--	<1	0.05-1.7	0.26	0.36
Chromium	1-2000	37	54	23-1579	76.25	122.08
Nickel	<5-700	13	19	9.0-509	35.75	56.60

¹Shacklette and Hansford, “Element Concentrations in Soils and Other Surficial Materials of the Conterminous United States”, USGS Professional Paper 1270, 1984.

²Bradford et. al, “Background Concentrations of Trace and Major Elements in California Soils”, Kearney Foundation Special Report, UC-Riverside and CAL-EPA DTSC, March 1996.

3.3 Screening Sites with Multiple Pollutants

A suggested stepwise approach for PRG-screening of sites with multiple pollutants is as follows:

- Perform an extensive records search and compile existing data.

- Identify site contaminants in the PRG Table. Record the PRG concentrations for various media and note whether PRG is based on cancer risk (indicated by "ca") or noncancer hazard (indicated by "nc"). Segregate cancer PRGs from non-cancer PRGs and exclude (but don't eliminate) non-risk based PRGs ("sat" or "max").
- For cancer risk estimates, take the site-specific concentration (maximum or 95 UCL) and divide by the PRG concentrations that are designated for cancer evaluation ("ca"). Multiply this ratio by 10^{-6} to estimate chemical-specific risk for a reasonable maximum exposure (RME). For multiple pollutants, simply add the risk for each chemical:

$$Risk = \left[\left(\frac{conc_x}{PRG_x} \right) \% \left(\frac{conc_y}{PRG_y} \right) \% \left(\frac{conc_z}{PRG_z} \right) \right] \times 10^{-6}$$

- For non-cancer hazard estimates. Divide the concentration term by its respective non-cancer PRG designated as "nc" and sum the ratios for multiple contaminants. The cumulative ratio represents a non-carcinogenic hazard index (HI). A hazard index of 1 or less is generally considered "safe". A ratio greater than 1 suggests further evaluation. **[Note that carcinogens may also have an associated non-cancer PRG that is not listed in the PRG Table. To obtain these values, the user should view or download the InterCalc Tables at the PRG website and display the appropriate sections.]**

$$Hazard\ Index = \left[\left(\frac{conc_x}{PRG_x} \right) \% \left(\frac{conc_y}{PRG_y} \right) \% \left(\frac{conc_z}{PRG_z} \right) \right]$$

For more information on screening site risks, the reader should contact EPA Region 9's Technical Support Section.

3.4 Potential Problems

As with any risk-based tool, the potential exists for misapplication. In most cases the root cause will be a lack of understanding of the intended use of Region 9 PRGs. In order to prevent misuse of PRGs, the following should be avoided:

- Applying PRGs to a site without adequately developing a conceptual site model that identifies relevant exposure pathways and exposure scenarios,
- Not considering background concentrations when choosing PRGs as cleanup goals,
- Use of PRGs as cleanup levels without the nine-criteria analysis specified in the National Contingency Plan (or, comparable analysis for programs outside of Superfund),
- Use of PRGs as cleanup levels without verifying numbers with a toxicologist or regional risk assessor,

- Use of antiquated PRG Tables that have been superseded by more recent publications,
- Not considering the effects of additivity when screening multiple chemicals, and
- Adjusting PRGs upward by factors of 10 or 100 without consulting a toxicologist or regional risk assessor.

4.0 TECHNICAL SUPPORT DOCUMENTATION

Region 9 PRGs consider human exposure hazards to chemicals from contact with contaminated soils, air, and water. The emphasis of the PRG equations and technical discussion are aimed at developing screening criteria for soils, since this is an area where few standards exist. For air and water, additional reference concentrations or standards are available for many chemicals (e.g. MCLs, non-zero MCLGs, AWQC, and NAAQS) and consequently the discussion of these media are brief.

4.1 Ambient Air and the Vapor Intrusion Pathway

The ambient air PRG is applicable to both indoor and outdoors and is based on a residential exposure scenario using standard Superfund exposure factors (see Exhibit 4-1 below).

The air PRG may also be used as a health-protective indoor air target for determining soil gas and groundwater screening levels for the evaluation of the subsurface vapor intrusion pathway. The “vapor intrusion pathway” refers to the migration of volatile chemicals from the subsurface into overlying buildings. Volatile chemicals in buried wastes and/or contaminated groundwater can emit vapors that may migrate through subsurface soils and into indoor air spaces of overlying buildings in ways similar to that of radon gas seeping into homes.

To derive a soil gas and/or groundwater screening level that targets the air PRG, it is necessary to divide the air PRG by an appropriate attenuation factor. The attenuation factor represents the factor by which subsurface vapor concentrations migrating into indoor air spaces are reduced due to diffusive, advective, and/or other attenuating mechanisms. The attenuation factor can be empirically determined and/or calculated using an appropriate vapor intrusion model such as the Johnson and Ettinger model available at: http://www.epa.gov/oerrpage/superfund/programs/risk/airmodel/johnson_ettinger.htm. Once the appropriate attenuation factor is determined, the following equation can be used to derive a screening level that would be protective of indoor air assuming residential land use.

For Soil Gas, the relationship is as follows:

$$C_{\text{soil-gas}}[\text{ug}/\text{m}^3] = \text{Air PRG} [\text{ug}/\text{m}^3]/\text{AF}$$

where

$C_{\text{soil-gas}}$ = soil gas screening level

AF = attenuation factor (ratio of indoor air concentration to soil gas concentration)

For Groundwater, the relationship is as follows:

$$C_{gw}[\text{ug/L}] = \text{Air PRG} [\text{ug/m}^3] \times 10^{-3} \text{ m}^3/\text{L} \times 1/H \times 1/AF$$

where

C_{gw} = groundwater screening level

H = dimensionless Henry's Law Constant at 25C [(mg/L - vapor)/(mg/L - water)]

AF = attenuation factor (ratio of indoor air concentration to soil gas concentration)

For more information on EPA's current understanding of this emerging exposure pathway, please refer to EPA's recent draft guidance *Evaluating the Vapor Intrusion to Indoor Air Pathway from Groundwater and Soils (Subsurface Vapor Intrusion Guidance)* (USEPA 2002) available on the web at:

<http://www.epa.gov/correctiveaction/eis/vapor.htm>

4.2 Soils - Direct Ingestion

Calculation of risk-based PRGs for direct ingestion of soil is based on methods presented in RAGS HHEM, Part B (USEPA 1991a) and *Soil Screening Guidance* (USEPA 1996a,b, USEPA 2001a). Briefly, these methods backcalculate a soil concentration level from a target risk (for carcinogens) or hazard quotient (for noncarcinogens).

Residential Soil PRGs

A number of studies have shown that inadvertent ingestion of soil is common among children 6 years old and younger (Calabrese et al. 1989, Davis et al. 1990, Van Wijnen et al. 1990). To take into account the higher soil intake rate for children, two different approaches are used to estimate PRGs, depending on whether the adverse health effect is cancer or some effect other than cancer.

For carcinogens, the method for calculating PRGs uses an age-adjusted soil ingestion factor that takes into account the difference in daily soil ingestion rates, body weights, and exposure duration for children from 1 to 6 years old and others from 7 to 31 years old. This health-protective approach is chosen to take into account the higher daily rates of soil ingestion in children as well as the longer duration of exposure that is anticipated for a long-term resident. For more on this method, see USEPA RAGs Part B (1991a).

For noncarcinogenic concerns, the more protective method of calculating a soil PRG is to evaluate childhood exposures separately from adult exposures. In other words, an age-adjustment factor is not applied as was done for carcinogens. This approach is considered conservative because it combines the higher 6-year exposure for children with chronic toxicity criteria. In their analysis of the method, the Science Advisory Board (SAB) indicated that, for most chemicals, the approach may be overly protective. However, they noted that there are specific instances when the chronic RfD may be based on endpoints of toxicity that are specific to children (e.g. fluoride and nitrates) or when the dose-response is steep (i.e., the dosage difference between the no-observed-adverse-effects level [NOAEL] and an adverse effects level is small). Thus, for the purposes of screening, EPA Region 9 has adopted this approach for calculating soil PRGs for noncarcinogenic health concerns.

Industrial Soil PRGs

In the *Supplemental Guidance for Developing Soil Screening Levels for Superfund Sites* (Supplemental SSL Guidance, EPA 2001a), two different soil ingestion rates are assumed for non-construction workers: 100 mg/day is assumed for outdoor workers whereas 50 mg/day is assumed for indoor workers. The default value of 100 mg/day for outdoor workers is also recommended by EPA's Technical Review Workgroup for Lead (TRW), and it reflects increased exposures to soils for outdoor workers relative to their indoor counterparts. For more on this, please see the Supplemental SSL Guidance available at the following website:

<http://www.epa.gov/superfund/resources/soil/index.htm>

Because the Region 9 PRGs are generic and intended for screening sites early in the investigation process (often before site-specific information is available), we have chosen to use the 100 mg/day soil ingestion (i.e. outdoor worker) assumption to calculate industrial soil PRGs. The appropriateness of this assumption for a particular site may be evaluated when additional information becomes available regarding site conditions or site development.

4.3 Soils - Dermal Contact

Dermal Contact Assumptions

Exposure factors for dermal contact with soil are based on recommendations in *Risk Assessment Guidance for Superfund Volume I: Human Health Evaluation Manual (Part E, Supplemental Guidance for Dermal Risk Assessment) Interim Guidance* (USEPA 2004). Recommended RME (reasonable maximum exposure) defaults for adult workers' skin surface areas (3300 cm²/day) and soil adherence factors (0.2 mg/cm²) now differ from the defaults recommended for adult residents (5700 cm²/day, 0.07 mg/cm²) as noted in Exhibit 4-1. This is due to differences in the range of activities experienced by workers versus residents.

Dermal Absorption

Chemical-specific skin absorption values recommended by the Superfund Dermal Workgroup were applied when available. Chemical-specific values are included for the following chemicals: arsenic, cadmium, chlordane, 2,4-D, DDT, lindane, TCDD, PAHs, PCBs, and pentachlorophenols.

The *Supplemental Guidance for Dermal Risk Assessment* (USEPA 2004) recommends a default dermal absorption factor for semivolatile organic compounds of 10% as a screening method for the majority of SVOCs without dermal absorption factors. Default dermal absorption values for other chemicals (VOCs and inorganics) are not recommended in this new guidance. Therefore, the assumption of 1% for inorganics and 10% for volatiles is no longer included in the PRG Table. This change has minimal impact on the final risk-based calculations because human exposure to VOCs and inorganics in soils is generally driven by other pathways of exposure.

4.4 Soils - Vapor and Particulate Inhalation

Agency toxicity criteria indicate that risks from exposure to some chemicals via inhalation far outweigh the risk via ingestion; therefore soil PRGs have been designed to address this pathway

as well. The models used to calculate PRGs for inhalation of volatiles/particulates are based on updates to risk assessment methods presented in RAGS Part B (USEPA 1991a) and are identical to the *Soil Screening Guidance: User's Guide and Technical Background Document* (USEPA 1996a,b).

It should be noted that the soil-to-air pathway that is evaluated in the PRGs calculations is based on inhalation exposures that result from the volatilization or particulate emissions of chemicals from soil to outdoor air. **The soil PRG calculations do not evaluate potential for volatile contaminants in soil to migrate indoors. For more on the subsurface vapor intrusion pathway please see Section 4.1.**

To address the soil-to-outdoor air pathways, the PRG calculations incorporate volatilization factors (VF_s) for volatile contaminants and particulate emission factors (PEF) for nonvolatile contaminants. These factors relate soil contaminant concentrations to air contaminant concentrations that may be inhaled on-site. The VF_s and PEF equations can be broken into two separate models: an emission model to estimate emissions of the contaminant from the soil and a dispersion model to simulate the dispersion of the contaminant in the atmosphere.

The box model in RAGS Part B has been replaced with a dispersion term (Q/C) derived from a modeling exercise using meteorological data from 29 locations across the United States because the box model may not be applicable to a broad range of site types and meteorology and does not utilize state-of-the-art techniques developed for regulatory dispersion modeling. The dispersion model for both volatiles and particulates is the AREA-ST, an updated version of the Office of Air Quality Planning and Standards, Industrial Source Complex Model, ISC2. However, different Q/C terms are used in the VF and PEF equations. Los Angeles was selected as the 90th percentile data set for volatiles and Minneapolis was selected as the 90th percentile data set for fugitive dusts (USEPA 1996 a,b). A default source size of 0.5 acres was chosen for the PRG calculations. This is consistent with the default exposure area over which Region 9 typically averages contaminant concentrations in soils. If unusual site conditions exist such that the area source is substantially larger than the default source size assumed here, an alternative Q/C could be applied (see USEPA 1996a,b).

Volatilization Factor for Soils

Volatile chemicals, defined as those chemicals having a Henry's Law constant greater than 10^{-5} (atm-m³/mol) and a molecular weight less than 200 g/mole, were screened for inhalation exposures using a volatilization factor for soils (VF_s). Please note that VF_s 's and other physical-chemical data for VOCs are contained in the InterCalc Tables at the EPA Region 9 PRG website.

The emission terms used in the VF_s are chemical-specific and were calculated from physical-chemical information obtained from several sources. The priority of these sources were as follows: *Soil Screening Guidance* (USEPA 1996a,b), *Superfund Chemical Data Matrix* (USEPA 1996c), *Fate and Exposure Data* (Howard 1991), *Subsurface Contamination Reference Guide* (EPA 1990a), and *Superfund Exposure Assessment Manual* (SEAM, EPA 1988). When there was a choice between a measured or a modeled value (e.g. Koc), our default was to use modeled values. In those cases where Diffusivity Coefficients (Di) were not provided in existing literature, Di 's were calculated using Fuller's Method described in SEAM. A surrogate term was required for some chemicals that lacked physico-chemical information. In these cases, a proxy chemical of similar structure was used that may over- or under-estimate the PRG for soils.

Equation 4-9 forms the basis for deriving generic soil PRGs for the inhalation pathway. The following parameters in the standardized equation can be replaced with specific site data to develop a simple site-specific PRG

- Source area
- Average soil moisture content
- Average fraction organic carbon content
- Dry soil bulk density

The basic principle of the VF_s model (Henry's law) is applicable only if the soil contaminant concentration is at or below soil saturation "sat". Above the soil saturation limit, the model cannot predict an accurate VF-based PRG. How these particular cases are handled, depends on whether the contaminant is liquid or solid at ambient soil temperatures (see Section 4.6).

Particulate Emission Factor for Soils

Inhalation of chemicals adsorbed to respirable particles (PM_{10}) were assessed using a default PEF equal to $1.316 \times 10^9 \text{ m}^3/\text{kg}$ that relates the contaminant concentration in soil with the concentration of respirable particles in the air due to fugitive dust emissions from contaminated soils. The generic PEF was derived using default values in Equation 4-11, which corresponds to a receptor point concentration of approximately $0.76 \text{ ug}/\text{m}^3$. The relationship is derived by Cowherd (1985) for a rapid assessment procedure applicable to a typical hazardous waste site where the surface contamination provides a relatively continuous and constant potential for emission over an extended period of time (e.g. years). This represents an annual average emission rate based on wind erosion that should be compared with chronic health criteria; it is not appropriate for evaluating the potential for more acute exposures.

The impact of the PEF on the resultant PRG concentration (that combines soil exposure pathways for ingestion, skin contact, and inhalation) can be assessed by accessing the Region 9 PRG website and viewing the pathway-specific soil concentrations listed in the InterCalc Tables. Equation 4-11 forms the basis for deriving a generic PEF for the inhalation pathway. For more details regarding specific parameters used in the PEF model, the reader is referred to *Soil Screening Guidance: Technical Background Document* (USEPA 1996a).

Note: the generic PEF evaluates windborne emissions and does not consider dust emissions from traffic or other forms of mechanical disturbance that could lead to greater emissions than assumed here.

4.5 Soils - Migration to Groundwater

The methodology for calculating SSLs for the migration to groundwater was developed to identify chemical concentrations in soil that have the potential to contaminate groundwater. Migration of contaminants from soil to groundwater can be envisioned as a two-stage process: (1) release of contaminant in soil leachate and (2) transport of the contaminant through the underlying soil and aquifer to a receptor well. The SSL methodology considers both of these fate and transport mechanisms.

SSLs are backcalculated from acceptable ground water concentrations (i.e. nonzero MCLGs, MCLs, or risk-based PRGs). First, the acceptable groundwater concentration is multiplied by a

dilution factor to obtain a target leachate concentration. For example, if the dilution factor is 10 and the acceptable ground water concentration is 0.05 mg/L, the target soil leachate concentration would be 0.5 mg/L. The partition equation (presented in the *Soil Screening Guidance* document) is then used to calculate the total soil concentration (i.e. SSL) corresponding to this soil leachate concentration.

The SSL methodology was designed for use during the early stages of a site evaluation when information about subsurface conditions may be limited. Because of this constraint, the methodology is based on conservative, simplifying assumptions about the release and transport of contaminants in the subsurface. For more on SSLs, and how to calculate site-specific SSLs versus generic SSLs presented in the PRG Table, the reader is referred to the *Soil Screening Guidance* document (USEPA 1996a,b).

4.6 Soil Saturation Limit

The soil saturation concentration “sat” corresponds to the contaminant concentration in soil at which the absorptive limits of the soil particles, the solubility limits of the soil pore water, and saturation of soil pore air have been reached. Above this concentration, the soil contaminant may be present in free phase, i.e., nonaqueous phase liquids (NAPLs) for contaminants that are liquid at ambient soil temperatures and pure solid phases for compounds that are solid at ambient soil temperatures.

Equation 4-10 is used to calculate “sat” for each volatile contaminant. As an update to RAGS HHEM, Part B (USEPA 1991a), this equation takes into account the amount of contaminant that is in the vapor phase in soil in addition to the amount dissolved in the soil’s pore water and sorbed to soil particles.

Chemical-specific “sat” concentrations must be compared with each VF-based PRG because a basic principle of the PRG volatilization model is not applicable when free-phase contaminants are present. How these cases are handled depends on whether the contaminant is liquid or solid at ambient temperatures. Liquid contaminant that have a VF-based PRG that exceeds the “sat” concentration are set equal to “sat” whereas for solids (e.g., PAHs), soil screening decisions are based on the appropriate PRGs for other pathways of concern at the site (e.g., ingestion).

4.7 Tap Water - Ingestion and Inhalation

Calculation of PRGs for ingestion and inhalation of contaminants in domestic water is based on the methodology presented in RAGS HHEM, Part B (USEPA 1991a). Ingestion of drinking water is an appropriate pathway for all chemicals. For the purposes of this guidance, however, inhalation of volatile chemicals from water is considered routinely only for chemicals with a Henry’s Law constant of 1×10^{-5} atm-m³/mole or greater and with a molecular weight of less than 200 g/mole.

For volatile chemicals, an upperbound volatilization constant (VF_w) is used that is based on all uses of household water (e.g. showering, laundering, and dish washing). Certain assumptions were made. For example, it is assumed that the volume of water used in a residence for a family of four is 720 L/day, the volume of the dwelling is 150,000 L and the air exchange rate is 0.25 air changes/hour (Andelman in RAGS Part B). Furthermore, it is assumed that the average transfer efficiency weighted by water use is 50 percent (i.e. half of the concentration of each

chemical in water will be transferred into air by all water uses). Note: the range of transfer efficiencies extends from 30% for toilets to 90% for dishwashers.

4.8 Default Exposure Factors

Default exposure factors were obtained primarily from RAGS Supplemental Guidance Standard Default *Exposure Factors* (OSWER Directive, 9285.6-03) dated March 25, 1991 and more recent information from U.S. EPA's Office of Solid Waste and Emergency Response, U.S. EPA's Office of Research and Development, and California EPA's Department of Toxic Substances Control (see Exhibit 4-1).

Because contact rates may be different for children and adults, carcinogenic risks during the first 30 years of life were calculated using age-adjusted factors ("adj"). Use of age-adjusted factors are especially important for soil ingestion exposures, which are higher during childhood and decrease with age. However, for purposes of combining exposures across pathways, additional age-adjusted factors are used for inhalation and dermal exposures. These factors approximate the integrated exposure from birth until age 30 combining contact rates, body weights, and exposure durations for two age groups - small children and adults. Age-adjusted factors were obtained from RAGS PART B or developed by analogy (see derivations next page).

For soils only, noncarcinogenic contaminants are evaluated in children separately from adults. No age-adjustment factor is used in this case. The focus on children is considered protective of the higher daily intake rates of soil by children and their lower body weight. For maintaining consistency when evaluating soils, dermal and inhalation exposures are also based on childhood contact rates.

(1) ingestion([mg-yr]/[kg-d]):

$$IFS_{adj} = \frac{ED_c \times IRS_c}{BW_c} \% \frac{(ED_r \& ED_c) \times IRS_a}{BW_a}$$

(2) skin contact([mg-yr]/[kg-d]):

$$SFS_{adj} = \frac{ED_c \times AF \times SA_c}{BW_c} \% \frac{(ED_r \& ED_c) \times AF \times SA_a}{BW_a}$$

(3) inhalation ([m³-yr]/[kg-d]):

$$InhF_{adj} = \frac{ED_c \times IRA_c}{BW_c} \% \frac{(ED_r \& ED_c) \times IRA_a}{BW_a}$$

EXHIBIT 4-1 STANDARD DEFAULT FACTORS

<u>Symbol</u>	<u>Definition (units)</u>	<u>Default</u>	<u>Reference</u>
CSFo	Cancer slope factor oral (mg/kg-d)-1	--	IRIS, PPRTV, HEAST, NCEA, or California
CSFi	Cancer slope factor inhaled (mg/kg-d)-1	--	IRIS, PPRTV, HEAST, NCEA, or California
RfDo	Reference dose oral (mg/kg-d)	--	IRIS, PPRTV, HEAST, NCEA, or California
RfDi	Reference dose inhaled (mg/kg-d)	--	IRIS, PPRTV, HEAST, NCEA, or California
TR	Target cancer risk	10 ⁻⁶	--
THQ	Target hazard quotient	1	--
BWa	Body weight, adult (kg)	70	RAGS (Part A), EPA 1989 (EPA/540/1-89/002)
BWc	Body weight, child (kg)	15	Exposure Factors, EPA 1991 (OSWER No. 9285.6-03)
ATc	Averaging time - carcinogens (days)	25550	RAGS(Part A), EPA 1989 (EPA/540/1-89/002)
ATn	Averaging time - noncarcinogens (days)	ED*365	
SAa	Exposed surface area for soil/dust (cm ² /day) – adult resident	5700	Dermal Assessment, EPA 2004 (EPA/540/R-99/005)
	– adult worker	3300	
SAc	Exposed surface area, child in soil (cm ² /day)	2800	Dermal Assessment, EPA 2004 (EPA/540/R-99/005)
AFa	Adherence factor, soils (mg/cm ²) – adult resident	0.07	Dermal Assessment, EPA 2004 (EPA/540/R-99/005)
	– adult worker	0.2	
AFc	Adherence factor, child (mg/cm ²)	0.2	Dermal Assessment, EPA 2004 (EPA/540/R-99/005)
ABS	Skin absorption defaults (unitless): – semi-volatile organics	0.1	Dermal Assessment, EPA 2004 (EPA/540/R-99/005)
	– volatile organics	--	Dermal Assessment, EPA 2004 (EPA/540/R-99/005)
	– inorganics	--	Dermal Assessment, EPA 2004 (EPA/540/R-99/005)
IRAA	Inhalation rate - adult (m ³ /day)	20	Exposure Factors, EPA 1991 (OSWER No. 9285.6-03)
IRAc	Inhalation rate - child (m ³ /day)	10	Exposure Factors, EPA 1997 (EPA/600/P-95/002Fa)
IRWa	Drinking water ingestion - adult (L/day)	2	RAGS(Part A), EPA 1989 (EPA/540/1-89/002)
IRWc	Drinking water ingestion - child (L/day)	1	PEA, Cal-EPA (DTSC, 1994)
IRSa	Soil ingestion - adult (mg/day)	100	Exposure Factors, EPA 1991 (OSWER No. 9285.6-03)
IRSc	Soil ingestion - child (mg/day)	200	Exposure Factors, EPA 1991 (OSWER No. 9285.6-03)
IRSo	Soil ingestion - occupational (mg/day)	100	Soil Screening Guidance (EPA 2001a)
EFr	Exposure frequency - residential (d/y)	350	Exposure Factors, EPA 1991 (OSWER No. 9285.6-03)
EFo	Exposure frequency - occupational (d/y)	250	Exposure Factors, EPA 1991 (OSWER No. 9285.6-03)
EDr	Exposure duration - residential (years)	30 ^a	Exposure Factors, EPA 1991 (OSWER No. 9285.6-03)
EDc	Exposure duration - child (years)	6	Exposure Factors, EPA 1991 (OSWER No. 9285.6-03)
EDo	Exposure duration - occupational (years)	25	Exposure Factors, EPA 1991 (OSWER No. 9285.6-03)
IFSadj	Age-adjusted factors for carcinogens: Ingestion factor, soils ([mg-yr]/[kg-d])	114	RAGS(Part B), EPA 1991 (OSWER No. 9285.7-01B)
SFSadj	Dermal factor, soils ([mg-yr]/[kg-d])	361	By analogy to RAGS (Part B)
InhFadj	Inhalation factor, air ([m ³ -yr]/[kg-d])	11	By analogy to RAGS (Part B)
IFWadj	Ingestion factor, water ([L-yr]/[kg-d])	1.1	By analogy to RAGS (Part B)
VFw	Volatilization factor for water (L/m ³)	0.5	RAGS(Part B), EPA 1991 (OSWER No. 9285.7-01B)
PEF	Particulate emission factor (m ³ /kg)	See below	Soil Screening Guidance (EPA 1996a,b)
VF _s	Volatilization factor for soil (m ³ /kg)	See below	Soil Screening Guidance (EPA 1996a,b)
sat	Soil saturation concentration (mg/kg)	See below	Soil Screening Guidance (EPA 1996a,b)

Footnote:

^aExposure duration for lifetime residents is assumed to be 30 years total. For carcinogens, exposures are combined for children (6 years) and adults (24 years) .

4.9 Standardized Equations

The equations used to calculate the PRGs for carcinogenic and noncarcinogenic contaminants are presented in Equations 4-1 through 4-8. The PRG equations update RAGS Part B equations. The methodology backcalculates a soil, air, or water concentration level from a target risk (for carcinogens) or hazard quotient (for noncarcinogens). For completeness, the soil equations combine risks from ingestion, skin contact, and inhalation simultaneously. **Note: the InterCalc Tables available at the EPA Region 9 PRG website also includes pathway-specific concentrations, should the user decide against combining specific exposure pathways; or, the user wants to identify the relative contribution of each pathway to exposure.**

To calculate PRGs for volatile chemicals in soil, a chemical-specific volatilization factor is calculated per Equation 4-9. Because of its reliance on Henry's law, the VF_s model is applicable only when the contaminant concentration in soil is at or below saturation (i.e. there is no free-phase contaminant present). Soil saturation ("sat") corresponds to the contaminant concentration in soil at which the adsorptive limits of the soil particles and the solubility limits of the available soil moisture have been reached. Above this point, pure liquid-phase contaminant is expected in the soil. If the PRG calculated using VF_s was greater than the calculated sat, the PRG was set equal to sat, in accordance with *Soil Screening Guidance* (USEPA 1996 a,b). The equation for deriving sat is presented in Equation 4-10.

PRG EQUATIONS

Soil Equations: For soils, equations were based on three exposure routes (ingestion, skin contact, and inhalation).

Equation 4-1: Combined Exposures to Carcinogenic Contaminants in Residential Soil

$$C \text{ (mg/kg)} = \frac{TR \times AT_c}{EF_r \left[\left(\frac{IFS_{adj} \times CSF_o}{10^6 \text{ mg/kg}} \right) \% \left(\frac{SFS_{adj} \times ABS \times CSF_o}{10^6 \text{ mg/kg}} \right) \% \left(\frac{InhF_{adj} \times CSF_i}{VF_s^a} \right) \right]}$$

Equation 4-2: Combined Exposures to Noncarcinogenic Contaminants in Residential Soil

$$C \text{ (mg/kg)} = \frac{THQ \times BW_c \times AT_n}{EF_r \times ED_c \left[\left(\frac{1}{RfD_o} \times \frac{IRS_c}{10^6 \text{ mg/kg}} \right) \% \left(\frac{1}{RfD_o} \times \frac{SA_c \times AF \times ABS}{10^6 \text{ mg/kg}} \right) \% \left(\frac{1}{RfD_i} \times \frac{IRA_c}{VF_s^a} \right) \right]}$$

Equation 4-3: Combined Exposures to Carcinogenic Contaminants in Industrial Soil

$$C \text{ (mg/kg)} = \frac{TR \times BW_a \times AT_c}{EF_o \times ED_o \left[\left(\frac{IRS_o \times CSF_o}{10^6 \text{ mg/kg}} \right) \% \left(\frac{SA_a \times AF \times ABS \times CSF_o}{10^6 \text{ mg/kg}} \right) \% \left(\frac{IRA_a \times CSF_i}{VF_s^a} \right) \right]}$$

Footnote:

^aUse VF_s for volatile chemicals (defined as having a Henry's Law Constant [atm-m³/mol] greater than 10⁻⁵ and a molecular weight less than 200 grams/mol) or PEF for non-volatile chemicals.

Equation 4-4: Combined Exposures to Noncarcinogenic Contaminants in Industrial Soil

$$C(mg/kg) = \frac{THQ \times BW_a \times AT_n}{EF_o \times ED_o \left[\left(\frac{1}{RfD_o} \times \frac{IRS_o}{10^6 mg/kg} \right) \% \left(\frac{1}{RfD_o} \times \frac{SA_a \times AF \times ABS}{10^6 mg/kg} \right) \% \left(\frac{1}{RfD_i} \times \frac{IRA_a}{VF_s^a} \right) \right]}$$

Tap Water Equations:

Equation 4-5: Ingestion and Inhalation Exposures to Carcinogenic Contaminants in Water

$$C(ug/L) = \frac{TR \times AT_c \times 1000ug/mg}{EF_r \left[(IFW_{adj} \times CSF_o) \% (VF_w \times InhF_{adj} \times CSF_i) \right]}$$

Equation 4-6: Ingestion and Inhalation Exposures to Noncarcinogenic Contaminants in Water

$$C(ug/L) = \frac{THQ \times BW_a \times AT_n \times 1000ug/mg}{EF_r \times ED_r \left[\left(\frac{IRW_a}{RfD_o} \right) \% \left(\frac{VF_w \times IRA_a}{RfD_i} \right) \right]}$$

Air Equations:

Equation 4-7: Inhalation Exposures to Carcinogenic Contaminants in Air

$$C(ug/m^3) = \frac{TR \times AT_c \times 1000ug/mg}{EF_r \times InhF_{adj} \times CSF_i}$$

Equation 4-8: Inhalation Exposures to Noncarcinogenic Contaminants in Air

$$C(ug/m^3) = \frac{THQ \times RfD_i \times BW_a \times AT_n \times 1000ug/mg}{EF_r \times ED_r \times IRA_a}$$

Footnote:

^aUse VF_s for volatile chemicals (defined as having a Henry's Law Constant [atm-m³/mol] greater than 10⁻⁵ and a molecular weight less than 200 grams/mol) or PEF for non-volatile chemicals.

SOIL-TO-AIR VOLATILIZATION FACTOR (VF_s)

Equation 4-9: Derivation of the Volatilization Factor

$$VF_s (m^3/kg) = (Q/C) \times \frac{(3.14 \times D_A \times T)^{1/2}}{(2 \times \rho_b \times D_A)} \times 10^4 (m^2/cm^2)$$

where:

$$D_A = \frac{[(\Theta_a^{10/3} D_i H) \% \Theta_w^{10/3} D_w] / n^2}{\rho_b K_d \% \Theta_w \% \Theta_a H}$$

<u>Parameter</u>	<u>Definition (units)</u>	<u>Default</u>
VF _s	Volatilization factor (m ³ /kg)	--
D _A	Apparent diffusivity (cm ² /s)	--
Q/C	Inverse of the mean conc. at the center of a 0.5-acre square source (g/ ^{M2} -s per kg/m ³)	68.81
T	Exposure interval (s)	9.5 x 10 ⁸
ρ _b	Dry soil bulk density (g/cm ³)	1.5
Θ _a	Air filled soil porosity (L _{air} /L _{soil})	0.28 or n-Θ _w
n	Total soil porosity (L _{pore} /L _{soil})	0.43 or 1 - (ρ _b /ρ _s)
Θ _w	Water-filled soil porosity (L _{water} /L _{soil})	0.15
ρ _s	Soil particle density (g/cm ³)	2.65
Di	Diffusivity in air (cm ² /s)	Chemical-specific
H	Henry's Law constant (atm-m ³ /mol)	Chemical-specific
H'	Dimensionless Henry's Law constant	Calculated from H by multiplying by 41 (USEPA 1991a)
D _w	Diffusivity in water (cm ² /s)	Chemical-specific
K _d	Soil-water partition coefficient (cm ³ /g) = K _{oc} f _{oc}	Chemical-specific
K _{oc}	Soil organic carbon-water partition coefficient (cm ³ /g)	Chemical-specific
f _{oc}	Fraction organic carbon in soil (g/g)	0.006 (0.6%)

SOIL SATURATION CONCENTRATION (sat)

Equation 4-10: Derivation of the Soil Saturation Limit

$$sat = \frac{S}{\rho_b} (K_d \rho_b \% \Theta_w \% H' \Theta_a)$$

<u>Parameter</u>	<u>Definition (units)</u>	<u>Default</u>
sat	Soil saturation concentration (mg/kg)	--
S	Solubility in water (mg/L-water)	Chemical-specific
ρ_b	Dry soil bulk density (kg/L)	1.5
n	Total soil porosity (L_{pore}/L_{soil})	0.43 or $1 - (\rho_b/\rho_s)$
ρ_s	Soil particle density (kg/L)	2.65
K_d	Soil-water partition coefficient (L/kg)	$K_{oc} \times f_{oc}$ (chemical-specific)
k_{oc}	Soil organic carbon/water partition coefficient (L/kg)	Chemical-specific
f_{oc}	Fraction organic carbon content of soil (g/g)	0.006 or site-specific
Θ_w	Water-filled soil porosity (L_{water}/L_{soil})	0.15
Θ_a	Air filled soil porosity (L_{air}/L_{soil})	0.28 or $n - \Theta_w$
w	Average soil moisture content (kg_{water}/kg_{soil} or L_{water}/kg_{soil})	0.1
H	Henry's Law constant (atm-m ³ /mol)	Chemical-specific
H'	Dimensionless Henry's Law constant	$H \times 41$, where 41 is a units conversion factor

SOIL-TO-AIR PARTICULATE EMISSION FACTOR (PEF)

Equation 4-11: Derivation of the Particulate Emission Factor

$$PEF(m^3/kg) = Q/C \times \frac{3600s/h}{0.036 \times (1+V) \times (U_m/U_t)^3 \times F(x)}$$

<u>Parameter</u>	<u>Definition (units)</u>	<u>Default</u>
PEF	Particulate emission factor (m ³ /kg)	1.316 x 10 ⁹
Q/C	Inverse of the mean concentration at the center of a 0.5-acre-square source (g/m ² -s per kg/m ³)	90.80
V	Fraction of vegetative cover (unitless)	0.5
U _m	Mean annual windspeed (m/s)	4.69
U _t	Equivalent threshold value of windspeed at 7 m (m/s)	11.32
F(x)	Function dependent on U _m /U _t derived using Cowherd (1985) (unitless)	0.194

REFERENCES

- ASTM. 1995. *Standard Guide for Risk-Based Corrective Action Applied at Petroleum Release Sites*. Designation E 1739 - 95. Philadelphia, Pennsylvania.
- Calabrese, E.J., H. Pastides, R. Barnes, et al. 1989. How much soil do young children ingest: an epidemiologic study. In: *Petroleum Contaminated Soils*, Vol. 2. E.J. Calabrese and P.T. Kostecki, eds. pp. 363-417. Chelsea, MI, Lewis Publishers.
- California EPA. 1994. *Preliminary Endangerment Assessment Guidance Manual*. (PEA) Department of Toxic Substances Control, Sacramento, California.
- California EPA. 1996. *Guidance for Ecological Risk Assessment at Hazardous Waste Sites and Permitted Facilities, Part A: Overview*. Department of Toxic Substances Control, Sacramento, California.
- Cowherd, C., G. Muleski, P. Engelhart, and D. Gillette. 1985. *Rapid Assessment of Exposure to Particulate Emission from Surface Contamination*. EPA/600/8-85/002. Prepared for Office of Health and Environmental Assessment, U.S. Environmental Protection Agency, Washington, DC. NTIS PB85-1922197AS.
- Davis, S., P. Waller, R. Buschom, J. Ballou, and P. White. 1990. Quantitative estimates of soil ingestion in normal children between the ages of 2 and 7 years: population-based estimates using Al, Si, and Ti as soil tracer elements. *Archives of Environmental Health* 45:112-122.
- Howard, P.H. 1990. *Handbook of Environmental Fate and Exposure Data for Organic Chemicals*. Lewis Publishers, Chelsea Michigan.
- U.S. EPA. 1988. *Superfund Exposure Assessment Manual*. EPA/540/1-88/001. Office of Emergency and Remedial Response, Washington, DC.
- U.S. EPA. 1990a. *Subsurface Contamination Reference Guide*. EPA/540/2-90/011. Office of Emergency and Remedial Response, Washington, DC.
- U.S. EPA 1990b. *Exposure Factors Handbook*. EPA/600/8089/043. Office of Health and Environmental Assessment, Washington, DC.
- U.S. EPA. 1991a. *Risk Assessment Guidance for Superfund Volume I: Human Health Evaluation Manual (Part B, Development of Risk-Based Preliminary Remediation Goals)*. Publication 9285.7-01B. Office of Emergency and Remedial Response, Washington, DC. NTIS PB92-963333.
- U.S. EPA. 1991b. *Human Health Evaluation Manual, Supplemental Guidance: Standard Default Exposure Factors*. Publication 9285.6-03. Office of Emergency and Remedial Response, Washington, DC. NTIS PB91-921314.
- U.S. EPA. 1992a *Technical Support Document for Land Application of Sewage Sludge; Volumes I and II*. Office of Water, Washington, DC. 822/R-93-001a,b.
- U.S. EPA. 1992b *Dermal Exposure Assessment: Principles and Applications*. EPA/600/8-91/011B. Office of Health and Environmental Assessment, Washington, DC.
- U.S. EPA 1994a. *Estimating Exposure to Dioxin-Like Compounds*. U.S. EPA Office of Research and Development, EPA/600/6-88/005B.
- U.S. EPA 1994b. *Role of Ecological Assessment in the Baseline Risk Assessment*. OSWER Directive No. 9285.7-17. Office of Solid Waste and Emergency Response, Washington, DC.
- U.S. EPA. 1996a. *Soil Screening Guidance: Technical Background Document*. EPA/540/R-95/128. Office of Emergency and Remedial Response, Washington, DC. PB96-963502.
- U.S. EPA. 1996b. *Soil Screening Guidance: User's Guide*. EPA/540/R-96/018. Office of Emergency and Remedial Response, Washington, DC. PB96-963505.

REFERENCES

- U.S. EPA 1996c. *Superfund Chemical Data Matrix*. EPA/540/R-96/028. Office of Solid Waste and Emergency Response, Washington, DC. PB94-963506.
- U.S. EPA. 1997a. *Health Effects Assessment Summary Tables (HEAST): Annual Update, FY 1997*. National Center For Environmental Assessment (NCEA), Office of Research and Development and Office of Emergency and Remedial Response, Washington, DC.
- U.S. EPA. 1997b. *Ecological Risk Assessment Guidance for Superfund: Process for Designing and Conducting Ecological Risk Assessments, Interim Final*. EPA/540/R-97/006. Office of Solid Waste and Emergency Response, Washington, DC. PB97-963211.
- U.S. EPA. 2001a. *Supplemental Guidance for Developing Soil Screening Levels for Superfund Sites, Interim Guidance*. OSWER 9355.4-24.
- U.S. EPA. 2001B. *Guidance for Characterizing Background Chemicals in Soil at Superfund Sites (Draft)* June 2001, EPA/540/R-01/003. Office of Solid Waste and Emergency Response, Washington, DC.
- U.S. EPA. 2002. *Evaluating the Vapor Intrusion to Indoor Air Pathway from Groundwater and Soils (Subsurface Vapor Intrusion Guidance)*, Draft. EPA/530/F/02/052.
- U.S. EPA. 2004. *Risk Assessment Guidance for Superfund Volume I: Human Health Evaluation Manual (Part E, Supplemental Guidance for Dermal Risk Assessment)*, Final. EPA/540/R/99/005. Office of Solid Waste and Emergency Response, Washington, DC. PB99-963312.
- Van Wijnen, J.H., P. Clausen and B. Brunekreef. 1990. Estimated soil ingestion by children. *Environmental Research*, 51:147-162.