



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 33637

LOCATION Oaklev

FOREMAN Kelly Gabbe

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-15-11	9160	Along Muir #15	19	105	55 ⁴⁰	Lincoln
CUSTOMER Wheip King Fullerton			<div> <div>Hugo</div> <div>7-NW</div> <div>Winto</div> </div>			
MAILING ADDRESS						
CITY	STATE	ZIP CODE				

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>325</u>	CASING SIZE & WEIGHT <u>8 5/8 24#</u>
CASING DEPTH <u>321'</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>14'</u>	SLURRY VOL <u>1.36</u>	WATER gal/sk <u>6.5</u>	CEMENT LEFT in CASING <u>30</u>
DISPLACEMENT <u>18 1/2</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: Safety Meeting. Rigged up on Murtin drilling rig #25. Hooked up to circulate. Mixed 265 SKS Com 3%OCC 2%gel. Released Plug and displaced with 18 1/2 bbl H₂O. Shut in. Washed out pumps and lines. Rigged down and left location.

Circulated approx 500 to Pitt

Cement did circulate

Thank You
Kelly & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	1025 ⁰⁰	1025 ⁰⁰
5406	100	MILEAGE	5 ⁰⁰	500 ⁰⁰
5407A	12.46	Ton Mileage delivery	158	1969 ⁰⁰
11045	265 sks	Class A Cement	1680	4452 ⁰⁰
1102	747 #	calcium chloride	84	62748
1188	498 #	Bentonite	24	11953
4432	1	8 5/8 Wooden Plug	96 ⁰⁰	96 ⁰⁰
				8789 ⁰⁰
			Less 10% disc.	8789 ⁰⁰
				7910 ¹⁰
			SALES TAX	371.71
			ESTIMATED TOTAL	8281.81

Ravin 3737

0 PM
AUTHORIZATION Danny Smith

TITLE Cc Rep

DATE 10/15/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.