

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400229066

PluggingBond SuretyID

20030110

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: WHITING OIL AND GAS CORPORATION

4. COGCC Operator Number: 96155

5. Address: 1700 BROADWAY STE 2300

City: DENVER State: CO Zip: 80290

6. Contact Name: Michael Brown Phone: (307)237-9310 Fax: ()

Email: ml_brown@bresnan.net

7. Well Name: Twomile Well Number: 15-1033H

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 12341

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 15 Twp: 11N Rng: 57W Meridian: 6

Latitude: 40.920428 Longitude: -103.734511

Footage at Surface: 422 feet FNL/FSL 1997 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4912 13. County: WELD

14. GPS Data:

Date of Measurement: 07/05/2011 PDOP Reading: 1.9 Instrument Operator's Name: Jerremy Harris

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
957 FSL 1980 FEL 1980 FSL 1980 FEL
Sec: 15 Twp: 11N Rng: 57W Sec: 10 Twp: 11N Rng: 57W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 333 ft

18. Distance to nearest property line: 422 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1620 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-60	960	SEC 15, S/2 10

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

All of Section 15 & S/2 of Section 10, T11N-R57W

25. Distance to Nearest Mineral Lease Line: 422 ft

26. Total Acres in Lease: 960

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26			0	60			
SURF	13+1/2	9+5/8	36.0	0	1,000	449	1,000	0
1ST	8+3/4	7	29.0	0	5,985	425	5,985	0
2ND	6	4+1/2	11.6	0	12,341			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments _____

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Michael L. Brown

Title: Agent

Date: 12/5/2011

Email: ml_brown@bresnan.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline

Director of COGCC

Date: 12/29/2011

API NUMBER

05 123 34877 00

Permit Number: _____ Expiration Date: 12/28/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us .
- 2) Provide cement coverage from base of intermediate casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400229066	FORM 2 SUBMITTED
400229085	WELL LOCATION PLAT
400229086	TOPO MAP
400229090	DEVIATED DRILLING PLAN
400229091	DRILLING PLAN
400229227	SURFACE AGRMT/SURETY

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comment received; final review completed.	12/28/2011 11:42:37 AM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with oil and gas development throughout the State of Colorado. BMPs will be constructed as necessary to prevent stormwater from leaving the construction site. BMPs used will vary according to the location, and will remain until the pad is reclaimed.
Material Handling and Spill Prevention	<p>Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with oil and gas operations throughout the State of Colorado.</p> <ul style="list-style-type: none"> • Materials and fluids will be stored in a neat and orderly fashion. • Waste will be collected regularly and disposed of at an offsite facility. • Prompt cleanup is required of spills to minimize waste materials entering the stormwater runoff. • Drip pans will be used during fueling and maintenance to contain spills or leaks. • Cleanup of trash and discarded material will be done at the end of the work day. • Cleanup will consist of monitoring the road, location and any other work areas. • Material to be cleaned up includes trash, scrap, and contaminated soil.

Total: 2 comment(s)