

FORM  
2Rev  
12/05State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400237441

PluggingBond SuretyID

20090078

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐Refiling ☐Sidetrack ☐

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Liz Lindow Phone: (303)831-3974 Fax: ()  
Email: llindow@petd.com

7. Well Name: Leffler Well Number: 24-1H

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 11850

## WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 1 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.510700 Longitude: -104.733740

Footage at Surface: 190 feet FNL/FSL FSL 323 feet FEL/FWL FWL

11. Field Name: Eaton Field Number: 19350

12. Ground Elevation: 4816 13. County: WELD

## 14. GPS Data:

Date of Measurement: 06/15/2011 PDOP Reading: 1.7 Instrument Operator's Name: 4816

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
809 FSL 763 FWL 500 FNL 2520 FWL  
Sec: 1 Twp: 6N Rng: 66W Sec: 1 Twp: 6N Rng: 66W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 180 ft

18. Distance to nearest property line: 191 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1246 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	407-87	320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

W2 of Section 1 T6N R66W 6th PM

25. Distance to Nearest Mineral Lease Line: 500 ft

26. Total Acres in Lease: 320

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: closed loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	875	730	875	0
1ST	8+3/4	7	26	0	7,527	650	7,526	600
1ST LINER	6+1/8	4+1/2	11.6	6331	11,850			

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. Operator requests approval of an exception location per rule 318Aa - well will not be drilled in a legal drilling window but will be twinned with the Leffler 24-1H to be drilled on this pad. Waivers are attached. Operator requests approval of the proposed spacing unit consisting of the SW, W2NE, and E2NW of Section 1 T6N R66W per rule 318Ae. Proposed spacing unit map is attached. Rig height is 118'.

34. Location ID: 425284

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Liz Lindow

Title: Permit Representative Date: \_\_\_\_\_ Email: llindow@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### Attachment Check List

Att Doc Num	Name
400237483	30 DAY NOTICE LETTER
400237484	EXCEPTION LOC REQUEST
400237485	EXCEPTION LOC WAIVERS
400237486	WELL LOCATION PLAT
400237490	DEVIATED DRILLING PLAN
400237499	PROPOSED SPACING UNIT

Total Attach: 6 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)