



02055380

Andrews, David

From: GJRig01@oxy.com
Sent: Monday, January 02, 2012 6:09 AM
To: Andrews, David
Cc: Simon_Benevides@oxy.com
Subject: RE: OXY / H&P 330 / 697-04D PAD / CC 697-04-74A/ SURFACE CEMENT SUMMARY

There was some incorrect data on the previous summary. Please see the changes in the summary below in red.

WELL : CC 697-04-74A
API : 050452071800
CASING DEPTH : 2679'

RIGGED DOWN CASING RUNNING TOOL AND LAID DOWN SAME. RELEASED RIG TO CC 697-04-74A AT 11:30 HOURS.

09:30 HOURS (1-1-2012) - 12:13 HOURS (1-1-2012) HALLIBURTON PERFORMED CEMENT JOB OFF LINE AS FOLLOWS: TESTED LINES TO 2500 PSI. GOOD TEST CEMENTED 9.625" 36LLB/FT J-55 LTC CASING AS FOLLOWS: PUMPED 20 BBLS FRESH WATER; 20 BBLS OF GEL SPACER; 20 BBLS OF FRESH WATER. CEMENTED 9.625" SURFACE CASING WITH: 1070 SACKS OF LEAD - 444 BBLS OF 12.3 PPG - 2.33 CU. FT/SK VERSACEM LEAD AT 6 BPM 170 SACKS OF TAIL - 62.7 BBLS OF 12.8 PPG - 2.07 CU. FT/SK VERSACEM TAIL AT 6 BPM. 50% EXCESS ON LEAD AND 60% EXCESS ON TAIL. HAD PARTIAL RETURNS THROUGHOUT CEMENT JOB DROPPED PLUG AND DISPLACED WITH 201 BBLS FRESH WATER AT 6 BPM OBSERVED 404 PSI LIFT PRESSURE AT 6 BPM SLOWED RATE TO 2 BPM AT 190 BBLS INTO DISPLACEMENT AND OBSERVED 390 PSI LIFT PRESSURE. BUMPED PLUG WITH 930 PSI. PLUG DOWN AT 11:33 HOURS (1/1/2012). HELD FOR FIVE MINUTES. BLED PRESSURE TO ZERO AND CHECKED FLOATS. FLOATS HELD. HAD PARTIAL RETURNS WHILE PUMPING DISPLACEMENT TESTED CASING TO 1500 PSI HELD FOR 30 MINUTES. TEST PASSED. FLUSHED PARASITE LINE WITH 10 BBLS SUGAR WATER - HAD RETURNS AFTER 6 BBLS.

ESTIMATED TOC AT: 780'.

14:04 HOURS - 19:15 HOURS (1/1/2011) HOURS - PERFORMED TOP OUT WITH 120 SACKS - 42 BBLS OF 12.5 PPG TOP OUT BLEND CEMENT.
5 BBLS CEMENT RETURNED TO SURFACE.

Thanks & Regards

Jeff Gill / Derek Adam
DSM
H&P 330
281-436-6424

DSM
H&P 330
281-436-6424