



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600064

Date 10-4-11	Well Owner Kerr McGee	Well No. 2-7	Lease WETHINGTON
County WELD	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700 (XTREME #11)			
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	FL	908
Surface	8 5/8" CSG-24H	Bottom of Surface	FL 903
Plug	Plug Landed @ 857	FL	Time On 1600
Production	Pipe Landed @ 903	FL	Plug Down 2100

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	570	SKS		
POZ. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	210	Miles		
Fuel Surcharge	210	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	2004	2012	
Disp. Rate 5 BPM	Mixing	2012	2046	
Slurry Vol. 1.32 Cu.Ft./Sk	Change Valves	2046	2049	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	2049	2100	
Water/Cement 6.25 Gal/SK				2045474
Water Temp. 66°F				
Total Slurry Vol. 134.0	BBLS Cement			80012090 D219
Landed Plug @ 800	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 54.5	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		70			
1217/1218		Bulk Truck		70/70			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, JOSH, EVAN, ERNIE**

Received By **[Signature]**
Customer or His Agent