



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600146

Date <u>9/26/2011</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>27-7</u>	Lease <u>LYETHINGTON</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (XTREME #11)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	
Surface <u>8 5/8" CSG 24"</u>	Bottom of Surface	Fl. <u>906</u>	
Plug	Plug Landed @ <u>816.2</u>	Fl.	Time On <u>1800</u>
Production	Pipe Landed @ <u>906</u>	Fl.	Plug Down <u>2045</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>570</u>	SKS		
Poz. Mix <u>2045472</u>				
Calcium Chloride <u>80012 090</u>	2.5	%		
Get % Flo-Crete 1/4 # Per Sack				
Mileage Charge	<u>210</u>	Miles		
Fuel Surcharge	<u>210</u>	MILES		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>1953</u>	<u>1959</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>1955</u>	<u>2032</u>	
Slurry Vol. <u>1.32 Cu. Ft./Sk.</u>	Change Valves	<u>2032</u>	<u>2035</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>2035</u>	<u>2045</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>61</u>				
Total Slurry Vol. <u>134</u>	BBLS Cement			
Landed Plug @ <u>1200</u>	PSI/Final Lift @ <u>480</u>	PSI		
Pre-Flush Wt. <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace Wt. <u>54.8</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>70</u>			
<u>1217/1218</u>		Bulk Truck		<u>70/70</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/Adam/Chris

Received By Tom Bower
Customer or His Agent