

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400229858

PluggingBond SuretyID

20010023

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: K P KAUFFMAN COMPANY INC

4. COGCC Operator Number: 46290

5. Address: 1675 BROADWAY, STE 2800

City: DENVER State: CO Zip: 80202

6. Contact Name: Susana Lara-Mesa Phone: (303)825-4822 Fax: (303)825-4825

Email: slaramesa@kpk.com

7. Well Name: Pope Well Number: 3-17-21R

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8086

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 17 Twp: 4N Rng: 66W Meridian: 6

Latitude: 40.317260 Longitude: -104.803780

Footage at Surface: 669 feet FNL 2083 feet FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4705 13. County: WELD

14. GPS Data:

Date of Measurement: 03/29/2007 PDOP Reading: 6.0 Instrument Operator's Name: Kipper Goldsberry

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
1320 FNL 2480 FWL 1320 FNL 2480 FWL  
Sec: 17 Twp: 4N Rng: 66W Sec: 17 Twp: 4N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 589 ft

18. Distance to nearest property line: 595 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 830 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J SAND	JSND	GWA	320	N/2
NIOBRARA-CODELL	NB-CD	407-87	160	E/2NW4 & W/2NE4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

N/2NW/4 SECTION 17-T4N-R66W

25. Distance to Nearest Mineral Lease Line: 180 ft

26. Total Acres in Lease: 80

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	700	500	700	0
1ST	7+7/8	4+1/2	11.5	0	8,086	750	8,086	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED, CONSULTATION WITH SURFACE PRIOR TO 12-01-2011. FORMERLY POPE #3-17-21, OFFSETS LEWIS #2-20.

34. Location ID: 336643

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Susana Lara-Mesa

Title: Engineering Project Mgr Date: 12/8/2011 Email: slaramesa@kpk.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 1/6/2012

#### API NUMBER

05 123 26256 00

Permit Number: \_\_\_\_\_ Expiration Date: 1/5/2014

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Requires water sampling. Opr notified. Corrected top of production & notified opr. Ready to pass pending public comment 1/2/12.

- 1)Provide 24 hour notice of MIRU to Mike Hickey via e-mail at mike.hickey@state.co.us.
- 2)Comply with Rule 317.i and provide cement coverage from the end of the production casing to a minimum of 200' above the Niobrara and from 200' below Shannon to 200' above Shannon. Verify coverage with a cement bond log.
- 3)Comply with Rule 321. Run and submit Directional Survey from the end of production casing to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name
2481344	SURFACE CASING CHECK
400229858	FORM 2 SUBMITTED
400229862	30 DAY NOTICE LETTER
400229864	TOPO MAP

Total Attach: 4 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Final review compelte.	12/30/2011 1:36:06 PM
Permit	Operator corrected plugging bond. This form has passed completeness.	12/12/2011 10:17:14 AM
Permit	Returned to draft. Invalid plugging bond.	12/9/2011 7:37:42 AM

Total: 3 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)