



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600077

Date <u>9/30/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>6-7</u>	Lease <u>Wethington</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to:	<u>Kerr McGee Oil & Gas Onshore, LP</u>		
Address	<u>1999 Broadway, Suite 3700 (Xtreme #11)</u>		
City, State Zip	<u>Denver, Colorado 80202</u>		
Type of Job	Depth	Fl.	
(Surface) <u>8 5/8" CSG-24"</u>	Bottom of Surface	Fl. <u>914</u>	
Plug	Plug Landed @ <u>865</u>	Fl. Time On <u>2310</u>	
Production	Pipe Landed @ <u>904</u>	Fl. Plug Down <u>0100</u>	
Description	Qty.	Meas.	Unit Price
Set Up Charge	1		
Cement Neat <u>✓ Type III</u>	570	SKS	
Proz. Mix			
Calcium Chloride	2.5	%	
Gel % Flo-Cete 1/4 # Per Sack			
Mileage Charge	210	Miles	
Fuel Surcharge	210	Miles	
Additional Cement		SKS	
Mixing Rate	4 BPM	Pre-Flush	0015-0021
Disp. Rate	5 BPM	Mixing	0021-0046
Slurry Vol.	1.32 ³ Cu-FL/Sk	Change Valves	0046-0049
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0049-0100
Water/Cement	6.25 Gal/SK		
Water Temp.	105°F		
Total Slurry Vol.	134	BBLs Cement	
Landed Plug @	450	PSI/Final Lift @ 200	PSI
Pre-Flush W/ 30	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/ 54.6	BBLs H ₂ O	State CO 2.9%	Tax
Circulate 5	BBLs Cement		Total
Truck No.	Code	State Mileage	Nebraska
1208		Pump Truck	70
1214/1216		Bulk Truck	70/70

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Kerry Demetrio

Received By [Signature]
Customer or His Agent