



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600034

WETTINGTON

Date	9-18-11	Well Owner	Kerr McGee	Well No.	41-7	Lease	FEDERAL
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	906		
Surface	8 5/8" CSG-24#	Bottom of Surface		Ft.	896		
Plug		Plug Landed @	851	Ft.	Time On	2245	
Production		Pipe Landed @	896	Ft.	Plug Down	0230	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III 20454730RL	570	SKS		
Poz. Mix				
Calcium Chloride 500 12090	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	210	Miles		
Fuel Surcharge	210	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	0137	0142	
Disp. Rate 5 BPM	Mixing	0142	0216	
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	0216	0219	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0219	0230	
Water/Cement 6.25 Gal/SK				
Water Temp. 58°F				
Total Slurry Vol. 134.0	BBS Cement			
Landed Plug @ 800	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 20	BBS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ 54.1	BBS H <sub>2</sub> O	State CO 2.9%	Tax	
Circulate 5	BBS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		70			
1207/1217		Bulk Truck		70/70			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By TOM BOWER  
Customer or His Agent