

FORM 5A

Rev 02/08

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

COMPLETED INTERVAL REPORT

Document Number: 2285997

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 8960
2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY
3. Address: P O BOX 21974
City: BAKERSFIELD State: CA Zip: 93390
4. Contact Name: KERRY MCCOWEN
Phone: (720) 440-6100
Fax: (720) 279-2331

5. API Number 05-123-34044-00
6. County: WELD
7. Well Name: Antelope
Well Number: 12-20
8. Location: QtrQtr: NWNW Section: 20 Township: 5N Range: 62W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA-CODELL Status: PRODUCING

Treatment Date: 10/01/2011 Date of First Production this formation: 10/21/2011

Perforations Top: 6484 Bottom: 6747 No. Holes: 80 Hole size: 40/100

Provide a brief summary of the formation treatment: Open Hole: []

CODL PUMPED 32,508 GAL PAD FLUID AND 109,982 GAL PHASERFRAC W/251,200 LBS 30/50 SAND. ISDP 3151 PSI; ATP 3787 PSI; ATR 22.5 BPM. NBRR PUMPED 19,656 GAL PAD FLUID AND 120,414 GAL PHASERFRAC W/263,200 LBS 30/50 SAND. ISDP 3075 PSI; ATP 3721 PSI; ATR 50 BPM.

This formation is commingled with another formation: [] Yes [X] No

Test Information:

Date: 10/26/2011 Hours: 24 Bbls oil: 19 Mcf Gas: 59 Bbls H2O: 0

Calculated 24 hour rate: Bbls oil: 19 Mcf Gas: 59 Bbls H2O: 0 GOR: 3105

Test Method: FLOWING Casing PSI: 511 Tubing PSI: Choke Size: 18/64

Gas Disposition: SOLD Gas Type: WET BTU Gas: 1283 API Gravity Oil: 39

Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: [] Yes [] No If yes, number of sacks cmt

Bridge Plug Depth: Sacks cement on top:

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: KERRY A. MCCOWEN

Title: VP OPERATIONS Date: 11/11/2011 Email: KAM@BONANZACRK.COM

Attachment Check List

Att Doc Num	Name
2285997	FORM 5A SUBMITTED
2285998	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)