



# CEMENTER'S-WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600134

Date <u>8/21/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>23-29</u>	Lease <u>HOWARD</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700</u>	<u>(XTREME # 15)</u>		
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>1215</u>	
Surface <u>8 5/8" CSG 24"</u>	Bottom of Surface	Ft. <u>1208</u>	
Plug	Plug Landed @ <u>1164</u>	Ft. Time On <u>1000</u>	
Production	Pipe Landed @ <u>1208</u>	Ft. Plug-Down <u>1615</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>760</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	<u>204</u>	Miles		
Fuel Surcharge	<u>204</u>	miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	<u>1511</u>	<u>1524</u>	
Disp. Rate 5 BPM	Mixing	<u>1524</u>	<u>1557</u>	
Slurry Vol. 1.32 <sup>3</sup> Cu. Ft./Sk	Change Valves	<u>1557</u>	<u>1600</u>	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	<u>1600</u>	<u>1615</u>	<u>205 7796. DRI</u>
Water/Cement 6.25 Gal/SK				
Water Temp. <u>62</u>			<u>800</u>	<u>12090</u>
Total Slurry Vol. <u>178.6</u>	BBLs Cement			
Landed Plug @ <u>850</u>	PSI/Final Lift @ <u>300</u>	PSI		
Pre-Flush W/ <u>40</u>	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ <u>74</u>	BBLs H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax	
Circulate <u>3</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>68</u>			
<u>1217/1218</u>		Bulk Truck		<u>68/68</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/ADAM/STEW/CHRIS

Received By Rusty Tucker  
Customer or His Agent