

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



| | | | |
|-----------------------------------|----|----|----|
| DE | ET | OE | ES |
| Document Number: 400239369 | | | |
| PluggingBond SuretyID 20100017 | | | |

APPLICATION FOR PERMIT TO:

1. ☐ Drill, ☐ Deepen, ☐ Re-enter, ☒ **Recomplete and Operate**

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☒
Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC 4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700
City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JENNIFER LIND Phone: (720)876-5890 Fax: (720)876-6890
Email: JENNIFER.LIND@ENCANA.COM

7. Well Name: SEGAL Well Number: 41-24

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7860

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 24 Twp: 4N Rng: 66W Meridian: 6
Latitude: 40.303971 Longitude: -104.717467

Footage at Surface: 510 feet FNL/FSL 593 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4726 13. County: WELD

14. GPS Data:

Date of Measurement: 09/18/2007 PDOP Reading: 1.4 Instrument Operator's Name: DALLAS NIELSEN

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 510 ft

18. Distance to nearest property line: 510 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 890 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| NIOBRARA | NBRR | 407 | 320 | N/2 |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T4N-R66W-SEC.24: N/2

25. Distance to Nearest Mineral Lease Line: 510 ft

26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|------------|---------------|---------------|-----------|---------|---------|
| SURF | 12+1/4 | 8+5/8 | 24 | 0 | 535 | 280 | 535 | 0 |
| 1ST | 7+7/8 | 4+1/2 | 11.6 | 0 | 7,850 | 300 | 7,850 | 6,094 |
| | | | Stage Tool | | 4,852 | 280 | 4,852 | 3,618 |

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments RECOMPLETION OF THE SEGAL 41-24. THIS RECOMPLETION DOES NOT REQUIRE A FORM 2A ASNO PITS WILL BE CONSTRUCTED AND THERE WILL BE NO ADDITIONAL SURFACE DISTURBANCE OUTSIDE OF THE ORIGINALLY DISTURBED AREA.

34. Location ID: 310576

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: 1/10/2012 Email: JENNIFER.LIND@ENCANA.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05 123 26616 00

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

| Att Doc Num | Name |
|-------------|------------------|
| 400239369 | FORM 2 SUBMITTED |

Total Attach: 1 Files

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|-------------------|----------------|---------------------|
| | | |

Total: 0 comment(s)

BMP

| <u>Type</u> | <u>Comment</u> |
|-------------|----------------|
| | |

Total: 0 comment(s)